


GEOLOGIC AND GEOTECHNICAL INVESTIGATION

1925 EL CAMINO DE LA LUZ
SANTA BARBARA, CALIFORNIA


Prepared for:
1729 Calle Boca Del Canon
Santa Barbara, California 93110-2320

OCTOBER 2012



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

330 Village Lane • Los Gatos, California 95030 • (408) 354-5542 Fax (408) 354-1852
6417 Dogtown Road • San Andreas, California 95249 • (209) 736-4252 Fax (209) 736-1212
550 St. Charles Drive Ste. 108 • Thousand Oaks, California 91360 • (805) 497-7999 Fax (805) 497-7933



GEOLOGIC AND GEOTECHNICAL INVESTIGATION
1925 El Camino De La Luz
Santa Barbara, California

For:


Emprise Trust
1925 El Camino De La Luz
Santa Barbara, California 93109

by

COTTON, SHIRES AND ASSOCIATES, INC.

330 Village Lane
Los Gatos, California 95030

October 2012



October 8, 2012
G0058

Emprise Trust
1925 El Camino De La Luz
Santa Barbara, California 93109

SUBJECT: **Geologic and Geotechnical Investigation**
RE: 1925 El Camino De La Luz
 (Proposed Single-Family Residence - APN 045-100-024)
 Santa Barbara, California

Dear Representatives of the Emprise Trust:

Cotton, Shires and Associates, Inc. (CSA) is pleased to provide Emprise Trust with the following report wherein we describe the findings, conclusions and recommendations of our geologic and geotechnical investigation of the parcel at 1925 El Camino De La Luz (APN 045-100-024, 'the parcel'), Santa Barbara ('the City'), California. It is our understanding that the trust is proposing to develop the parcel with a single-family residence and appurtenant structures. The parcel was previously developed (between 1956 and 1978) with a split-level single-family residence, and is currently (2012) partially developed in conjunction with El Camino De La Luz by a private driveway that jointly serves the parcels at 1925 and 1927 El Camino De La Luz, the City's Mesa Sewer Trunk Line and areas that were graded by the City in 1978, and graded by the neighboring property owner at 1933-1937 El Camino De La Luz.

In the following report, we provide the results of our geotechnical surface and subsurface exploration, monitoring, and slope stability analyses relating to the currently proposed development of the parcel. Included in this report are an engineering geologic characterization and assessment of the site conditions, drainage, and slope stability, and geotechnical design recommendations for residential construction. For clarity, we have provided an Executive Summary at the front of the report to summarize our pertinent conclusions and recommendations.

We appreciate the opportunity to be of service to you on this project. If you have any questions regarding this report, please contact our office.

Very truly yours,

COTTON, SHIRES AND ASSOCIATES, INC.

John M. Wallace
Principal Engineering Geologist
CEG 1923

Patrick O. Shires
Senior Principal Geotechnical Engineer
GE 770

JMW:POS:st

GEOLOGIC AND GEOTECHNICAL INVESTIGATION
1925 El Camino De La Luz
Santa Barbara, California

Table of Contents

	Page
EXECUTIVE SUMMARY	
Conclusions	1
Recommendations	4
 TECHNICAL REPORT	
1.0 INTRODUCTION	7
1.1 Proposed Development	7
1.2 Background	7
1.3 Purpose and Scope of Work.....	9
 2.0 PHYSICAL SETTING	 12
2.1 Topography	12
2.1.1 Terrain.....	12
2.1.2 Top of Bluff.....	13
2.1.3 Bluff Retreat	14
2.2 Geologic Setting.....	15
2.3 Seismic Setting	16
2.3.1 Deterministic Seismic Analysis	17
 3.0 SITE CONDITIONS	 19
3.1 Surface Conditions	19
3.1.1 Aerial Photograph Analysis.....	20
3.1.2 1978 Landslide	21
3.2 Local Geology	23
3.3 Earth Materials.....	24
3.3.1 Beach Deposits.....	24
3.3.2 Landslide Debris.....	24
3.3.3 Non-Marine Terrace Deposits	25
3.3.4 Monterey Formation Bedrock.....	25
3.4 Subsurface Conditions.....	26

3.4.1	Small-Diameter Borehole Exploration.....	26
3.4.2	Instrumentation	27
3.4.3	Large-Diameter Borehole Exploration	28
3.5	Groundwater Conditions	30
3.6	Summary of Findings.....	30
4.0	SLOPE STABILITY ANALYSIS	32
4.1	Representative Cross Section Analyzed.....	32
4.2	Analysis Procedure	32
4.3	Software and Methodology	33
4.4	Analysis Input Parameters.....	33
4.5	Analysis Results.....	37
5.0	CONCLUSIONS REGARDING GEOLOGIC CONSTRAINTS AND GEOTECHNICAL FEASIBILITY OF RESIDENTIAL CONSTRUCTION ..	42
5.1	Potential Geologic Hazards	43
5.1.1	Landsliding	44
5.1.2	Reactivation of 1978 Landslide.....	45
5.1.3	Seismic Ground Shaking	45
5.1.4	Expansive Earth Materials	45
5.1.5	Tsunami Hazards	46
6.0	GEOTECHNICAL DESIGN RECOMMENDATIONS	47
6.1	Foundation Design Considerations	47
6.2	Foundation Design Criteria	47
6.2.1	Cast-in-Place Drilled Piers	47
6.2.2	Shear Pins	48
6.2.3	Tiebacks	49
6.3	Mat Floor Foundation.....	49
6.4	Site Grading.....	49
6.4.1	Site Preparation	50
6.4.2	Compacted Fill.....	50
6.4.3	Utility Trench Backfill.....	50
6.4.4	Cut Slope Design	50
6.5	Retaining Wall Design.....	50
6.5.1	Retaining Walls.....	51

6.5.2	Backdrain.....	51
6.6	Slabs-on-Grade and Concrete Flatwork.....	51
6.7	Drainage	52
6.7.1	Sub-Floor Mat/Slab Subdrains.....	52
6.8	Seismic Design.....	53
6.9	Horizontal Drains.....	54
7.0	INVESTIGATION LIMITATIONS.....	55
8.0	REFERENCES.....	56
8.1	Documents/Maps.....	54
8.2	Vertical Aerial Photographs	57
8.3	Oblique Aerial Photographs.....	58

APPENDICES

A	Field Investigation	A-1
B	Laboratory Testing.....	B-1
C	Instrumentation.....	C-1
D	Slope Stability Analysis Output Files.....	D-1

FIGURES

		Follows Page
1	Site Location Map	7
2	Topographic Profile A-A'	13
3	Regional Geologic Map	15
4	Regional Fault Map	16
5	Engineering Geologic Map (Reduced Scale).....	19
6	Engineering Geologic Cross Section A-A' (Reduced Scale).....	19
7	Conceptual Slope Stabilization Plan	47
8	Conceptual Slope Stabilization Cross Section A-A'	47
9	Anistropic Strength Function for Bedding Inclination.....	on p. 36
10	Sign Convention for Anisotropic Strength Function	on p. 37

TABLES

Table 1	Deterministic Seismic Analysis.....	17
Table 2	Slope Stability Earth Material Properties	37
Table 3	Slope Stability Analysis Results.....	38

PLATES (In Pocket at Back of Report)

- 1 Engineering Geologic Map
- 2 Engineering Geologic Cross Section 2-2'

APPENDIX FIGURES

Follows Page

APPENDIX A:

Log of Small-Diameter Exploratory Boring CSA/SD-1.....	A-1
Log of Small-Diameter Exploratory Boring CSA/SD-2.....	SD-1
Log of Small-Diameter Exploratory Boring CSA/SD-3.....	SD-2
Log of Small-Diameter Exploratory Boring CSA/SD-4.....	SD-3
Log of Small-Diameter Exploratory Boring CSA/SD-5.....	SD-4
Log of Large-Diameter Exploratory Boring CSA/LD-1	SD-5
Log of Large-Diameter Exploratory Boring CSA/LD-2	LD-1
Log of Small-Diameter Exploratory Boring CSA/LD-3	LD-2
Photographs of Small-Diameter Core	On Disc

APPENDIX B:

Table B-1, Summary of Laboratory Test Results	B-1
Figure B-2, Summary of Atterberg Limits Testing.....	"
Figure B-3, Summary of TXCU Compression Strength Tests	"
Figure B-4, Summary of Remolded Ring Shear Tests.....	"


APPENDIX C:

Inclinometer CSA/SI-1	B-1
Inclinometer CSA/SI-2.....	"
Inclinometer CSA/SI-3.....	"
Piezometer CSA/SI-1	"
Piezometer CSA/SI-2	"
Piezometer CSA/SI-3	"

APPENDIX D:

Slope Stability Analysis Output Files.....	D-1
--	-----

EXECUTIVE SUMMARY



EXECUTIVE SUMMARY

This Executive Summary provides a summary of the pertinent conclusions and recommendations resulting from Cotton, Shires and Associates, Inc. (CSA)'s geologic and geotechnical investigation of the parcel at 1925 El Camino De La Luz in Santa Barbara, California. The parcel extends between the Mean High Tide Line on the beach (at elevation +4.63 feet MLLW)¹ and the centerline of El Camino De La Luz (at elevation +140 feet). It is our opinion that development of a single-family residence and appurtenant structures is feasible within the proposed development envelope on the parcel provided that the recommendations of this report are incorporated into the design, construction, and operation of the project during its 75-year economic life.

The potential hazards present at the parcel include static and seismic slope instability, long-term toe and top of bluff retreat, wave run-up, saturation of the weathered Monterey Formation strata, surficial soil creep, and expansive surficial earth materials. CSA analyzed the geotechnical parameters of the site and the static and seismic stability of a representative cross section through the central portion of the parcel. The long-term (1950 through 2010) position of the distinct coastal bluff at the parcel was evaluated by Joseph Scepan Geoscience Consultant (September, 2012), and wave run-up and coastal hazards were evaluated by David Skelly of GeoSoils, Inc. (July, 2012). A detailed discussion of our findings, conclusions and recommendations is presented in the technical report that follows this Executive Summary.

Conclusions

- 1) The proposed building envelope for the single-family residence and appurtenant structures is located on the south-facing, moderately steep, previously graded and landslide-impacted West Mesa hillside, between elevation 86 feet and elevation 140 feet¹. Subgrade landform stabilization and residential foundation elements are proposed to extend to approximately 40 to 50 feet below existing grade. No shoreline protective structure is proposed.
- 2) The pronounced top of coastal bluff is located near elevation 48 to elevation 50 feet, approximately 150 to 160 feet downslope of the southern limit of the proposed building envelope. The coastal bluff face is characterized by a

¹ All elevations in this report are in feet above Mean Lower Low Water (MLLW), unless otherwise indicated.

precipitously (50- to 75-degree inclinations) steep slope that extends down to the toe of the bluff at the rear of the persistent cobble-sand beach near elevation 10 feet. The parcel contains no elevated marine terrace or “upper riser” coastal bluff.

- 3) The proposed development envelope consists of previously graded landslide debris (maximum of 12 feet thick, at the downslope side of the building envelope at elevation 90 ± 5 feet), in-place Monterey Formation bedrock for the majority of the building envelope, and shallow terrace deposits/fill (up to 8 feet thick, at elevation 126 feet to elevation 140 feet). The Tertiary marine sedimentary bedrock materials of the Monterey Formation are characterized by thin-bedded siliceous and calcareous shale with interbedded mudstone. This rock formation is striking (oriented) nearly east-west, and is dipping moderately (generally 20- to 35-degree inclinations) to the south/southwest. The orientation of the Monterey Formation bedrock results in a dip-slope condition with stratigraphic units daylighting in the coastal bluff. The parcel (and eight adjacent parcels to the west and east) experienced reactivated landsliding in 1978, characterized by a deep-seated translational landslide that affected the parcel below elevation 130 feet. The recommended pier and grade beam residential foundation within the proposed development envelope is to be located in intact Monterey Formation bedrock. Shear pins with tiebacks are proposed to increase the slope stability of the building envelope to industry acceptable standards (i.e., factors of safety of 1.5 for static and 1.1 for seismic conditions).
- 4) CSA’s field investigation (2008-2011) included detailed topographic surveying, engineering geologic mapping, small- and large-diameter borehole exploration, piezometer and inclinometer installation and monitoring to facilitate construction of a representative engineering geologic cross section through the parcel.
- 5) Groundwater levels at the parcel are being monitored using multi-staged vibrating wire piezometers. Using these instruments, we have documented groundwater levels that have fluctuated little over the monitoring period (May 2011 to January 2012), with groundwater depths ranging from 22 to 35 feet below the ground surface.
- 6) The parcel will likely be subjected to strong, and perhaps violent, seismic ground shaking within the 75-year economic life of the development. The maximum

earthquake events on nearby active faults, such as the Mission Ridge-Arroyo Parida, Santa Ynez, offshore North Channel Slope, Red Mountain, and Oakridge faults, could result in peak ground accelerations at the subject property of up to 0.51g. Based on a probabilistic analysis with an exceedance probability of 10% in 50 years, a peak ground acceleration of 0.44g was determined.

- 7) No known active or potentially active faults have been mapped across the parcel, and no evidence of faulting was identified at it.
- 8) The persistent (1850's to 2011) orientation and position of the coastal bluff along the south portion of the parcel is primarily controlled by coastal processes within this subarea of the semi-sheltered Santa Barbara Channel, but has been intermittently impacted by landsliding (in 1978) as described herein. Annualized long-term coastal bluff retreat rates for the Mesa sub-region of the Santa Barbara coastline vary, but have previously been identified to be approximately 4 inches per year (Fisher, 2001), 7.7 inches per year (Norris, 1968), up to 10 inches per year (City of Santa Barbara General Plan, Seismic Safety Element, 1979), and, on a generalized City-wide basis, 12 inches per year during the planning horizon of the recently updated General Plan (City of Santa Barbara, 2011). Historic, long-term (60 year) coastal bluff retreat along this parcel has been analyzed on the basis of aerial photographic imagery between 1950 and 2010 to be at an average annualized rate of 0.8-1.4 inches/year along the toe of the coastal bluff, while as a result of the 1978 landslide and subsequent marine, atmospheric, and anthropogenic processes, the top of the coastal bluff in 2010 is 10.5-33.0 feet further to seaward (south) than it was in 1950 (Scepan, September, 2012).
- 9) The southerly edge of the proposed residence is located at elevation 92 feet, 150-160 feet upslope of the prominent top of coastal bluff, and thus, 90 to 100 feet landward of the projected coastal bluff retreat range during the 75-year economic life of the residence.²
- 10) Based on our slope stability analysis, we conclude that the proposed residential building envelope, while located upslope of the majority of the 1978 landslide

² Site-specific historical retreat rate (toe of coastal bluff, 1950-2010): (A) 0.8 inches/year x 75 years = 60 inches (5 feet), and (B) 1.4 inches/year x 75 years = 105 inches (8.75 feet). With Coastal Commission's additional 15 feet setback = 20-23.5 feet. The City's adopted generalized coastal bluff retreat rate (without distinction between the toe and top of coastal bluff) is 12 inches/year x 75 years = 75 feet, plus Coastal Commission's 15 feet, = 90 feet from the top of the coastal bluff.

and atop intact Monterey Formation bedrock, currently exhibits a static factor of safety (FS) of 1.39. Residential foundation recommendations are provided herein to improve the building envelope and upslope hillside stability to the industry standards of $FS \geq 1.5$ static, and $FS \geq 1.1$ to 1.2 seismic (pseudo-static with a seismic coefficient $k = 0.15$).

- 11) The State of California has summarized the current standard-of-care for slope stability analysis in Special Publication 117 ("Guidelines for Evaluating and Mitigating Seismic Hazards in California", Department of Conservation Division of Mines and Geology, 1997) and "Recommended Procedures for Implementation of DMG Special Publication 117 Guidelines for Analyzing and Mitigating Landslide Hazards in California" (June 2002). These guidelines indicate that the acceptable factor of safety (FS) for static conditions is 1.5, and for seismic conditions (pseudo-static analysis using a seismic coefficient of 0.15) varies from 1.0 to 1.2. It is our understanding that the certified City of Santa Barbara Local Coastal Program (LCP) Zoning Ordinance incorporates these State guidelines by reference.

Recommendations


- A) The residential building envelope should be stabilized using deep, reinforced concrete piers (shear pins) with tiebacks. We recommend that a shear pin wall with tiebacks be located along the downslope side of the construction envelope, near elevation 90 feet. In addition, an upper shear pin wall, without tiebacks, should be located near elevation 115 feet, but could be incorporated as part of the residential foundation structure. These foundation elements should be designed to resist the anticipated lateral loads imposed by the upslope earth materials, as discussed in Sections 4 and 6, below, in order that the building envelope and area upslope of it achieve static and seismic Factors of Safety of ≥ 1.5 and ≥ 1.1 to 1.2, respectively.
- B) The residential structure should be supported on a pier-and-grade beam foundation system with piers embedded a minimum of 20 feet into competent bedrock materials.
- C) Because of the detrimental influence of water on stability, erosion, and expansion of earthen material, it is important that surface water be strictly controlled in the

project area. We recommend that all surface water within and upslope of the development on the parcel be captured and directed in closed pipe(s) to one or more tanks for beneficial reuse, or in the alternative, be discharged into the City's municipal drainage system. In no event should any water from the proposed development be discharged to, or over (down), the coastal bluff. It will be important that surface and subsurface drainage are strictly controlled to avoid infiltration of rainfall or anthropogenic water to ground (e.g., into any remaining artificial fill, terrace deposits, or near the top of coastal bluff) or into and/or over the coastal bluff. CSA encourages utilization of low stature (fire resistant) deep-rooted native vegetation that does not require substantial irrigation in the residential re-use project landscaping.

- D) We recommend installing horizontal drains along the downslope shear pin wall to help prevent a rise in the groundwater levels over those observed during our monitoring period.
- E) We recommend that all water fixtures on the parcel be installed with automatic shut-off and back-flow valves, as applicable, and that connecting lateral pipes be located in separate conduits.
- F) We recommend that all utility lines and trenches on the parcel, including but not limited to the City's Mesa Trunk Line Sewer, be checked, and upgraded as necessary, to prevent exfiltration of water to the parcel.
- G) We recommend that grading at the site be kept to a minimum, and that grading or foundation construction be performed only during the dry season. We recommend that prior to the start of construction, the inclinometers and piezometers be monitored and surface conditions upslope and downslope of the building envelope, and at the coastal bluff, on the parcel be documented.
- H) The design drawings and specifications for all proposed (regulatory agency-approved) improvements (development) on the parcel should be reviewed by a Certified Engineering Geologist and Registered Geotechnical Engineer to assure that the recommendations of this report and site-specific design criteria are adequately incorporated into project design and construction.

- I) CSA recommends a minimum monitoring and reporting program of conditions at the parcel during the 75-year economic life of the proposed project to document its performance and to inform the property owner and public agencies of any substantial changes in them.

TECHNICAL REPORT



GEOLOGIC AND GEOTECHNICAL INVESTIGATION

1925 El Camino De La Luz

Santa Barbara, California

1.0 INTRODUCTION

This report contains the findings, conclusions, and recommendations of Cotton, Shires and Associates, Inc. (i.e., CSA's) geologic and geotechnical investigation of the parcel located at 1925 El Camino De La Luz, in the City of Santa Barbara (the City), Santa Barbara County, California - APN 045-100-024 (see Location Map, Figure 1). This investigation report is the culmination of a three-year study of the parcel and adjacent areas. It is our understanding that the results of our geologic and geotechnical investigation will accompany focused investigations relating to bluff retreat by Joseph Scepan Geoscience Consultant (September, 2012), and a coastal/wave hazards evaluation performed by David Skelly of GeoSoils, Inc. (July, 2012). In our investigation report, we specifically address the geologic conditions, slope stability, and geotechnical design recommendations for residential development on the parcel.


1.1 Proposed Development

It is our understanding that the proposed development is to include a single-family residence and appurtenant structures located in the northerly portion of the 50-foot wide parcel, near the southern terminus of the driveway that is its 'flag' portion. We understand that the base elevation of the building pad is to be at approximately elevation 92 feet (plus or minus approximately 5 feet), and the top elevation of the proposed residence and appurtenant structures will be below elevation 130 feet.

1.2 Background

The ± 0.44 -acre parcel is presently (2012) developed in various parts with El Camino De La Luz, a connecting driveway that serves both 1925 and 1927 El Camino De La Luz, a segment of the City's combination gravity flow and pumped 1940's vitrified clay pipe Mesa Trunk Line Sewer,³ other public utility conduits, a minor subareal stormwater v-ditch that discharges to 1921 El Camino De La Luz, older wooden fencing at the

³ In or about 2006, the City installed an interior lining in the sewer pipe.



Reference: ESRI Base Map, 2011



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

SITE LOCATION MAP

1925 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY JW	SCALE 1"=2000'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	FIGURE NO. 1

southerly end of the driveway, the City's post-1978 landslide grading envelope, and the Doolittle, et al. 1984 grading envelope.

The parcel was created by City approval of a minor land division (lot split) in 1955 and developed in 1956 pursuant to an inclusive City building permit with a split-level two-story residence and appurtenances.⁴ The residence was located on a notched building pad at the top of the headscarp of a pre-existing landslide. The driveway functioned to drain stormwater runoff from the street and other impervious surfaces on adjoining parcels to a drainage ditch along the east side of the house. A large landslide mobilized in the area of 2001 through 1903 El Camino De La Luz between February 11/12 and 14, 1978, during a period of heavy rainfall. Its catastrophic failure on the latter date impacted eight parcels and resulted, among other impacts, in the destruction of the residence and appurtenances south of the driveway at 1925 El Camino De La Luz. The City subsequently removed some, but not all, of the structural debris from the parcel, superficially graded it above elevation 60 feet, and in the process established the terrain that currently exists in that area.

In 1984, grading occurred on 2001-1927 El Camino de la Luz to fill the landslide graben and construct a benched keyway and subdrain-supported buttress on these parcels to help support the residence at 1933 El Camino de la Luz and the Mesa Trunk Line Sewer, and extended through vertical cutting of the coastal bluff top and adjacent hillside onto westerly 1925 El Camino de la Luz. Aerial photography from 1979 to the present indicates that post-1978 landslide coastal processes substantially restored the orientation and position of the coastal bluff, which had been translated seaward, within approximately 20 months. The graded terrain of the parcel has remained essentially unchanged during the subsequent years, including through several substantially above-average precipitation rain years.

A prior geotechnical investigation was performed on the adjacent 1921 El Camino De La Luz parcel in 2006 by Padre Associates, Inc. to analyze the geology and geotechnical conditions of that site in the context of a proposed residence on the upper hillside portion of that parcel. Padres' investigation included the drilling of two 18-inch diameter and three 24-inch diameter boreholes; the three 24-inch diameter boreholes were downhole logged by the project geologist. Laboratory tests were performed, including direct shear testing of downhole samples.

⁴ The El Camino De La Luz area of the West Mesa was substantially built out with single-family residences during the 1950's-1970's.

As part of our investigation, we reviewed background documents and maps, including the Padre Associates, Inc. investigation report and comments on it. However, CSA has not relied in our investigation, conclusions, or recommendations on Padres' data, laboratory test results, downhole interpretations, or geologic mapping.

1.3 Purpose and Scope of Work

The objectives of this geologic and geotechnical investigation have been to characterize the site surface and subsurface geologic conditions, determine the stability state of the site, and provide geotechnical design recommendations for construction of the proposed residence and appurtenances. Through exploration of the surface and subsurface geologic conditions and laboratory testing of representative earth materials, the geometry and engineering properties of the surficial earth materials and bedrock materials were characterized to allow our firm to perform detailed slope stability analyses and provide geotechnical design recommendations for construction. To fully address these objectives, we performed the following scope of work:

1. Document Research - Geologic and geotechnical documents, reports, and maps pertinent to the site were obtained, reviewed and analyzed (see Sections 8.1, Documents/Maps and Technical References, for a list of documents, maps and technical publications reviewed).
2. Evaluation of Aerial Photographs - Aerial photographs taken between 1929 and 2005 were analyzed by stereoscopic viewing to identify, within the limitations of the individual photographs, geologic hazards and/or historical changes in topography (see Section 8.2, Aerial Photographs, for a list of aerial photographs evaluated).
3. Topography Surveying - We generated an original, detailed topographic base map of the parcel using our total station theodolite surveying equipment. This topographic survey provides the necessary and accurate base map upon which our engineering geologic mapping was performed, and for generating the topographic profile for use in slope stability analysis, and for evaluating the coastal landforms, including the top and toe of the coastal bluff.

4. Engineering Geologic Mapping – The regional geology was reviewed, and detailed engineering geologic field mapping was performed to determine the site-specific geologic conditions of the subject property. The bluff face and the geologic exposures on the beach at the south end of the parcel were mapped in detail to supplement our surface and subsurface exploration program (see Plate 1, Engineering Geologic Map, in pocket at back of report).
5. Small-Diameter Subsurface Investigation – Three (3), 8-inch diameter borings were excavated, logged, and sampled to depths of 98 to 100 feet on 1925 El Camino De La Luz to determine the subsurface geologic conditions in the subject area. We also excavated and sampled two (2) additional small-diameter boreholes on the adjacent property (1921 El Camino De La Luz), which were used to aid in subsurface characterization of the parcel. These five borings were logged in the field by our staff and principal engineering geologists (see Appendix A, Field Investigation for logs of these borings).
6. Large-Diameter Subsurface Investigation – Two (2), 24-inch diameter borings were excavated, logged, and sampled to depths of 26 to 30 feet on 1925 El Camino De La Luz to determine the subsurface geologic conditions at the parcel. We also excavated and sampled one (1) additional large-diameter borehole on the adjacent property (1921 El Camino De La Luz), which was used to aid in subsurface characterization of the parcel. These three borings were logged in the field by our staff and principal engineering geologists (see Appendix A, Field Investigation for logs of these borings).
7. Instrumentation – We installed three slope inclinometers and three piezometers within the three small-diameter borings on the parcel in May 2011 to help evaluate the groundwater levels at depth, and to assess/characterize any slope movement. We have subsequently regularly monitored these instruments and recorded their data (see Appendix C, Monitoring, for results).
8. Laboratory Testing - Laboratory tests were performed on representative earth materials to obtain critical engineering properties for use in slope

stability analyses and foundation design criteria (see Appendix B, Laboratory Testing, for results).

9. Slope Stability Analyses – Static and seismic slope stability analyses were performed for critical failure surfaces on a representative cross section to evaluate the stability of the site during seismic and static (high groundwater) conditions (see Appendix D, Slope Stability Analysis Results).
10. Geotechnical Analyses and Formulation of Recommendations – Research, field, laboratory, and slope stability data were analyzed to characterize the geologic and geotechnical site conditions. The conclusions and recommendations set forth in this report were developed from these analyses.
11. Presentation of Findings - This report and the accompanying illustrations were prepared to summarize the findings, conclusions and recommendations of our investigation.

2.0 PHYSICAL SETTING

The parcel at 1925 El Camino De La Luz is approximately 344 feet in length, 50 feet in width along its main 'flag' body, and has a 200-foot long by 12.5 feet wide 'flag pole' lot component along the driveway and to the centerline of the street. The southern, downslope property line of the parcel is along the Mean High Tide Line, approximately 32 feet seaward of the toe (lower break in slope) of the coastal bluff. The parcel is bounded to the east and west by single-family residences on variously sized parcels, to the south by the Pacific Ocean (Santa Barbara Channel), and to the north by El Camino De La Luz. The physical parameters that influence the parcel include topography (terrain), the geologic setting, seismicity, coastal processes, and surface and subsurface hydrology. In the following report sections, we present descriptions of each of these parameters, including discussions of the influence that each parameter has on the subject area. Skelly (2012) describes the coastal processes that impact the parcel.

2.1 Topography



2.1.1 Terrain - The terrain at the parcel, at present (2012), consists of a gently inclined to moderately steep (5- to 25-degree inclination), south-facing, hillside, distinct coastal bluff, and rear cobble-sand beach on a gently inclined wave-cut terrace that extends seaward from the toe of the coastal bluff. Elevations on the parcel range from el. 4.63 feet along the seaward Mean High Tide Line property line of the parcel, to elevation 140 feet at El Camino De La Luz. The proposed base floor elevation of the residence is to be approximately elevation 90 feet (plus or minus 5 feet). The distinct top of coastal bluff is located near elevation 48 to 50 feet, approximately 150 to 180 feet downslope from the southern limit of the proposed building envelope. The coastal bluff is characterized by a precipitously steep slope (50- to 75-degree inclinations) that extends, with localized variations, down to the beach near elevation 10 feet, where a prominent break in slope is defined by a persistent cobble/boulder layer on the back beach. At the toe of coastal bluff immediately above the cobbles, marine erosion has developed a low height and narrow horizontal feature along the easterly half of the parcel and a small cave has developed along a near-vertical fracture zone near a Monterey shale outcrop on the adjacent 1927 El Camino De La Luz parcel. Approximately 25 feet to the east of the 1925 El Camino De La Luz parcel, a relict drainage swale on 1921 El Camino De La Luz cuts through the top of the coastal bluff and contributes to minor bluff face erosion in the area of a small promontory.

2.1.2 Top of Bluff - The southern end of the hillside on the parcel contains a very steep to precipitous (50- to 75-degree inclinations) coastal bluff. The coastal bluff face, with localized rilling, extends downslope to where the toe of the bluff face intersects the beach at approximately elevation 10 feet. The height of the coastal bluff from the well-defined top to the toe is 38 to 40 feet, and approximates the pre-1978 landslide grade toward the relict drainage swale on adjacent 1921 El Camino De La Luz parcel. The intersection of the top of the precipitous coastal bluff face with the relatively more gently inclined hillside to the north is a highly conspicuous, well-defined "top of bluff" point on the topographic profile (see Figure 2). The parcel contains no elevated marine terrace or "upper riser" coastal bluff feature. A representative topographic profile is illustrated on Figure 2 through the central portion of the parcel. This profile was generated from our detailed topographic surveying in 2010. Recent (2012) site reconnaissance indicates that the site topography (terrain) has not experienced significant changes between the time of our survey and the present.


Our evaluation of the site topography reveals that this prominent coastal bluff is located near the southern edge of the subject property. This coastal bluff is characterized by: 1) a prominent toe of slope at the back beach; 2) a precipitous bluff face, the lower portion of which is subject to episodic (limited period) wave run-up during high surf; and 3) a distinct top of the coastal bluff defined by a prominent inflection in the bluff face where the precipitous bluff face abruptly transitions to a more gently inclined to moderately steep bluff top hillside. This top of coastal bluff location is consistent with the methodology for identifying (determining) the top of coastal bluff as set forth in Coastal Commission's adopted regulation that defines this term of art (14 Cal. Code of Regs., sec. 13577), Coastal Commission's "Geologic Stability of Blufftop Development" Guideline, and Coastal Commission staff geologist Mark Johnsson's paper on "Establishing Development Setbacks from Coastal Bluffs" (2002). Johnsson defines the top of coastal bluff as:

"The bluff edge is simply the line of intersection between the steeply sloping bluff face and the flat or more gently sloping bluff top."

The parcel, as illustrated by the topographic profile of Figure 2, clearly has a well-defined top of coastal bluff approximately 288 feet south of the east-west property line with the adjacent 1927 El Camino De La Luz parcel. This top of coastal bluff (including the fact that it was lowered by grading in 1984) is consistent in its trend across the parcel and adjacent parcels, and has been in this approximate position and in this form dating



NOTES:
1) Topographic Profile surveyed by Cotton, Shires and Associates, on April 15 and April 16, 2010.
2) Mean Lower Low Water (MLLW) data obtained from National Oceanic and Atmospheric Administration (NOAA), April 2010 tidal predictions for the Santa Barbara Area.
3) MLLW datum is 2.788' lower than Mean Sea Level (MSL)

 COTTON, SHIRES AND ASSOCIATES, INC. CONSULTING ENGINEERS AND GEOLOGISTS		
Topographic Profile A-A' 1925 El Camino De La Luz APN:045-100-024 SANTA BARBARA, CALIFORNIA		
GEO/ENG BY JD	SCALE 1"= 50'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	FIGURE NO. 2

back to the earliest available aerial photographs taken in 1928. The 1978 landslide pushed this top of coastal bluff seaward approximately 80 feet, but the top of coastal bluff was restored to near its original position within several years of the landslide occurrence. Scepan (September, 2012) indicates that the top of coastal bluff remains approximately 10 to 33 seaward of its 1950 position. The proposed location of the residential structure must demonstrate that it is inland of the 75-year anticipated retreat rate setback line from the top of the coastal bluff, and maintain suitable static and pseudostatic ($F.S.=1.5$ and 1.1 , respectively) factors of safety. It is our opinion that the proposed building envelope is well inland of the 75-year anticipated retreat rate setback line from the well-defined top of bluff, and the proposed building site would be founded in (on) ground that has not experienced prior landslide movements, and should maintain a suitable factor of safety provided that the foundation design recommendations of this report are incorporated into the project.

2.1.3 Bluff Retreat – The orientation and location of the coastal bluff in the Mesa subarea of the Santa Barbara coastline that includes the subject parcel has demonstrated long-term persistence during the past 60 to 80+ years (Scepan, 2012; GSI, 2012). Previous studies and adopted reports have identified a general shoreline retreat rate (annualized average retreat) of 7.7 inches/year (Norris, 1968, reflected as 8 inches/year in the City of Santa Barbara LCP land use plan [1978, 2004]), and up to 10 inches/year (City of Santa Barbara General Plan Seismic Safety Element 1979). Fischer (2001) and Campbell (2007) have identified coastal bluff retreat rates of approximately 4 inches/year at a site some 500 feet to the east of the subject parcel, and on the adjacent parcel to the west. The City's recently adopted General Plan (2011) posits a generalized coastal bluff retreat rate of 12 inches/year. However, the site-specific study of the location of the coastal bluff top (edge) indicates that as a result of the seaward distention of the landform associated with the anthropogenically activated 1978 El Camino de la Luz landslide, the top of coastal bluff at 1925 El Camino de la Luz was located 10 to over 33 feet further south as of 2010 than it was in 1950 (Scepan, 2012).

The location of the top of coastal bluff on the subject parcel has not measurably changed during the past two years. Concurrently, the toe of coastal bluff has retreated at 1925 El Camino de la Luz at a long-term annualized average of 0.8 inches/year to 1.4 inches/year at the respective easterly and westerly parcel boundaries (Scepan, 2012). The proposed residential reuse development envelope on the subject parcel is set back a minimum of 171.9 feet from the top of the coastal bluff (GSI, 2012), landward of both the City's most recently adopted regulatory coastal bluff setback line (including Coastal Commission's

additional 10-foot setback) and 68 to 73 feet from the coastal bluff in 2087, under the City's presently pending tiered (accelerating) coastal bluff retreat rate in the Climate Action Plan.⁵ The proposed project therefore meets and exceeds all applicable coastal bluff retreat setback standards of the City of Santa Barbara.⁶

2.2 Geologic Setting


The parcel at 1925 El Camino De La Luz is located along the southern flank of the Santa Ynez Mountain Range in the central portion of the western Transverse Ranges of California. The western Transverse Ranges extend for approximately 75 miles from Point Arguello to Ventura County, and are generally characterized by tightly folded, Mesozoic and Cenozoic marine and non-marine sedimentary strata. Regional compressive stress within the late Tertiary in a north-south orientation has resulted in a prominent mountain building event, producing the characteristic east-west structural grain of the Transverse Ranges. The southern flank of the Santa Ynez Mountains contains early to mid-Tertiary sedimentary strata, tightly folded and extensively faulted along a nearly east-west trend (see Figure 3, Regional Geologic Map, by Minor, 2003).

Mapped active and potentially active faults are mostly high-angle reverse faults, and historic seismicity is characterized primarily by reverse fault focal mechanisms. Rapid uplift of the range from the Pliocene to recent time, which ranges from 1mm/yr to 2mm/yr (Keller, 2000), has resulted in rapid downcutting, deeply incised drainages, and abundant mass wasting. Large fan conglomerate deposits are located at the base of the range and are locally blanketed by uplifted marine terrace deposits and alluvium. Landslide deposits are common along the southern flank of the Santa Ynez Mountains, with the fine-grained Tertiary deposits particularly susceptible to landsliding.

The subject site is located in the Mesa area of the City of Santa Barbara, which is characterized as a Pleistocene uplifted marine terrace seaward of the southern flank of

⁵ The City's pending draft Climate Action Plan (June, 2012) proposes an annualized average coastal bluff retreat rate of 12 inches/year through the year 2050 and a rate of 24 inches/year for 2051-2100. CSA will confirm the location of the coastal bluff by a supplemental site-specific survey prior to submittal of the residential reuse project permit application to the City.

⁶ At 75-100 years, with an additional 10-ft wide band as applied by the California Coastal Commission within its jurisdiction, the setback dimensions are 85 to 110 feet from the top of the 2010 coastal bluff. Although no measurable top of coastal bluff erosion has been identified on this parcel since CSA's 2010 topographic survey, CSA can confirm the location of the top of coastal bluff by a supplemental area-specific survey prior to finalization of the residential re-use project permit application package to the City.



Reference: Geologic Map of the Santa Barbara Coastal Plain Area, Santa Barbara County, California, Minor et al., 2009

EXPLANATION

GEOLOGIC UNITS

- Qls Landslide deposit
- Qmt Marine Terrace Deposit
- Qsb Santa Barbara Formation (sandstone)
- Tmm Miocene Shale
- Tml Miocene Limestone
- Tr Rincon Shale

SYMBOLS

- 53 Strike and Dip
- Reverse Fault
- Thrust Fault
- Axis of Syncline or Anticline
- Marine-Terrace Shoreline Angle



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

REGIONAL GEOLOGIC MAP

1925 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY

JW

SCALE

1"=2000'

PROJECT NO.

G0058

APPROVED BY

JW

DATE

OCTOBER 2012

FIGURE NO.


3

the Santa Ynez Range. The parcel is located at approximate Latitude 34° 23' 47'' and Longitude 119° 43' 30'', approximately 780 feet west of the Santa Barbara Lighthouse. The site is underlain by Tertiary marine sedimentary bedrock materials of the Monterey Formation. This rock formation is oriented nearly east-west, and is dipping moderately (20- to 35-degrees) to the south/southwest. The Monterey Formation in the general vicinity is typically characterized by well-bedded, thin-bedded siliceous and calcareous shale with isolated dolomitic concretionary beds, and thin volcanic interbeds that are commonly altered to bentonite. Residual and colluvial soil materials derived from the Monterey Formation can be prone to expansivity and soil creep. No elevated scarp or 'upper riser' of a second marine terrace occurs on the subject parcel.

2.3 Seismic Setting

The Santa Barbara coastal plain and the Santa Ynez Mountains are located in a very seismically active area. Historically, this area has been subjected to strong seismic ground shaking from major earthquakes, and will continue to experience strong ground shaking in the future. The project site is located near several potentially active and active faults, some of which have ruptured in historic times. The faults in the region are mostly reverse slip faults, and are capable of generating strong seismic ground shaking. Some of these faults include the Mission Ridge-Arroyo Parida fault, the Santa Ynez fault, the offshore North Channel Slope fault, and the Red Mountain fault. The Lavigia fault is the closest (1.0 mile) mapped fault to the site (see Figure 4, Regional Fault Map, Keller, 2000); however, due to the lack of Holocene activity and relatively short fault length (15 km), this fault is not the design fault for this site. The active San Andreas fault zone is located approximately 41 miles to the east of the site, and while it represents the fault with the highest activity level and potential for large earthquakes, its distance precludes it from being a significant seismic constraint to the site.

The site has experienced strong ground shaking from several large earthquakes in the historic past. Most notably, the offshore Santa Barbara Channel faults have ruptured several times in the historic past, including a M7.0 in 1812, M6.25 in 1883, M6.3 in 1925, M5.9 in 1941, and M5.1 in 1978. The Santa Barbara earthquake of 1925 damaged or destroyed numerous buildings in the City's commercial district and resulted in 13 deaths. Large earthquakes on the San Andreas fault have also been experienced in the area, including the 1812, 1857, and 1906 multi-segment major earthquakes, and the Parkfield earthquakes of 1934, 1952, and 1966.



Reference: Earthquake Hazards of the Santa Barbara Fold Belt, California, (Report) E.A. Keller, 2000

EXPLANATION

FAULTS

MrR	More Ranch	RM	Red Mountain
MsR	Mission Ridge	OR	Oakridge
AP	Arroyo Parida	NCS	North Channel
DP	Dos Pueblos		Slope
CF	Carneros	RC	Rincon Creek
SJ	San Jose	PP	Pitas Point
SP	San Pedro		
LF	Lavigia		
MF	Mesa		
OH	Ortega Hill		
LP	Loon Point		



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

REGIONAL FAULT MAP

1925 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY
JW

SCALE
As noted

PROJECT NO.
G0058

APPROVED BY
JW

DATE
OCTOBER 2012

FIGURE NO.
4

2.3.1 Deterministic Seismic Analysis – The site could be affected by strong seismic ground shaking due to an earthquake from one of several active faults in the region. The Mission Ridge-Arroyo Parida fault is the active fault that poses the greatest potential threat to the site from a seismic shaking standpoint, and a maximum probable earthquake on this fault should serve as the "design event". The faults tabulated below could produce strong seismic shaking and are all considered to be active or potentially active. The following table provides the results of our deterministic analysis and lists the major earthquake sources, distance from the source to the site, maximum moment magnitudes and peak horizontal ground accelerations anticipated at the site:

TABLE 1 – DETERMINISTIC SEISMIC ANALYSIS

<u>Fault Source</u>	<u>Distance (mi.)</u>	<u>Moment Magnitude¹</u>	<u>Peak Horizontal Accelerations (g)²</u>
Mission Ridge/ Arroyo Parida	4.8	7.2	0.51
North Channel Slope	5.7	7.4	0.51
Red Mountain	4.7	7.0	0.50
Oak Ridge-Mid Channel	8.1	6.6	0.34
Santa Ynez (E)	8.6	7.1	0.30
Santa Ynez (W)	8.8	7.1	0.30
San Andreas (1857)	41.4	7.8	0.10

¹Based on "Probabilistic Seismic Hazard Assessment for the State of California" by CDMG, DMG Open File Report 96-08.

²Based on attenuation relationships developed by Sadigh, et al., 1997 (Horiz. - Rock) as determined using the computer program EQFAULT by Blake, 1989, updated 1997.

Using the maximum probable earthquake (which is considered to be the maximum earthquake expected to occur in a 100-year period) and a **deterministic** approach based on an attenuation relationship developed by Sadigh, et al. (1997), the subject site is expected to experience a mean peak horizontal ground acceleration of 0.51g. Based on a **probabilistic** analysis with an exceedance probability of 10% in 50 years, a peak ground acceleration of 0.44g was determined (U.S.G.S., 2011).



3.0 SITE CONDITIONS


The site geologic conditions of the subject parcel were investigated by our engineering geologists in order to characterize the surface and subsurface materials so that appropriate geotechnical design recommendations could be developed. The surface conditions were characterized using detailed topographic surveying and profiling followed by detailed engineering geologic mapping, which is portrayed on our Engineering Geologic Map (see Plate 1 and Figure 5, reduced version of Plate 1). The site subsurface conditions were investigated using small- and large-diameter boreholes, and these conditions are portrayed on our Engineering Geologic Cross Section A-A' (Figure 6). The groundwater conditions were characterized by the installation of multi-staged piezometers in each of the three small-diameter boreholes on the parcel. Inclometers were also installed within each small-diameter borehole on the parcel to verify current slope stability and as a means of verifying future slope stability.

3.1 Surface Conditions

The parcel surface is developed, in parts, with the driveway and adjacent southerly half of El Camino De La Luz (ECDLL), weedy and horticultural landscaping east of the driveway, a minor stormwater drainage v-ditch that discharges to the parcel at 1921 El Camino De La Luz, an older wooden fence (with seasonal sandbags to divert subareal runoff to the v-ditch) at the base of the driveway, a chain link metal fence that extends easterly near the top of the 1978 landslide headscarp, erosion control shrubs, the City's 1978 and the 1984 Doolittle, et al. grading envelopes. A vigorous contiguous stand of lemonade berry has colonized the landslide debris, colluvium, and (1984) excavated slope on the parcel below elevation 70 to 80 feet from a small number of shrubs that were repositioned by the 1978 landslide and subsequent City grading. Southern coastal bluff scrub substantially covers the distinct coastal bluff except at lower elevations that experience episodic wave spray or where the colluvium and landslide debris mantle has been eroded. The back beach area of the parcel consists of a persistent cobble field, with seasonal sand lenses and episodic marine detritus. In the biological reconnaissance report of 1925 El Camino De La Luz by WRA, Inc. (2012), the flora and fauna on the parcel are further described and analyzed.

The northern "flag pole" portion of the parcel is relatively level (less than 5-degree inclinations) and underlain by unconsolidated alluvial terrace deposits and artificial fill. The northern "flag" portion of the 50-foot wide area of the parcel, located just south of



 COTTON, SHIRES AND ASSOCIATES, INC. CONSULTING ENGINEERS AND GEOLOGISTS		
Engineering Geologic Cross Section A-A' 1925 El Camino De La Luz APN:045-100-024 SANTA BARBARA, CALIFORNIA		
GEO/ENG BY JD	SCALE 1"= 60'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	FIGURE NO. 6

the driveway and the site of the proposed residence, is characterized by moderately steep (20- to 25-degree inclination) hillside topography. This area was graded for development of the original residence in 1956, again in or about August-September, 1978, following the February 1978 landslide, and along its westerly margin in 1984. The 1978 grading resulted in a relatively uniformly sloping surface topography between elevations 130 feet and approximately 80 feet. This grading resulted in a loosely graded mantle of landslide earthen debris and colluvium, with numerous voids and relict structural debris between elevations ~60 feet and 80 to 90 feet. The 1984 grading by Doolittle, et al. resulted in a cut along the westerly margin of the parcel, between the top of coastal bluff and elevation 90 feet by approximately 6 to 10 feet vertical. Colluvium and landslide debris, to an unknown depth, underlay the present (2012) area of the robust contiguous lemonade berry stand between the top of the coastal bluff and elevations 80 to 90 feet. Weathered colluvium and fractured or displaced and sheared Monterey Formation materials are exposed along most of the 40-foot high coastal bluff face. Rilling, variously partly covered by vegetation, occurs on the coastal bluff face from near the top to near the toe of the coastal bluff. Where visible, the coastal bluff face displays weathered and fractured Monterey Formation shale that is oriented nearly east-west with out-of-slope dips generally ranging from 10 to 25 degrees.

3.1.1. Aerial Photograph Analysis - We analyzed multiple sets of stereo-pair aerial photographs to evaluate the parcel and to document topographic changes between 1929 and 2005. Our evaluation of the 1929 aerial photos reveals that a pre-existing landslide was located in the general vicinity of the 1978 landslide. This landslide contained dormant landslide debris to the east and west, but intact ground upslope. In 1929, a prominent linear drainage channel extended from farmland upslope (north), east of present day Oliver Road to the pre-existing landslide area and likely contributed to the slope instability. The prominent persistent coastal bluff is visible along the shoreline on the subject parcel, immediately to the north and upslope from the back beach. No coastal bluff “upper riser” occurs on the historical aerial photography of the area of the subject parcel.

We scanned the 1950 aerial photograph and overlayed it onto the 1962 photograph in ArcMap format to determine the location of the pre-existing landslide with respect to the existing residential structures, to the 1978 landslide, and to the location of the proposed structure. Based upon this geo-referencing exercise, it is apparent that the 1978 landslide occurred in virtually the same location as the pre-existing landslide limits, particularly

in the headscarp area. The eastern portion of the 1978 landslide appeared to have incorporated the older landslide debris visible in the 1929 aerial photographs. No pre-existing landslide debris is located upslope of the proposed residence at 1925 ECDLL.

The 1938 and 1950 aerial photographs reveal similar features as the 1929 aerial photographs, and also show active shallow slumps and slides along the face of the coastal bluff. The 1962 aerial photographs show that most of the residential structures along El Camino De La Luz are in place, including the house on the subject parcel. It is apparent in 1962 stereo-paired photographs, that the houses at 1925 and 1921 El Camino De La Luz were placed atop the contact between intact rock and the pre-existing landslide debris. Prior to the 1978 landslide, substantial artificial fill was also placed on 1937 El Camino De La Luz to support a driveway, which extended downslope atop the pre-existing landslide debris.

The 1978 oblique aerial photographs obtained by Weaver (1978) depict a large, relatively intact landslide block that has pushed seaward up to approximately 80 feet. A prominent headscarp can be seen, exposing light colored Monterey Formation bedrock. The surf zone has been altered by the intrusion of the landslide debris, and wave action is deflecting around this debris. In the Pacific Materials Lab, Inc. (1978) report, they mentioned that the surf zone had been uplifted in front of the coastal bluff, and their interpretation was that a deep rotational slide had uplifted these materials. It is our interpretation that the landslide was translational, and the landslide toe was near the base of the coastal bluff, and that the landslide 'bulldozed' the cobble and beach sand upward, rather than by rotational lifting. By October 1979, the majority of the landslide debris protruding into the surf zone had been eroded, and the grading performed in the headscarp area was complete. In a 1987 aerial oblique, the grading performed in 1984 for the buttress at 1933 ECDLL is clearly visible. In this photo it is clear that a substantial cut was performed near the top of the coastal bluff and this material was placed up under the residence as fill. The coastal bluff is clearly visible in this photograph as a prominent, precipitous, denuded slope face with a very sharp break in slope at the top of the exposed bluff face.

3.1.2 1978 Landslide – On February 14, 1978, a landslide occurred along the portions of approximately 8 parcels, including at 1925 El Camino De La Luz (ECDLL). We understand that initial movement was noticed as early as February 11, 1978 as tension cracks in the headscarp region. As a result of the catastrophic landslide movements that occurred late in the evening of February, 14, 1978, the residence at this

address was destroyed, along with the residence on the adjoining parcel at 1921 ECDLL. The residence at 1925 ECDLL was constructed of concrete blocks on a shallow foundation that straddled the landslide headscarp, which resulted in most of the concrete block foundation being translated downslope. The residence at 1933 ECDLL was not directly impacted, but was severely undermined, as were portions of the patio. An oblique low-altitude aerial photograph taken by or on behalf of Weaver shortly after the 1978 El Camino de la Luz landslide indicates a prominent lobe of landslide debris that extends from 1925-1927 ECDLL through 1909-1903 ECDLL in a south-southeasterly wedge onto the beach platform. Although parts of that wedge were subsequently eroded by marine processes, and excavated in 1984 along westerly 1925 ECDLL between el. 90 feet and elevation 50 feet as part of the Doolittle grading to buttress the 1978 landslide headscarp at 2001-1933-1927 ECDLL, the 1978 landslide appears to have been triggered by saturation of the oxidized Monterey Formation from upslope anthropogenic sources during the above-average 1977-1978 rain year, rather than by marine undercutting of the distinct coastal bluff.

In or about August-September, 1978, the City variously removed or buried landslide structural debris at 1925 ECDLL in conjunction with grading of the Mesa Trunk Line Sewer earthen buttress, to elevation 126 feet, and demolished the remaining standing part of the house at adjacent 1921 El Camino de la Luz. The City's grading extended between elevations 60 and 126 feet at 1925 El Camino de la Luz and was augmented by installation of sand bag walls, drainage flex pipe, a low berm near the head of the driveway, and v-ditch drainage to direct stormwater runoff to the relict drainage swale on the coastal bluff top at 1921 El Camino de la Luz. In 1984, grading (excavation) by Doolittle directed stormwater runoff from the westerly band of 1925 El Camino de la Luz, between elevations 90 and 55 feet, toward 1927 ECDLL.

Our analysis indicates that the 1978 landslide failed along, or near, the limits of the pre-existing landslide. However, we do not see evidence in the historical aerial photographs, or from our geologic mapping, for older landslide debris extending upslope of the 1978 landslide in the driveway segment of 1925 ECDLL, the street, or lots to the north. Based upon geologic relationships identified in the field and in aerial photographs, and our subsurface exploration, CSA interprets the 1978 landslide to be a translational rock-block landslide. The current (2011) exploration of this landslide reveals a basal landslide rupture surface depth of approximately 0 to 11 feet within the southern portion of the proposed building envelope of 1925 ECDLL, and a maximum depth of approximately 40 to 50 feet downslope near the coastal bluff (see Figure 6,

Engineering Geologic Cross Section A-A'). Historical photographs reveal that the headscarp of the 1978 landslide, in the middle to eastern portion of the landslide (including the 1925 ECDLL parcel), has a relatively moderate inclination (i.e., less than 35 degrees), and likely failed along bedrock stratification inclined seaward (i.e., dip-slope bedding). Aerial photographs reveal fence line offsets that indicate the landslide moved slightly southeastward, which is slightly oblique to the bedding orientations documented in the headscarp region within large diameter boreholes, but near-parallel to the orientations near the beach. In our investigation, we documented southwesterly dips ranging from 25 to 35 degrees in the upper portion of the slope, but found much shallower bedrock inclinations (10 to 20 degrees) and more southerly orientations in the bluff face and in the surf zone.

The residence on 1925 ECDLL prior to the 1978 landslide was, in part, constructed atop the margin of the older landslide observed in the historical aerial photographs and mapping, thus was straddling the contact between landslide debris and intact rock. The lack of deep foundation support and poor placement of the structure resulted in its experiencing downslope movement when the landslide debris reactivated, removing support for the southern side of the structure. Unlike that location and foundation, the current residential project locates the proposed house exclusively within intact Monterey Formation bedrock within the headscarp of the evacuated landslide, on a deep pier and grade beam foundation and in an area bounded to the south (downslope) and north (upslope) by shear pin (stitch-pier) walls. As illustrated in Figures 5 and 6, Engineering Geologic Map and Engineering Geologic Cross Section A-A', the northern portion of the 1978 landslide debris is mostly removed from the area of the proposed building envelope, with only a small wedge located in the southern portion of the building envelope, which is proposed to be stabilized with a tied-back shear pin wall.

3.2 Local Geology

The parcel is underlain by bedrock materials of the Monterey Formation (i.e., well-stratified siltstone and shale with isolated interbedded bentonite horizons). Alluvial terrace materials and artificial fill are located beneath and east of the driveway in the northern "flag pole" portion of the 'flag lot' parcel. Oxidized bedrock materials on the parcel experienced landsliding in 1978. These displaced bedrock materials are well-exposed on the coastal bluff face on the parcel. Bedrock materials are exposed along the coastal bluff on the upcoast and downcoast sides of the 1978 ECDLL landslide. Bedrock orientations, in general, are documented to be very similar within the landslide mass as

they are outside of the landslide, with northwest strikes and southwest dips ranging from 15 to 35 degrees. Bedrock materials are locally overlain by alluvial terrace deposits in the northern portion of the site, landslide deposits in the southern portion of the site, surficial soil materials, and artificial fill. The 1978 ECDLL landslide mobilized along the central and southern portions of the site and resulted in residential distress and the ultimate removal of the two residential structures (1921 and 1925 El Camino De La Luz). The City graded the area of the parcel between elevation 60 and 126 feet on or about August-September 1978 and installed sand bag walls, flex pipe, and v-ditch drainage to direct stormwater runoff to the relict drainage swale on the 1921 El Camino De La Luz coastal bluff top.

3.3 Earth Materials

Earth materials present in the subject parcel include beach deposits, landslide deposits, surficial soil/colluvium, non-marine terrace deposits and Monterey Formation bedrock materials as described below:

3.3.1 Beach Deposits (Qbs) - Beach deposits are present in the subject area seasonally as a thin veneer of well-sorted medium-grained sand atop bedrock materials and coarse cobble deposits. The beach deposits are derived from local and regional weathering of the coastline and net longshore drift currents that transport materials from west to east. The beach deposits are light to medium gray in color, medium grained, well sorted and rounded, contain abundant shell fragments, and contain occasional rounded cobbles up to 6 inches in dimension. A more persistent accumulation of very coarse cobbles is located at the landward edge of the beach and consists of very hard and strong, fossiliferous, dolomitic and siliceous cobbles derived from mass wasting of the local Monterey Formation.

3.3.2 Landslide Debris (Als) – Landslide debris associated with the 1978 landslide, as illustrated on our Engineering Geologic Map (see reduced version, Figure 5), underlies the southern portion of the parcel. Our geologic mapping, logging of small-diameter boreholes, and downhole logging of large-diameter borehole LD-3 reveals that the landslide deposits consist of highly fractured, dilated, disrupted, and weathered Monterey Formation sedimentary materials consisting of mudstone, siltstone, and shale. The landslide debris contains bedrock orientations near the regional conditions, consistent with a translational type of earth movement. The bedrock orientations on either side of the basal rupture surface in LD-3 are virtually identical; by

definition, this necessitates a translational failure mechanism. The basal rupture surface is not exposed in the coastal bluff, and our interpretation suggests that the 1978 landslide 'toed-out' near the shoreline angle defined by the cobble deposits on the back beach. We did observe a shear surface near the top of the cobble deposits, but our interpretation is that this shear surface is likely an intermediate shear above the buried basal shear surface.

3.3.3 Non-Marine Terrace Deposits (Qt) – Non-marine terrace deposits unconformably overlie Monterey Formation bedrock across the driveway portion of the parcel, between elevations 130 and 140 feet. The non-marine terrace deposits range in thickness from approximately 5 to 8 feet. These materials are characterized by a dark brown, organic rich, silty clay soil profile on which vegetation is established. This soil profile grades down into medium brown silty sands with occasional pebbles up to 4 inches scattered throughout. These silty sands, which form the main body of the terrace materials, also contain laterally discontinuous lenses of well-rounded pebbles that represent channel gravel deposits. At the base of the terrace is a semi-continuous gravel lag deposit that is directly atop the siltstone bedrock. These earth materials were exposed and logged in a hand-excavated test pit just below the end of the driveway by Weaver.

3.3.4 Monterey Formation Bedrock (Tm) – The parcel is underlain by sedimentary bedrock materials of the Monterey Formation. These earth materials consist of variably weathered siliceous shale, mudstone, siltstone, and isolated fine sandstone. The Monterey Formation is generally thin-bedded and has a weathering zone of between 25 and 30 feet thickness consisting of tan/buff shale and mudstone that is closely fractured and weak to moderately strong. Isolated, deeply weathered mudstone interbeds were observed in the subsurface during downhole logging of LD-1 and LD-2. Below the weathering zone, the bedrock is dark brown to dark gray, petroliferous, and well-bedded, with isolated tightly-folded rock having numerous tar seams. Bedrock orientations observed in the large-diameter borings and in the coastal bluff reveal persistent east-west to northwest strikes and southerly dips of moderate inclination, resulting in dip-slope conditions (sedimentary bedrock layers sloping downslope) at the bluff face.

3.4 Subsurface Conditions

The subsurface geologic conditions at 1925 El Camino De La Luz were explored by excavating three small-diameter boreholes in May 2011, and two large-diameter boreholes in October 2011 (see Plate 1 and Figure 5, Engineering Geologic Map).

3.4.1 Small-Diameter Borehole Exploration – Three small-diameter boreholes were drilled on the 1925 El Camino De La Luz parcel, and two borings were drilled on the adjacent 1921 El Camino De La Luz parcel. The small-diameter boreholes were excavated primarily utilizing mud-rotary, continuous coring methods; however, the upper portions of the boreholes within artificial fill, weathered bedrock and landslide debris were drilled using hollow-stem auger techniques. Inclinator casing was installed in each borehole, and 2 vibrating wire piezometers were attached to the outside of each borehole casing and grouted into place. Detailed logs of these borings were generated in the field and augmented by additional logging of retained cores in our lab by staff and principal geologists (see borehole logs in Appendix A).

Borehole B-1 – Borehole B-1 was excavated along the east side of the 1925 El Camino De La Luz driveway, near elevation 132 feet and upslope of the proposed building envelope. In Borehole B-1, we encountered approximately 7 feet thickness of non-bedrock material consisting of silty clay, silty sand terrace deposits, and possibly some artificial fill. Below these earth materials, we encountered weathered Monterey Formation bedrock consisting of weak to moderately strong, fractured, laminated shale and claystone. The terrace deposits and weathered bedrock in the upper 28 feet below ground surface (to elevation 104 feet) were drilled using a hollow-stem auger with Modified California sampling at approximate 3-foot intervals. Approaching the boundary between the weathered and unweathered bedrock, the drilling became much harder, and mud-rotary drilling methods were used with continuous core sampling (see Appendix A, representative photographs of core samples). We encountered slightly weathered to unweathered Monterey Formation bedrock from 38 feet depth (elevation 94 feet) to the bottom of the borehole at a depth of 98 feet below ground surface (elevation 34 feet). These earth materials consisted of unoxidized, variably fractured, and moderately strong to strong shale and claystone. Localized highly fractured and weak zones were encountered, and isolated clay seams were encountered at depths of 70 and 75 feet below ground surface. No bentonite layers were encountered, but numerous tar seams were encountered in Borehole B-1.

Borehole B-2 – Borehole B-2 was excavated within the proposed building envelope, near elevation 119 feet. In Borehole B-2, we encountered approximately 5 feet of non-bedrock material consisting of silty clay and silty sand artificial fill. Below these materials, weathered Monterey Formation bedrock was encountered, consisting of weak to moderately strong, fractured, laminated shale and claystone. The fill and weathered bedrock in the upper 30 feet were drilled using a hollow-stem auger with Modified California sampling at approximate 3- to 5-foot intervals. Approaching the boundary between the weathered and unweathered bedrock, the drilling became much harder, and mud-rotary drilling methods were used with continuous core sampling (see Appendix A, representative photographs of core samples). We encountered slightly weathered to unweathered Monterey Formation bedrock from 35 feet to the bottom of the borehole at a depth of 98 feet below ground surface. These materials consisted of unoxidized, variably fractured, and moderately strong to strong shale and claystone. Localized highly fractured and weak zones were encountered, and isolated, unsheared clay seams and/or thin (paper thin to a few mm thick) clay films were encountered at depths of 31, 89 and 95 feet below ground surface (elevations 101, 43, and 37 feet). No bentonite layers, but numerous tar seams were encountered in Borehole B-2.

Borehole B-3 – Borehole B-3 was excavated downslope of the proposed building envelope, near elevation 87 feet. In Borehole B-3, we encountered approximately 14 feet thickness of landslide deposits consisting of silty clay with rock fragments, disrupted shale and claystone with numerous interstices (voids). Below these earth materials, weathered Monterey Formation bedrock was encountered, consisting of moderately strong, fractured, laminated shale and claystone. The fill and landslide debris in the upper 10 feet were drilled using a hollow-stem auger with Modified California sampling at approximate 3-foot intervals. Mud-rotary drilling methods were used below a depth of 10 feet, with continuous core sampling. We encountered slightly weathered to unweathered Monterey Formation bedrock from 18 feet depth to the bottom of the borehole at a depth of 98 feet below ground surface. These materials consisted of unoxidized, variably fractured, and moderately strong to strong shale and claystone. Localized highly fractured and weak zones were encountered, but no bentonite layers were encountered. Numerous tar seams were encountered throughout the relatively unweathered portion of the borehole and these seams typically cross-cut bedding along very tight fracture zones.

3.4.2 Instrumentation – Inclometers and piezometers were installed within boreholes B-1, B-2, and B-3. Inclometers were installed the full length of each borehole

(98 feet depth below ground surface) and initialized on May 19, 2011. Subsequent inclinometer readings were performed on May 26, June 1, June 27, and September 22, 2011, and January 5, 2012. To date, we have not detected movements in any of the three inclinometers that exceed the precision limitations of the instrument (see Appendix C, inclinometer graphs). Two, vibrating wire piezometer sensors were installed in each of the three boreholes at mid-range depths of between 38 and 45 feet, and deep sensors between 88 and 93 feet depth below ground surface. The water levels recorded in these instruments (see Appendix C, piezometer graphs) between mid-May 2011 and early January, 2012 have been relatively consistent and generally correspond with the transition from oxidized to unoxidized bedrock between 25 and 30 feet depth below the ground surface, as shown on Engineering Geologic Cross Section A-A' (see Figure 6).

3.4.3 Large-Diameter Borehole Exploration – We excavated two, 24-inch diameter, large-diameter boreholes (LD-2 and LD-3) for the purpose of investigating the subsurface conditions of 1925 El Camino De La Luz. A third large diameter borehole (LD-1) was excavated on the adjacent property at 1921 ECDLL. These boreholes were downhole logged by our staff and principal geologists; our geologic logs are included in Appendix A. Figure 5 also shows the location of these boreholes.

Borehole LD-2 – Borehole LD-2 was excavated within the proposed building envelope of 1925 El Camino De La Luz, at an approximate ground surface elevation of 120 feet, upslope of the 1978 landslide debris, and within the headscarp region of the 1978 landslide. In Borehole LD-2, we encountered approximately 5 feet thickness of artificial fill in the southern (downslope) portion of the borehole only, which we interpret to be part of the post-1978 landslide grading. This fill was not observed in the northern (upslope) portion of the hole. The entire borehole (with the exception of the artificial fill) consists of relatively uniform Monterey Formation bedrock characterized by: deeply to moderately weathered, thin-bedded claystone and shale, weak to moderately strong, closely fractured, dry to moist in the upper 15 feet, and moist to locally wet below 15 feet. Conspicuous tar seams were observed cross-cutting bedding. The claystone interbeds were locally soft and plastic, whereas the shale was generally moderately hard, strong, and brittle. Bedding orientations were generally consistent, with average orientations documented to be N63W, 27SW. The borehole did not contain evidence of previous landsliding, such as open fractures, shears, offset bedding relationships, striated shear planes or abundant high-angle fractures with roots and openings. Very difficult drilling conditions were encountered at a depth of 26 feet. Seepage was encountered at a depth of 23 feet during drilling, and standing water

stabilized in the borehole at a depth of 21.5 feet at the end of the day. Photographs and video footage of this borehole are on file at CSA's Los Gatos office.

Borehole LD-3 – Borehole LD-3 is located downslope of LD-2 within the trailing edge of the 1978 ECDLL landslide debris, at approximate elevation 93 feet near the southeastern margin of the proposed building envelope. This borehole was excavated near the north-south property line, and several feet onto the 1921 El Camino De La Luz parcel. In Borehole LD-3, we encountered approximately 12 feet thickness of landslide debris characterized by profusely fractured, unstable, ravelly, deeply weathered and weak Monterey Formation materials. At a depth of 12 feet, we encountered a prominent basal landslide shear surface characterized by a 3- to 5-inch thick shear zone with upper and lower bounding shear surfaces that are bedding plane-parallel. Between the upper and lower bounding shears, we documented highly fractured, disrupted, and displaced silty sand and clayey silt with abundant shale rock fragments. The shear zone has an orientation of N70W, 30SW, which is similar to bedding orientations above and below. Clay gouge, paper thin to 0.25-inch in thickness, was observed along the upper and lower contacts of the shear zone, but these gouge zones were discontinuous and disrupted. We interpret this to be the result of dilation (unloading) along the shear zone as the main portion of the landslide evacuated this area and the trailing edge of the 1978 landslide came to rest at this location.

The basal shear zone defines a dramatic textural change in the borehole, where unoxidized, intact, hard and strong Monterey Formation bedrock materials were encountered below the shear, and extended to the bottom of the borehole at a depth of 30 feet. Bedding orientations were generally consistent above and below the landslide shear surface, with average orientations documented to be N67W, 28SW. Practical drilling refusal was encountered at a depth of 30 feet. Seepage was encountered during drilling at a depth of 25 feet, and standing water stabilized in the borehole at a depth of 26 feet the following morning. Photographs and video footage of this borehole are on file at CSA's Los Gatos office.

Borehole LD-1 – This borehole was drilled in the northern portion of 1921 El Camino De La Luz, outside of the limits of the 1978 landslide, and was used for correlation purposes in the analysis of the subsurface geology on 1925 El Camino De La Luz. In borehole LD-3, we encountered relatively uniform Monterey Formation bedrock for the entire depth of the hole (25.4 feet), characterized by: deeply to moderately weathered, thin-bedded claystone and shale, weak to moderately strong, closely

fractured, dry to damp for the entire borehole, and conspicuous tar seams along bedding near 18 feet. The claystone interbeds were locally soft and plastic, whereas the shale was moderately hard, strong, and brittle. Bedding orientations were generally consistent, with average orientations documented to be N40W, 33SW. The borehole did not contain evidence of previous landsliding, such as open fractures, shears, offset bedding relationships, striated bedding planes or abundant high-angle fractures with roots and openings. Very difficult drilling conditions were encountered at a depth of 25 feet. Seepage was not encountered in this borehole. Photographs and video footage of this borehole are on file at CSA's Los Gatos office.

3.5 Groundwater Conditions

Groundwater was observed in large-diameter boreholes LD-2 and LD-3 at stabilized (approximate 12-hour period) depths of 21.5 and 26 feet, respectively. Relatively minor seepage was observed during drilling and logging of these holes at depths of 23 feet (LD-2), and 25 feet (LD-3). Rotary wash drilling methods were utilized for the small-diameter drilling, and thus, no groundwater levels could be observed during drilling. However, two vibrating wire piezometer sensors were installed in each of the three small-diameter boreholes; one at a mid-range depth of between 38 and 45 feet, and one deep sensor between 88 and 93 feet below ground surface. Water levels were recorded in these instruments (see piezometer graphs, Appendix C) between mid-May 2011 and early January 2012. Groundwater levels have been relatively consistent during the monitoring period, and generally correspond with the transition from oxidized to unoxidized bedrock between 22 and 35 feet below the ground surface, as shown on Engineering Geologic Cross Section A-A' (see Figure 6). The deep and shallow sensors reveal groundwater levels nearly at the same elevation, indicating that neither artesian conditions nor perched water tables are present on the parcel.

3.6 Summary of Findings

Our surface and subsurface exploration reveals that the parcel at 1925 ECDLL is underlain by sedimentary bedrock materials of the Monterey Formation. These materials are generally oriented in a dip-slope condition with bedding sloped approximately 20 to 35 degrees to the south. The intact Monterey Formation at the subject parcel contains a prominent weathered zone that is approximately 20 to 40 feet in thickness. The central and southern portions of 1925 ECDLL are underlain by a moderately deep (i.e., 40 to 50 feet in maximum depth), translational landslide. This

landslide mobilized in February, 1978 in response to heavy rainfall and likely in response to stormwater discharge from ECDLL to the south trending driveways, and leakage from the Mesa Trunk Sewer Line into the headscarp area of the landslide. This landslide debris is in a low slope position on 1925 ECDLL and has not shown measurable reactivation since the primary failure in 1978; however, it is our opinion that reactivation of the debris could occur during heavy rainfall or seismic events. No evidence of pre-historic landsliding was observed upslope of the 1978 landslide. The mobilization of the 1978 landslide mass removed lateral subjacent support for the northern portion of 1925 ECDLL, and thus, thorough characterization and analysis of this slope has been performed to determine its stability state, as describe later in this report.

4.0 LIMIT EQUILIBRIUM SLOPE STABILITY ANALYSES

4.1 Representative Cross Section Analyzed

Engineering Geologic Cross Section A-A' (see Figure 6 and Plate 1) was analyzed for our slope stability analyses because it best represents the site topography and subsurface exploratory borehole data. This cross section was generated based upon our site-specific topographic survey of 2010 as well as our small- and large-diameter subsurface exploration and monitoring of groundwater levels.

4.2 Analysis Procedure

Our analysis was focused on evaluating the stability of the slopes at the parcel with the conservative assumption that the 1978 landslide mass below the proposed building envelope could potentially/eventually evacuate/mobilize seaward, and be subsequently eroded away by nearshore coastal processes. In reality, the remaining terrestrial landslide mass has not moved significantly since 1978, and is therefore likely actually providing some buttressing effect for the materials upslope. For conservatism, we did not rely on this buttressing component in our analysis and assumed that the existing landslide debris was no longer present. In our analysis, we evaluated the resulting slope stability by determining the required stabilization structures and shear resistance demand needed to mitigate the potential for future deep-seated slope instability to industry standard factors of safety. We evaluated the following four conditions:

1. We evaluated the future slope stability of the parcel by assuming that the landslide debris had evacuated with no improvements (residences) or stabilization made to the parcel;
2. We evaluated the future slope stability of the parcel by assuming that the landslide debris has evacuated, the residence has been constructed and the slope is stabilized with two rows of shear pins, the lower row equipped with tiebacks to achieve a satisfactory static Factor of Safety (FS) equal to or greater than 1.5;
3. We evaluated the same condition as 2, above, except that a pseudo-static coefficient of $k=0.15$ is added to model potential earthquake loading and a

satisfactory pseudo-static Factor of Safety (FS) equal to or greater than 1.1 to 1.2 is achieved; and

4.3 Software and Methodology

The computer program SLOPE/W (by Geo-Slope International) was used to perform the CSA slope stability analysis. All analyses were performed utilizing the Morgenstern-Price method of analysis. With this method, the parameters of our representative cross section are input into the program, the potential sliding mass is divided into slices by the program, and inter-slice side force inclinations are variable. The Morgenstern-Price method satisfies equilibrium conditions for overall moment, individual slice moment, and vertical and horizontal forces.

The Block Search method was used to identify hypothetical critical potential failure surfaces. This method is preferred for analyzing non-circular surfaces along bedding planes. Using the Block Search method, trial failure surfaces are created by connecting surfaces (linear lines) between nodes of user-specified blocks. The number of nodes and sizes/locations of blocks are parameters selected by the program operator. In addition, the operator can specify a range of projection angles of each block to the ground surface at both the head of the slide and the toe of the slide. This method of searching creates a large number of surfaces and significant iteration is required.

4.4 Analysis Input Parameters

The primary input parameters needed for the limit equilibrium sliding stability analyses included the ground surface topography, subsurface geologic stratigraphy, depth and inclination (geometry) of the hypothetical basal shear surface, strength and unit weight properties of the earth materials and the groundwater levels.

Ground Surface Topography – The topography was based on the site-specific 2010 CSA topographic survey (with 2-foot contour intervals) of the parcel.

Subsurface Geologic Stratigraphy – The geologic units were determined based on surface mapping and subsurface exploration, including small-diameter borings and downhole logging of large-diameter borings. The stratigraphy is comprised of two Monterey Formation bedrock units (Weathered Bedrock and Unweathered Bedrock), a Quaternary Terrace (Qt) deposit, Artificial Fill (Af), and Landslide Debris (Als).

Shear Strengths - We performed back-calculation analysis on the existing landslide and, based on that analysis, arrived at a residual shear strength parameters and average wet unit weight of $C = 0$ psf, $\phi = 19^\circ$, $\gamma = 89$ pcf for this material. The Weathered and Unweathered Bedrock were assigned along-bedding shear strength parameters and wet unit weight values of $C = 0$ psf, $\phi = 25^\circ$, $\gamma = 105$ pcf and $C = 1$ psf, $\phi = 32^\circ$, $\gamma = 110$ pcf, respectively. The Weathered Bedrock shear strength parameters of $C = 0$ psf, $\phi = 25^\circ$ were based on an average of four residual torsional ring shear test results from weathered bedrock samples taken by CSA staff geologists in the large-diameter boreholes. The Unweathered Bedrock shear strength parameters of $C = 1$ psf, $\phi = 32^\circ$ represent the highest residual torsional ring shear test result of the four weathered bedrock samples. The wet unit weight value selected for the Weathered Bedrock represents the average of seven unit weight tests, while the Unweathered Bedrock wet unit weight was selected based on an average of the five highest laboratory test result values. We note that the unweathered, along-bedding shear strength values were approximately 28% greater than the weathered shear strength values.

Cross-Bedding Shear Strength - During our geologic mapping, logging of small-diameter continuous cores and downhole logging of the large-diameter borings within the intact Monterey Formation bedrock, we observed layered stratigraphic rock with unit strengths that varied from very hard and strong rock, to weak to moderately strong rock. This layered, intact rock inherently contains significant cross-bedding shear strength in both the weathered and unweathered bedrock relative to along bedding shear strength. For the slope stability analysis, we used a cross-bedding shear strength in the weathered material based on the results of two of the four triaxial compression consolidated shear strength tests performed which resulted in anisotropic shear strength parameters of $C = 0$ psf, $\phi = 45^\circ$.

Since difficult drilling conditions were encountered in the unweathered bedrock, we could not obtain undisturbed tube samples; therefore, mud-rotary drilling was performed and continuous core samples were retrieved. The shear strength parameters (friction angle and cohesion) for the unweathered rock were consequently derived by using an estimate of the rock mass strength of the sedimentary rock using the Hoek-Brown failure criterion. This procedure consists of an empirical method used to estimate the strength parameters of jointed rock masses (Hoek and Brown, 1997). Input parameters to this analysis include the Geological Strength Index (GSI, Wyllie and Mah, 2004; and Rocscience, 2007), which is a rating system that allows the rock mass quality to

be quantified based on the surface conditions and rock fracturing. Other input parameters include unconfined compressive strength and rock type rating (a factor, m, which is a constant dependent on rock type) related to the principal stresses at failure.

We logged the core samples in detail and found that the unweathered Monterey Formation consists of three distinct rock domains based upon strength characteristics: 1) Concretionary Siltstone, very hard and very strong, limited to approximately 5% of the unweathered stratigraphy, GSI 55-70; 2) Siliceous Siltstone, medium strength, well-bedded, closely fractured, makes up approximately 65% of the unweathered stratigraphy, GSI 50-55; and 3) Weakly Cemented Siltstone, very weak to weak strength, well-bedded, makes up approximately 30% of the unweathered stratigraphy, GSI 20-25. We used a Schmidt Hammer to obtain the compressive strength of the rock, and correlated these test results with geologic field tests (hammer blows, knife scratch tests, etc.) to assure appropriate compressive strength input parameters were being used. The results of the calculations (performed using Rocscience, 1997 software) are presented in Appendix D.


In summary, the Hoek-Brown failure criterion (Mohr Coulomb cohesion strength parameter) resulted in $\Phi = 40$ degrees and cohesion of 3,700 psf. It should be noted that for conservatism, we utilized exclusively the lower bound range of the GSI input parameters for the Case 1 and Case 2 rock domains. For Case 3, the upper bound input parameters (GSI = 25 and 0.5 ksi compressive strength) were used rather than the lower bound (GSI = 20 and 0.15 ksi compressive strength), due to the low strength ($\Phi = 14^\circ$, $C = 720$ psf) of the results, which are unlikely to be achieved for these intact, unweathered bedrock materials. A weighted average of the three rock domains, and their associated strengths, was then generated to arrive at average shear strength parameters for the unweathered rock that would have to be sheared in order for a landslide shear plane to daylight at the toe of slope. This weighted average ($\Phi = 40^\circ$, $C = 3,700$ psf) was reduced to $\Phi = 40^\circ$, $C = 2,000$ psf to conservatively account for uncertainties.

It is worth noting that cross-bedding strengths for the Monterey Formation at the Ocean Trails Development project on the Palos Verdes Peninsula (with similar Monterey Formation bedrock type and similar stratigraphy as the subject parcel) were derived by the Project Geologist in much the same manner, except they used the Rock Mass Rating system. They arrived at a cross-bedded shear strength of $\Phi = 51^\circ$ and $C = 6,500$ psf. These data were peer reviewed by an independent panel of experts who determined that a range of strengths was more appropriate at the site, depending upon anticipated

loading conditions. The lower bounding strength parameters were $\Phi = 40^\circ$ and $C = 2,000$ psf, with the upper bound strength parameters at $\Phi = 51^\circ$ and $C = 6,500$ psf. As peer reviewers for the project, we inspected hundreds of feet of core and downhole logged over 50 large-diameter boreholes at the Palos Verdes site, and conclude that the rock at the subject West Mesa parcel is very similar to that observed at Ocean Trails. Therefore, it is our opinion that the cross-bedding strengths for the unweathered bedrock presented above are conservative, and are generally used for rock that is more disrupted than that observed in the unweathered zone at the subject West Mesa parcel.


To model this anisotropic strength in the computer program, we specified the along-bedding shear strength as failure surface inclinations between 24 and 30 degrees (see Figure 9) and any shear outside of this range would be assigned a cross bedding factor as discussed above and shown in the following Table 2.


Figure 9. Anistropic Strength Function for Bedding Inclination



The inclination angles measured from the positive x-axis are positive, and negative when measured from the negative x-axis (see Figure 10 below).

Figure 10. Sign Convention for Anisotropic Strength Function





(Source: Geostudio 2007 SLOPE/W)

Table 2 – Slope Stability Earth Material Properties

Earth Material	Unit Weight (pcf)	Along Bedding Cohesion (psf)	Along Bedding Friction Angle (degrees)	Cross Bedding Cohesion (psf)	Cross Bedding Friction Angle (degrees)
Weathered Bedrock	105	0	25	0	45
Unweathered Bedrock	110	1	32	2,000	40

For simplicity, the relatively thin zones of Artificial fill (Af) and Quaternary Terrace (Qt) materials were modeled as Weathered Bedrock.

Groundwater Levels – A piezometric surface was selected using the highest recorded water levels indicated by the piezometers installed in the small-diameter boreholes. From the furthest downslope piezometer, the water surface was assumed to gradually descend towards, and daylight at the toe of, the slope just above the back beach.

Building Load – We modeled the proposed residential development loads assuming two parallel continuous point loads of 850 lbs, 20 feet apart, for the proposed residential foundation piers.

4.5 **Analysis Results**

Back-Calculation - We began our slope stability analysis by performing a back-calculation to determine shear strengths for forward analyses by assuming the existing area of the slope comprised of the 1978 landslide debris has a factor of safety slightly above unity ($FS = 1.01$), since the 1978 landslide is not presently moving. Consequently, for development of areas of the site within the active landslide boundaries, our goal was to raise the factor of safety from the current $FS = 1.01$ to industry accepted factors of safety of $FS \geq 1.5$ static and $FS \geq 1.1$ to 1.2 seismic (pseudo-static with a seismic coefficient of 0.15). The back-calculated condition represents Run 1 in the following Table 3. In this table, SSA stands for Slope Stability Analysis, SP stands for Shear Pin shear capacity needed, TB stands for Tieback pullout resistance capacity needed, k stands for seismic coefficient and FS stands for Factor of Safety.

TABLE 3 – SLOPE STABILITY ANALYSIS RESULTS

SSA Run #	Slope Condition Analyzed	Lower SP Wall (kips)	Upper SP Wall (kips)	TB (kips)	FS
1	Back-Calculation of existing slide debris surface	N/A	N/A	N/A	1.01
2	Slide debris In place (Critical Surface obtained from post-construction condition Run 5)	N/A	N/A	N/A	2.38
2A	Potential bedding failure with slide debris in place	N/A	N/A	N/A	2.41
3	Same as Run 2, but with slide debris removed (Critical Surface obtained from post-construction condition Run 5)	N/A	N/A	N/A	1.66
3A	Potential bedding failure with slide debris removed (same Critical Surface as Run 2A)	N/A	N/A	N/A	1.96
3B	Deep Block Search with debris removed	N/A	N/A	N/A	1.58
4	Shallow Surface from Run 7, no SP or slide debris	N/A	N/A	N/A	1.39
4A	Same as 4, but with slide debris in place	N/A	N/A	N/A	1.88
5	Critical Deep Surface, post construction of SP walls/ TBs / house loads, slide debris removed downslope of lower SP	40	50	100	1.68
6	Same Critical Surface and construction as Run 5, Seismic with $k=0.15$	40	50	100	1.23
7	Potential failure through upper shear pin wall (post construction, slide debris removed downslope of lower SP)	40	50	100	2.15
8	Same as Run 7, now with seismic $k=0.15$	40	50	100	1.24
9	Same as Run 5, with landslide debris in place downslope of lower SP	40	50	100	2.42
10	Same as Run 5, with landslide debris in place downslope of lower SP, now with seismic $k=0.15$	40	50	100	1.66

Forward Analyses - With the landslide debris evacuated, we conducted a slope stability analysis to determine what the most likely hypothetical deep failure surface (that deep basal shear surface geometry with the lowest factor of safety) would be with the upper portion of the parcel developed and stabilized (Run 5, $FS = 1.68$, in the table). Run 2 ($FS = 2.38$) represents an analysis of the factor of safety of this fully developed

weakest potential shear surface if the landslide debris were still in place (not evacuated) and Run 2A (FS = 2.41) represents a search for the lowest factor of safety for a potential bedding plane failure with the landslide debris in place.

Also using the most like hypothetical failure surface from Run 5, Run 3 (FS = 1.66) represents what the factor of safety for this surface drops to if the landslide debris were to be fully evacuated, Run 3A (FS = 1.96) represents what the potential bedding plane failure factor of safety determined in Run 2A drops to if the landslide were to fully evacuate, and Run 3B (FS = 1.58) represents an analysis of the potential for a deep-seated landslide to develop with the landslide debris evacuated using a deep block search.

With the landslide debris evacuated, we also conducted a slope stability analysis to determine what the most likely shallow upslope hypothetical failure surface (that shallow basal shear surface geometry with the lowest factor of safety) would be with the upper portion of the parcel developed and stabilized (Run 7, FS = 2.15, in the table). Run 4 (FS = 1.39) represents an analysis of what the factor of safety for this shallow surface drops to if the landslide debris has evacuated and there are no shear pin walls constructed. Run 4A (FS = 1.88) represents the same analysis as Run 4, but with the landslide debris still in place.

As discussed above, Run 5 (FS = 1.68) represents an analysis of the most critical deep-seated failure potential of the slope if the parcel is developed with two shear pin walls (the lowermost of which also has tiebacks) and the landslide debris has been fully evacuated. Run 6 (FS = 1.23) is the pseudo-static analysis factor of safety of Run 5 using a seismic coefficient of $k = 0.15$.

As also discussed above, Run 7 (FS = 2.15) represents an analysis of the most critical shallow upslope (in the vicinity of the upper shear pin wall) failure potential of the slope if the parcel is developed with two shear pin walls (the lowermost of which also has tiebacks) and the landslide debris has been fully evacuated. Run 8 (FS = 1.24) is the pseudo-static analysis factor of safety of Run 7 using a seismic coefficient of $k = 0.15$.

Run 9 (FS = 2.42) is the same analysis as Run 5 (deep-seated stability), but with the landslide debris still in place as it is today and Run 10 (FS = 1.66) is the same analysis as Run 6, but with the landslide debris still in place as it is today. These runs should represent the static (FS = 2.42) and seismic (FS = 1.66) factors of safety of the developed portion of the parcel immediately after development. Should the existing remaining

portion of the 1978 landslide reactivate and move downslope in the future, this deep-seated factor of safety for the developed portion of the property will decline, but should not decline below the levels of Run 5 (static FS = 1.68) and Run 6 (seismic FS = 1.23).

Worst Case Condition – We performed an analysis of what could be considered the worst case condition for slope instability of the upslope portion of the property by conservatively assuming that the 1978 landslide mass fully reactivated, mobilized and evacuated from the site to be eroded by coastal processes, and thus would no longer provide a buttress for the remaining slope to its landward side. This analysis indicated that, if the landslide debris evacuates, the remaining slope would have a reduced FS. Depending on the hypothetical failure surface analyzed, the FS could be reduced by as much as 30%. To relate this analysis to the proposed project, we chose the most critical hypothetical failure surface determined for deep-seated slope stability of the developed portion of the property with the landslide mass completely gone as discussed above with results listed in Table 3.

Shear Pin Walls with Tiebacks Installed for Stabilization – We performed numerous analysis iterations in which we varied the number of shear pin rows, shear pin resistance, number of tieback rows, and tieback tensions until the static factor of safety was above 1.5 for all hypothetically searched (both shallow and deep) potential failure surfaces. These analyses culminated in the design concept analyzed as described above with results listed in Table 3.

Shear Pin with Tiebacks Installed for Stabilization and a Seismic Coefficient – We fixed (held in place) the hypothetical critical surfaces found under the static loading conditions, and performed psuedo-static analyses using a seismic coefficient of $k = 0.15$. We again modified the shear pin resistance and tieback tensions until we achieved a seismic (pseudo-static) factor of safety greater than or equal to 1.1 to 1.2. These analyses culminated in the design concept analyzed as described above with results listed in Table 3.

Required Shear Pin Capacity – Our analysis indicates that satisfactory factors of safety ($FS \geq 1.5$ static and $FS \geq 1.1$ to 1.2 pseudo-static) can be achieved at 1925 ECDLL by installing two rows of 40-foot deep shear pins (steel-reinforced cast-in-drilled-hole piers) with an allowable (service) shear capacity of 40 kips for the lower row and 50 kips for the upper row, and spaced at 6-foot on-centers. The upper row would be installed roughly 40 feet south of the east-west property line between 1925 and 1927 El Camino

De La Luz (near grade elevations 113 to 116 feet), while the lower row of shear pins would be located approximately 77 feet further south of the upper row, or approximately 117 feet south of that east-west property line (near grade elevations 90 feet).

Required Tieback Capacity – Our analysis indicates that satisfactory factors of safety ($FS \geq 1.5$ static and $FS \geq 1.1$ to 1.2 pseudo-static) can be achieved by equipping the lower shear pins with one row of 65-foot long, 100-kip (design load) tensioned tiebacks declined at 20 degrees from horizontal upslope and located 7 feet down from the top of the shear pin.

Should the 1978 landslide mass reactivate, the lower shear pin wall has been designed to protect the building envelope from adverse slope stability impacts. Additionally, it is our opinion that there will be a sufficient lateral improvement in slope stability beyond the upcoast (west) and downcoast (east) edges of the shear pin wall to shield the subject parcel from adverse slope stability impacts associated with such an event.

Horizontal Drains – We recommend that horizontal drains, with clean-outs, be installed along the lower shear pin wall. The drains should be spaced approximately 18 feet apart, be inclined 2-degrees upslope, and extend a minimum of 100 feet into the slope in roughly a north-south direction, or perpendicular to the shear pin wall. Cleanouts should be installed at the collar of each drain, and each drain should feed into a collector pipe that discharges into a collection basin for reuse in residential landscaping, or into an appropriate storm drain pipe.

5.0 CONCLUSIONS REGARDING GEOLOGIC CONSTRAINTS AND GEOTECHNICAL FEASIBILITY OF RESIDENTIAL CONSTRUCTION

Based on our engineering geologic and geotechnical engineering investigation, it is our opinion that the northern portion of the 50-foot wide flag subarea on the flag lot parcel at 1925 El Camino De La Luz is suitable for proposed residential development provided that the recommendations of this report are incorporated into the design, construction, and operation of the project during its 75-year economic life. The proposed conceptual residential re-use building envelope, between (and within) elevations +90 and +130 feet MLLW, at 1925 El Camino De La Luz, Santa Barbara, California would be located upslope of the majority of the 1978 landslide debris and mostly within the relatively stable bedrock materials along the headscarp of the 1978 landslide. The proposed residential development envelope is located a minimum of 150 feet from (north of) the top of the coastal bluff on the subject parcel, and thus is and will be set back sufficiently from it during the 75-year economic life of the development in order to meet all applicable adopted setback standards, assure stability and structural integrity, minimize risks to life and property, and neither create, nor contribute significantly to, erosion, geologic instability, or destruction of the site or surrounding area. The proposed residential structure does not require the construction of protective devices that would substantially alter any natural bluff or cliff landforms, and none are proposed in this report or the coastal hazards/wave runoff report by GeoSoils, Inc. for the subject parcel.

The City, in or about August-September, 1978, graded the 1978 ECDLL landslide on the subject parcel between elevations 60 and 130 feet, during which it partially buried the 1978 landslide headscarp with a shallow layer of artificial fill that constitutes non-engineered fill for foundation design recommendation purposes. We interpret the 1978 ECDLL landslide to have been a translational rockslide that failed along a pre-existing (i.e., pre-historical aerial imagery) landslide shear surface associated with an older landslide observed in the historical aerial photographs. There is no evidence in the subsurface or in the aerial photographs for an old landslide upslope (north) of the 1978 ECDLL landslide. From a geologic and geotechnical perspective, it is our opinion that a residential structure can be safely constructed within the proposed conceptual building envelope on the property, provided that the recommended deep foundation and subgrade landform stabilization shear pins, tiebacks and drains are incorporated into the residential reuse project plans for 1925 El Camino De La Luz.

We have generated Engineering Geologic Cross Section A-A' through the central portion of the subject parcel to illustrate our interpretation of the geologic conditions and landslide geometry based on the results of our surface and subsurface exploration. The intent of the residential re-use building plan would be to construct the residence, and appurtenant structures, on the upper 50-foot wide flag portion of the flag lot parcel, upslope from most of the 1978 landslide debris, and with deep stabilization elements [i.e., shear pins (steel reinforced concrete caissons) with tiebacks for the lower row of pins]. This construction would likely include some minor temporary grading (estimated at approximately 200 cubic yards) necessary for pier and grade beam footings and tieback installation. The stability of the hillside upslope from the stabilization elements would be improved to the industry standard static and pseudo-static Safety Factors. Drainage control measures, both surface and subsurface, would be implemented at the parcel, including through interception of water for beneficial on-site reuse. In addition, the residential construction of the parcel should provide slope stability and drainage benefits to nearby residences, utilities, and the driveway upslope by increasing the factor of safety of the upslope area to minimum $FS \geq 1.5$, and by preventing uncontrolled surface runoff from adversely impacting the existing landslide. Additionally, the horizontal drains should help reduce the risk of groundwater rise in the upslope area. Landform stabilization and residential reuse can occur at the subject parcel independently from adjacent parcels within the 1978 ECDLL landslide, all of which are under separate legal ownership from one another. CSA does not consider a seawall nor other shoreline protective structures to be necessary or required for the residential re-use of 1925 El Camino De La Luz, and none are recommended.

5.1 Potential Geologic Hazards

In our opinion, the potential primary engineering geologic and geotechnical constraints to residential reuse of the parcel at 1925 ECDLL are: 1) the potential for future instability in the oxidized Monterey Formation upslope of the 1978 landslide; 2) the potential for reactivation of the 1978 landslide in the middle/southern portion of the portion of the parcel, upslope from the top of coastal bluff; 3) the potential for translational landsliding incorporating both the upslope oxidized bedrock and unoxidized bedrock in the lower portion of the slope; 4) very strong seismic ground shaking associated with an earthquake along one of several nearby active faults; and 4) saturation of expansive earth materials. A detailed discussion of the geologic hazards and their potential to impact the site **follows:**

5.1.1 Landsliding - The primary engineering geologic constraint at this site is the 'dip slope' bedrock condition, which provides the potential for shallow to moderately deep landsliding to occur in bedrock along weak bedding planes. This dip slope condition results in the northern portion of the site having a safety factor, at present (2012), of less than 1.5. It should be noted that this condition extends upslope to include the City's Mesa Trunk Line Sewer, the driveway, and likely other residential properties located on shallow foundations along the headscarp of the 1978 landslide. For residential development of the parcel, mechanical, drainage and/or grading improvements are required to achieve a Safety Factor equal to or greater than 1.5. These improvements, while necessary to assure a stable building site, would also provide substantial stability benefits for the adjacent residentially developed upslope parcels, utilities, and infrastructure. For all of the above reasons and analyses, it is our opinion that the proposed development concept is consistent with the requirements of the State-certified City LCP, that new development shall both minimize risks to life and property in areas of high geologic, flood, or fire hazard, and assure stability and structural integrity, and neither create nor contribute significantly to erosion, geologic instability, or destruction of the site or surrounding area or in any way require the construction of protective devices that would substantially alter natural landforms along bluffs and cliffs.

By improving the drainage conditions and increasing the factor of safety of the hillside at the proposed residential development, as well as contributing to enhanced upslope and downslope landform stability, risks to life and property would be reduced (not only for this property but adjacent properties as well), stability and structural integrity would be assured, and the proposed development would in no way contribute to erosion or geologic instability. The placement of the residential structure in the northern portion of the 50-foot wide parcel would not constitute the stabilization of a natural landform along a bluff since this area was previously graded by the City in 1978 and in part under a coastal permit issued by the Coastal Commission in 1984, and the coastal bluff is located over 150 feet downslope of the proposed building envelope.

5.1.2 Reactivation of the 1978 Landslide – Reactivation of the 1978 landslide in some form is likely in the future, just as the 1978 ECDLL landslide was a reactivation of a previous landslide at this location. However, the present landslide debris associated with the 1978 landslide is in a relatively low slope position relative to the landslide headscarp. The proposed building envelope on the subject parcel is located largely upslope of this landslide debris and should not be impacted should the 1978 landslide

debris reactivate (in contrast to the 1978 landslide condition where the residences straddled the contact between intact rock and landslide debris). Additionally, geotechnical recommendations for residential improvements upslope of the landslide debris have been generated assuming, conservatively, that the 1978 landslide debris has completely evacuated and is thus incapable of providing any measure of buttressing stabilization for the upslope areas. It is our opinion that this is a conservative approach since the 1978 landslide debris has moved to a much lower slope position onto a failure plane that is shallower than the failure plane at the headscarp, and thus, should have less driving force now than the landslide had before the 1978 movement. Additionally, the western upper portion of the landslide has been stabilized with a keyed and benched fill and our recommendations for development of the upper portion of 1925 ECDLL include retaining an upper portion of the 1978 landslide, improved surface drainage that is intended to capture most of the rainfall and runoff in the developed area and the installation of horizontal drains to intercept and capture subsurface drainage near the upper portion of the 1978 landslide. Thus, it is our opinion that the 1978 landslide debris, while likely to experience slow creep in the future, is less likely to experience large-scale, deep-seated landslide movement similar to that which occurred in 1978. Even if it were to move more rapidly, it should not adversely impact the proposed development at 1925 ECDLL, since we have modeled the site assuming that this material has already completely evacuated.

5.1.3 Seismic Ground Shaking – The proposed residential development will likely experience strong and possibly violent seismic ground shaking during its 75-year design life, which has the potential to adversely impact residential structural integrity as well as to initiate landslides. Provided that the structure is designed to current building codes and the foundation design recommendations of this report are incorporated into the design, construction and operation/maintenance of the residence, seismic ground shaking presents a low risk to the proposed residential development.

5.1.4 Expansive Earth Materials – Potentially expansive earth materials, both surficial soil and bedrock materials, could produce adverse impacts to residential structures not designed to resist forces generated by expansion. Expansive surficial soil materials can experience volume increases with an increase in moisture, and volume decreases as moisture conditions decrease, resulting in the potential for distress to structures built on shallow foundations. Expansive surficial soil materials typically are susceptible to rapid soil creep, that can transport shallowly founded structures downslope over time. In addition, expansive bedrock materials can exert uplift

pressures on shallowly founded piers. Provided the foundation recommendations of this report are incorporated into the design, construction, and operation/maintenance of the residential structure and appurtenances, expansive earth materials present a low risk to the development.

5.1.5 Tsunami/Wave Run-up Hazards – The proposed development envelope is between elevations 90 feet and 130 feet, and thus, outside of the anticipated tsunami/wave run-up inundation zones during the 75-year economic life of the residence. A more thorough discussion of the tsunami and wave run-up hazards is presented in the Geosoils, Inc. report (2012) for this parcel.

6.0 GEOTECHNICAL DESIGN RECOMMENDATIONS

6.1 Foundation Design Considerations

The principal factors affecting foundation selection are the variable thickness of landslide debris underlying the downslope side of the residential reuse area on the subject parcel, the weaker weathered bedrock, and the potentially weaker bedding planes of both the unweathered and weathered bedrock. We have provided recommendations for protecting the proposed residential reuse envelope (which is primarily upslope of the 1978 landslide) with two (upper and lower) rows of shear pins designed to minimize potential landslide impacts. The lower row of shear pins will include one row of tiebacks, whereas the upper row will not need to be equipped with tiebacks. The upper shear pin row is shown to be at approximate elevation 113 feet, but can be moved upward or downward slightly to accommodate the residence foundation layout (see Figures 7 and 8, Conceptual Slope Stabilization Plan and Conceptual Slope Stabilization Cross Section A-A', respectively). In addition, upslope of the tied-back row of shear pins, we are recommending a drilled, cast-in-place pier and grade beam foundation system for the proposed residence with piers extending a sufficient depth (20 feet) into intact bedrock.

6.2 Foundation Design Criteria

6.2.1 Cast-in-Place Drilled Piers - The residence and garage should be supported on reinforced concrete piers. The drilled, cast-in-place piers should derive vertical support from adhesion (skin friction) in competent, intact bedrock as determined in the field by the Project Engineering Geologist/Geotechnical Engineer at the time of construction. Residential design may utilize the upper shear pins as part of the foundation support, as deemed appropriate by the Project Structural and Geotechnical Engineers. Piers should be sized according to the following criteria:



Vertical Capacity - minimum three (3) pier-diameter spacing apart


Minimum pier diameter_____18 inches



Minimum pier penetration into competent weathered bedrock____20 feet


Allowable adhesion (skin friction), for reinforced concrete dead plus live loads:

In weathered bedrock_____475 psf



 COTTON, SHIRES AND ASSOCIATES, INC. CONSULTING ENGINEERS AND GEOLOGISTS		
CONCEPTUAL SLOPE STABILIZATION PLAN		
1925 El Camino De La Luz Santa Barbara, California		
GEO/ENG BY JW	SCALE 1"=30'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	FIGURE NO. 7



 COTTON, SHIRES AND ASSOCIATES, INC. CONSULTING ENGINEERS AND GEOLOGISTS		
Conceptual Slope Stabilization Cross Section A-A' 1925 El Camino De La Luz APN:045-100-024 SANTA BARBARA, CALIFORNIA		
GEO/ENG BY JD	SCALE 1"= 30'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	FIGURE NO. 8

Lateral Passive Resistance - piers [equivalent fluid pressure applied over an effective width of two (2) pier diameters]

Below 2 feet in weathered bedrock material_____450 pcf

The above adhesion value (skin friction) can be increased by 1/3 for seismic loading and should be decreased by 1/2 for uplift. The upper portion of the piers should be formed to create vertical surfaces, and “mushrooming” of pier tops and over-pours around grade beams should be prevented. Drilled pier holes should be machine cleaned of all loose material prior to the placement of steel and concrete. Piers should be steel reinforced with a cage including a minimum of 4, No. 5 bars vertical (with greater reinforcement as required by the Project Structural Engineer). Casing could be necessary to prevent caving, especially in soils or landslide debris.

Water may be present in the pier holes, consequently, prior to placing concrete, the water should be pumped out until the pier holes are dry, or the concrete should be poured by tremie methods to displace the water. All pumped water and/or concrete overspill should be collected so as not to run freely across the ground surface and be disposed of offsite and outside of the coastal zone. All piers should be connected at their tops by a continuous structural slab/mat that in turn will support the structure.

6.2.2 Shear Pins – Shear pins should have a minimum diameter of at least 30 inches, and be at least 40 feet long (deep). In addition, the shear pins on the lower row should extend a minimum of 30 feet into unweathered bedrock or beneath the pad subgrade (whichever is deeper). Both shear pin rows (upper and lower) should consist of drilled, cast-in-place reinforced concrete piers that derive passive resistance to lateral forces in firm bedrock material, and be spaced at maximum 6 feet on-centers. Our analysis indicates that the shear pins should be designed to provide a minimum landslide resistant shear capacity of 40 kips (6.67 kips/ft) applied as a point load at a depth of 15 feet below top of shear pin for the lower row and a minimum landslide resistant shear capacity of 50 kips (8.33 kips/ft) 20 feet below top of shear pin for the upper row, or as a uniform load of 444 psf applied over a depth of 15 feet for the lower row and 417 psf applied over a depth of 20 feet for the upper row (analyze for both types of loading separately, and use the most critical case for design for each row).

The lateral loads can be resisted by passive pressure against the side of the shear pins using the Lateral Passive Resistance recommendation provided in Section 6.2.1, Cast-in-Place Drilled Piers, in the preceding recommendations, and tiebacks as described in the

following recommendations. A traffic surcharge of 250 psf uniform pressure should be included and applied against the top 10 feet of the piers and shear pins where the driveway/garage is within a 1:1 projected line up from a depth of 10 feet. Shear pins can be constructed using either wide flange steel beams or reinforcing bars (minimum of 9, No. 9 evenly spaced vertical bars encased by No. 3 spiral with a 3-inch pitch or greater reinforcement as required by the Project Structural Engineer).

6.2.3 Tiebacks – Our analysis indicates that the lower shear pin row should be equipped with at least one row of tiebacks located 7 feet below the existing ground surface and have a design capacity of 100 kips, and be tested to 1.33 times the design load. The tiebacks should be declined 20 degrees upslope and into the hillside, have an unbonded length of roughly 35 feet and have a minimum bonded length of 30 feet (or greater as determined by the tieback contractor in order to achieve design and testing capacities) in the unweathered bedrock, and should not extend beyond the east-west property line of 1925 El Camino De La Luz with 1927 El Camino De La Luz which is 117 feet landward of the lower shear pins. The tiebacks should be structurally connected to the shear pins and be double corrosion protected. The design adhesion in the bonded zone should be determined by the tieback contractor.

6.3 Mat Floor Foundation

For a mat foundation, the subgrade should be prepared as recommended under Site Grading (Section 6.4). The mat should be at least 12 inches thick and reinforced with minimum No. 4 steel reinforcing bars at maximum 16 inches on center, both ways, and crack control joints should be provided at maximum 12-foot intervals, both ways. Steel reinforcement may be increased and expansion joints may be added as required by the Project Civil or Structural Engineer.

6.4 Site Grading

Based on our field investigation, shallow grading excavations should be within the capabilities of heavy-duty excavation equipment (i.e., excavators, dozers, and large drill rigs); however, deeper excavations may require “ripping” and/or a “hoe-ram” to excavate. It should be noted that we encountered high blow counts in our small-diameter borings and very difficult drilling conditions in the large-diameter borehole exploration in the unweathered bedrock material.

6.4.1 Site Preparation - All loose material, vegetation, concrete, large rocks, debris, and other deleterious material, without limit, should be stripped and removed from the development envelope on the parcel, for disposal offsite and outside the coastal zone pursuant to applicable entitlement or license. In areas on the parcel to be filled, the exposed surface should be scarified to at least an 8-inch depth, moisture conditioned to at least optimum moisture content and compacted to at least 90 percent relative compaction based on ASTM D-1557-12. The subgrade beneath all fills should be keyed and benched as the fill is placed and brought upslope.

6.4.2 Compacted Fill – Excavated on-site material can be re-used as compacted fill provided it is free of organic matter and material (rocks) larger than 4 inches in diameter. Imported fill should be free of organic material and be certified weed free; it should contain no material larger than 4 inches and should have a plasticity index (P.I.) of less than 16. The fill should be placed in horizontal lifts not exceeding 8 inches in loose thickness, moisture conditioned to at least optimum moisture content, and compacted to at least 95 percent relative compaction beneath structures, slabs and within 18 inches of the aggregate baserock for pavements, and 90 percent relative compaction elsewhere based on ASTM D-1557-12.

6.4.3 Utility Trench Backfill - Utility trenches should be backfilled with approved, on-site soil. Bedding materials for pipes should be graded and placed in accordance with the manufacturer's recommendations. The backfill should be compacted to at least 90 percent relative compaction based on based on ASTM D-1557-12. Equipment and methods should be used that are suitable for work in confined areas without damaging trench walls or conduits.

6.4.4 Cut Slope Design – During the dry season, temporary cut slopes of 1.5:1 (H:V) in soils and 1:1(H:V) in bedrock should be satisfactory provided that they are inspected and approved by our field representative at the time of construction and monitored daily during construction. However, due to the dip slope bedding planes, some cuts may not be stable, and may require shoring regardless of inclination. Excavation methods, shoring, bracing and safety of excavations are the responsibility of the contractor. All excavations should comply with applicable local, State and Federal safety regulations.

6.5 Retaining Wall Designs

The following section provides our recommendations for design of site retaining walls.

6.5.1 Retaining Walls – Retaining walls should be supported on drilled, cast-in-place piers and designed according to the Foundation Design Criteria (Section 6.2.1) provided above. The retaining walls that are free to rotate should be designed to resist an active lateral equivalent fluid pressure of 50 pounds per cubic foot (pcf) for the existing slope inclination (we should be contacted in the event that backfill inclinations will exceed the existing 2.25:1 slope). The above active lateral fluid pressures should be increased by 50% for walls that are restrained from rotation (residential walls). The lateral loads on the retaining wall can be resisted by passive pressure against the sides of the piers using the lateral passive resistance provided both in foundation design criteria, above. For seismic loading, a dynamic resultant force acting at $1/3H$ up from the bottom of the wall and equal to an equivalent fluid pressure of 16 pcf should be applied to all residential retaining walls greater than 5 feet in height and any site walls located within a horizontal distance to the residence of the wall height or less.

6.5.2 Backdrain - Backdrains should be constructed behind all retaining walls. The backdrain should consist of a minimum 12-inch wide continuous blanket of either Caltrans Class 2 Permeable Material or 3/4-inch x 1/2-inch clean crushed drainrock enclosed in Mirafi 140N (or approved equivalent) filter fabric, and extended to within 1 to 1-1/2 feet of the ground surface where an impervious fill and/or asphaltic concrete cap should be placed. A minimum 4-inch diameter PVC Schedule 40 perforated drain pipe should be placed near the bottom of the drainrock (perforations down), surrounded by a minimum of 4 inches of drainrock with at least 2 inches of drainrock underlying the pipe. All backdrain pipes should be sloped to drain at a minimum of 1/2 percent and be collected in 4-inch diameter, non-perforated Schedule 40 PVC pipes which are sloped a minimum of 2 percent and discharged away from the landslide and in a suitable area which won't result in erosion.

6.6 Slabs-on-Grade and Concrete Flatwork

Slabs-on-grade and concrete flatwork subgrades should be prepared as recommended in Site Grading, above. Slab-on-grade floors, including the garage, should be directly underlain by at least 6 inches of clean, crushed drain rock (100 percent passing the 3/4-inch sieve; 0-2 percent passing the No. 4 sieve, and 0 percent passing the No. 200 sieve) except in areas of the bottom floor subdrain which should have a thicker section (See Drainage section below for mat subdrain design). For damp-proofing of the slab, a layer

of Moistop Underslab Vapor Retarder or Stegowrap should be provided over the capillary break (gravel or crushed rock).

Concrete flatwork (sidewalks, patios, etc.) should be supported on at least 6 inches of moist, compacted Caltrans Class 2 Aggregate Base rock material. The 6 inches of compacted base rock material should, in turn, be underlain by compacted fill or firm natural material.

Slabs and flatwork should be steel reinforced with at least No. 4 bars at 18 inches on centers each way (or greater reinforcement as determined by the Project Structural Engineer), and provided with crack control joints at maximum 10 feet on centers, both ways.

6.7 Drainage

Because of the detrimental influence of water as it interacts with soil, bedrock, foundations, pavements, and cut and fill slopes, it is important that surface water be controlled. Grades should be sloped to drain at a minimum of 2 percent for a distance of at least 10 feet out from structures with runoff directed into an appropriate catch basin/storm drain system. All roof runoff should be collected in gutters with downspouts tied into tightline pipes (Schedule 40 PVC) that also discharge into a catch basin/storm drain. The catch basin/storm drain should discharge into the property and City storm drainage system.

Where concrete curbs are used to isolate landscaping in or adjacent to pavement areas, we recommend that the curb extend a minimum of 8 inches into low permeable material below the baserock to provide a barrier against the migration of landscape water into the pavement section.

6.7.1 Sub-Floor Mat/Slab Subdrains – The mat/slab-on-grade floor should be underlain by a minimum 6-inch thick blanket of clean, free-draining crushed rock or gravel as specified in Slab-on-Grade and Concrete Flatwork sections, above. The blanket subgrade should be cut to drain (hydraulically connected) to one of the sub-floor subdrains which should be spaced at minimum 30-foot intervals and extend across the entire slab. The sub-floor slab subdrains should consist of a 4-inch diameter perforated Schedule 40 PVC pipe sloped a minimum of 1/2 percent and placed in a minimum 12-

inch wide, 6- to 18-inch deep or deeper (depending on the dimensions of the sub-floor) trench filled with crushed rock or gravel and a sheet of filter fabric separating the gravel from the blanket subgrade. There should be 2 inches of drainrock in the bottom of the trench, below the pipe. The subdrain pipes should be collected in 4-inch diameter, non-perforated Schedule 40 PVC pipes sloped a minimum of 2 percent and discharged either directly into the storm drain system by gravity outlet, or drained into a sump(s) equipped with a pump(s) which in turn flow into the property storm drainage system. The retaining wall backdrains should also be collected and drained in a similar manner as the sub-floor slab subdrain, or combined, if preferred. Clean-outs should be provided at both ends of each the sub-floor slab subdrain. Surface water should not be discharged into subdrain pipes.

6.8 Seismic Design

A peak ground acceleration of 0.44 g should be anticipated for design purposes.

Based on our geotechnical investigation, the site location and our interpretation of the 2007 CBC documents related to Earthquake Loads (CBC Section 1613), we are providing the following parameter recommendations from the corresponding figures and tables:

Parameter	Referenced Table/Figure/Eqn.	Value
Site Classification	1613.5.2	C
Mapped Spectral Acc. 0.2 Sec. (g)	1613.5(3)	$S_s = 1.890$
Mapped Spectral Acc. 1 Sec. (g)	1613.5(4)	$S_1 = 0.711$
F_a – Site Coefficient	1613.5.3(1)	1.0
F_v – Site Coefficient	1613.5.3(2)	1.3
Seismic Design Category	1613.5.6	D
$S_{MS} = F_a S_s$	16-37	1.890
$S_{M1} = F_v S_1$	16-38	0.924
$S_{DS} = 2/3 S_{MS}$	16-39	1.260
$S_{D1} = 2/3 S_{M1}$	16-40	0.616

6.9 Horizontal Drains

We recommend horizontal drains be installed along the lower shear pin wall. The drains should be spaced approximately 18 feet apart to avoid the upper shear pin wall, be inclined 2-degrees upward upslope, and extend a minimum of 100 feet into the slope. The drain outlets should be connected to tightline collector pipes and discharge into the newly established storm drain system designed to capture the residential runoff. The horizontal drains should be equipped with cleanout access ports, and the drains should be periodically flushed and inspected at a maximum of 5-year intervals.

7.0 INVESTIGATION LIMITATIONS

Our services consist of professional opinions and recommendations made in accordance with generally accepted engineering geology and geotechnical engineering principles and practices. No warranty, expressed or implied, or merchantability of fitness, is made or intended in connection with our work, by the proposal for consulting or other services, or by the furnishing of oral or written reports or findings.

Any recommendations and/or design criteria presented in this report are contingent upon our firm being retained to review the final drawings and specifications, to be consulted when any questions arise with regard to the recommendations contained herein, and to provide testing and inspection services for earthwork and construction operations. Unanticipated soil and geologic conditions are commonly encountered during construction and cannot be fully determined from existing exposures or by limited subsurface investigation. Such conditions may require additional expenditures during construction to obtain a properly constructed project. Some contingency fund is recommended to accommodate these possible extra costs.

This report is issued with the understanding that it is the responsibility of the owner, or of his representative, to ensure that the information and recommendations contained herein are called to the attention of the project engineer and incorporated into the plans. Furthermore, it is also the responsibility of the owner, or of his representative, to ensure that the contractor and subcontractors carry out such recommendations in the field.

8.0 REFERENCES

8.1 Documents/Maps

Aero Service Corporation, 1965, Topographic Base Map, City of Santa Barbara and the County of Santa Barbara Flood Control and Water Conservation District, 1"=200'.

Blake, T. F., 1989, EQFAULT: A computer Program for the Deterministic Prediction of Peak Horizontal Acceleration from Digitized California Faults, IBM-PC Version, Users Manual, July, 1989.

Blake, T.F., Hollingsworth, R.A., and Stewart, J.P., June 2002, Recommended Procedures for Implementation of DMG Special Publication 117 Guidelines for Analyzing and Mitigating Landslide Hazards in California.

Buena Engineers, 1983, Landslide Treatment at 1933 El Camino De La Luz, Santa Barbara, California, May 5, 1983.

Buena Engineers, Inc., 1983, Soils and Geologic Report, Doolittle, May 5, 1983.

California Coastal Commission, 1984, CDP 4-84-17 (Doolittle et al.)

California Department of Conservation Division of Mines and Geology, 1997, Special Publication 117: Guidelines for Evaluating and Mitigating Seismic Hazards in California.

California Department of Conservation Division of Mines and Geology, 2002, Recommended Procedures for Implementation of DMG Special Publication 117 Guidelines for Analyzing and Mitigating Landslide Hazards in California.

California Division of Mines and Geology, 1996, California Fault Parameters, DMG Open File Report 96-08.

Campbell-Geo, Inc., 2007, Geologic/Preliminary Geotechnical Evaluation, Monteabaro Property, 1927 El Camino De La Luz, March 5, 2007.

City of Santa Barbara, 2006, Draft EIR on the 1837 1/2 El Camino de la Luz Residence.

City of Santa Barbara, 1978, Geologic, Seismic Hazard, Liquefaction Hazard, Soil Creep and Expansive Soil Hazards, and Erosion Hazard maps, prepared by Michael Hoover, October 17, 1978, Scale = 1:12,000.

- City of Santa Barbara, 1979, Seismic Safety Element of the General Plan (1979).
- City of Santa Barbara, 2004, Local Coastal Plan, 1981, Amended November 2004.
- City of Santa Barbara, 2007, Neighbor's Photo Album of 1978 ECDLL Landslide, submitted in 2007 to City Community Development Department.
- City of Santa Barbara, 2011. General Plan Update.
- Cook, L. P., 2006, Boundary and Topographic Survey, 1925 El Camino De La Luz.
- Dibblee, T.W., 1986, Geologic Map of the Santa Barbara Quadrangle, Santa Barbara County, California, Dibblee Foundation Map DF-06, Scale = 1:24,000.
- Fairchild Aerial Photograph Collection, Whittier College, 1929, 1938, and 1950.
- Geosoils, Inc., 2012, Wave Runup & Coastal Hazard Analysis, 1925 El Camino De La Luz, Santa Barbara, California (APN 045-100-024).
- Gurrola, L.D., et al, 2003, Active Tectonics and Earthquake Hazards of the Santa Barbara Fold Belt, Southern California Earthquake Center Field Trip Guide Book, September, 7.
- Hoek, E., and E. T. Brown, 1997, Practical Estimates of Rock Mass Strength: International Journal of Rock Mechanics and Mineral Science, vol. 34, no. 8, p. 1165-1186.
- Hoek, E. and Bray, J.W., 2001, Rock Slope Engineering, 3rd Edition, The Institute of Mining and Metallurgy.
- Hoover, Michael, 2007, Letter to City of Santa Barbara on behalf of his clients November 2.
- Idriss, I. M., 1987, Lecture Notes, Presentation at the EERI Course on Strong Ground Motion, April 10-11, 1987, Pasadena, California, in Singh, J. P., Course Organizer, Strong Ground Motion, Seismic Analysis, Design, and Code Issues: Earthquake Engineering Research Institute, 14 pp.
- Johnson, M. J., 2002, Establishing Development Setbacks From Coastal Bluffs, in Magoon, Orville et al; Proceedings, California and the World Ocean 2002, Reston, Virginia: American Society of Civil Engineers.

- Joyner, W. B., and Boore, D. M., 1981, Peak horizontal acceleration and velocity from strong-motion records including records from the 1979 Imperial Valley, California, earthquake: *Bulletin of the Seismological Society of America*, v. 71, p. 2011 - 2038.
- Keller, E.A., Gurrola, L.D., 2000, Earthquake Hazard of the Santa Barbara Fold Belt, California, Institute for Crustal Studies, U.C. Santa Barbara, California; NEHRP Award 99HQGR0081, and SCEC Award 572726.
- Krinitzsky E.L., F.K. Chang and O.W. Nuttli, 1988, Magnitude-Related Earthquake Ground Motions: *Bulletin of the Assoc. of Engineering Geologists*, Vol. XXV, No. 4, pp. 399-423.
- Minor, S.A., et al., 2006, Preliminary Geologic Map of the Santa Barbara Coastal Plain Area, Santa Barbara County, California, U.S. Geological Survey Open File Report OFR 02-136.
- Pacific Materials Laboratory, Inc., 1978, Preliminary Landslide Investigation, Sea Cliff Property El Camino Del La Luz, March 6, 1978.
- Padre Associates, Inc., 2006, Geotechnical Study, 1921 El Camino De La Luz.
- Padre Associates, Inc., 2007, Evaluation of Bluff Setback, 1921 El Camino De La Luz, Santa Barbara, California; May 9, 2007.
- Padre Associates, Inc., 2008, Retraction of Geotechnical Study, 1921 El Camino De La Luz, Santa Barbara, California; April 17, 2006.
- Peak Surveys, Inc., Slope Repair (Grading) Plan, Doolittle Residence, 1933 El Camino de la Luz, 1984.
- Rocscience, 2007, RocLab version 1.031.
- Scepan, Joseph, 2012, Coastal Bluff Position Aerial Photographic Analysis, 1950-2010, 1925 El Camino de la Luz, Santa Barbara, California.
- Smith, R.J., 1980, Engineering Geology of Subsurface Soils, 1927 Camino De La Luz, July 7.
- Terzaghi, K., and Peck, R.B., 1967, *Soil Mechanics in Engineering Practice*, John Wiley and Sons, Inc.
- Towill, Inc., and Penfield and Smith Engineers and Surveyors, 1997; Topographic Map of the City of Santa Barbara, Public Works Department.

U.S. Coast Survey, Survey of Point Near Santa Barbara for a Light House Site November, 1854, Register 470, 1:10,000 scale.

U.S. Coast and Geodetic Survey, Santa Barbara and Approaches, California, 1887 (October, 1898), Sheet 5261, 1:20,000 scale.

WRA, Inc., 2012. Biological Reconnaissance Report, 1925 El Camino de la Luz, Santa Barbara, California.

Wyllie, D.C., and Mah, C.W. 2004, Rock Slope Engineering, Civil and Mining, 4th Edition, Based Upon 3rd Edition by E. Hoek and J. Bray.

U. S. Department of the Navy, 1982, Design Manual Soil Mechanics, Foundations, and Earth Structures, NAVFAC DM-7.2.

U.S.G.S. Seismic Hazard Curves and Uniform Hazard Response Spectra Program, Version 5.0.9a, dated 02/10/2011.

U.S. Soil Conservation Service, Soil Survey of Santa Barbara County, California, South Coastal Part, February 1981.

Weaver, Donald W., February, 1978 El Camino de la Luz landslide (vertical aerial, Fig. 17.9).

Weaver, Donald W., 1982, Preliminary Landslide Hazards Evaluation, prepared for Mr. Robert Doolittle, 1933 El Camino de la Luz, Santa Barbara, California 93109, May 6.

8.2 Vertical Aerial Photographs (Stereo-pairs)

<u>Date</u>	<u>Source</u>	<u>Flight No.</u>	<u>Scale</u>
1929	Fairchild Collection	C-430-A-13, 14	1"=2,000'
1938	Fairchild Collection	C-4950	1"=2,000'
1950	Fairchild Collection	C-14500	1"=600'
1962	U.C. Santa Barbara	HA-01-80, 81	1"=1,000'
1975	U.C. Santa Barbara	HB-XQ-240, 241	1"=1,000'
1978	USDA	06083-178-7, 8	1"=1,000'

1983	Pacific Western	PW-SB-5-2, 3	1"=2,000'
1995	Pacific Western	PW-55010-25, 26	1"=1,000'
2005	Pacific Western		1"=1,000'

8.3 Oblique Aerial Photographs (Single-frame)

<u>Date</u>	<u>Source</u>
1972	California Department of Navigation and Ocean Development
1972	Coastal Records Project, California Coastline.org
1978	Weaver (1978)
1978	Coastal Records Project, California Coastline.org
1979	Coastal Records Project, California Coastline.org
1987	Coastal Records Project, California Coastline.org

APPENDIX A

FIELD INVESTIGATION

Topographic Surveying and Geologic Mapping

Logs of Small-Diameter Exploratory Borings

Logs of Large-Diameter Exploratory Borings

APPENDIX A

FIELD INVESTIGATION

Surveying and Geologic Mapping

The surface conditions of 1925 El Camino De La Luz were investigated by our engineering geologists and geotechnical engineers from 2008 to the present using total station theodolite surveying equipment, measuring tape and pace, Brunton compass and hand-level techniques. Cotton, Shires and Associates, Inc. (CSA) generated an original, detailed topographic base map of the parcel, with 2-foot contour intervals, in 2010 with total station theodolite surveying techniques. Outside of the parcel, we augmented our topography with the City-County topographic base map of 1997. This 2010 base map was used for our topographic profiling, engineering geologic mapping, and slope stability analysis.

Small-Diameter Exploratory Boreholes

The subsurface geologic conditions at 1925 El Camino De La Luz were explored by excavating three small-diameter boreholes in May 2011. In addition, two additional small-diameter boreholes were located on the adjacent parcel at 1921 El Camino De La Luz during the same time period. The small-diameter boreholes were excavated by Britton Drilling of Campbell, California, who primarily utilized mud-rotary, continuous coring methods; however, the upper portions of the boreholes within artificial fill, weathered bedrock and landslide debris were drilled using hollow-stem auger techniques. Retrieved cores from the borings were brought back to our laboratory and logged in detail to augment our on-site logging. The cores remain in our laboratory for future inspections, as necessary. Detailed logs of these borings are presented in this appendix (following the text). These logs depict our interpretation of the subsurface conditions at the dates and locations indicated. It is not warranted that they are representative of subsurface conditions at other times and locations. The contacts on the logs represent the approximate boundaries between earth materials, and the transition may be gradual. Representative samples of earth materials were collected for subsequent laboratory identification and testing (see Appendix B for a summary of laboratory testing).

Large-Diameter Exploratory Boreholes

Two large-diameter boreholes (24-inch diameter) were excavated by RC Drilling of Thousand Oaks, California in October, 2011 for the purpose of investigating the subsurface conditions of 1925 El Camino De La Luz. A third large diameter borehole was excavated on the adjacent property at 1921 El Camino De La Luz and was used to aid in correlation of bedrock units at 1925 El Camino De La Luz. These boreholes were downhole logged by our staff and principal engineering geologist in October, 2011. We selectively sampled critical earth materials, such as the weakest claystone interbeds in the upper borehole and the sheared materials in the lower borehole, for laboratory testing. The boreholes were backfilled with the native spoils and compacted using tamping methods with the drill rig Kelly bar. Geologic logs of the boreholes are presented in this appendix.

APPENDIX B

LABORATORY TESTING

Table B-1, Summary of Laboratory Test Results

Figure B-1, Summary of Atterberg Limits

Figure B-2, Undrained, Consolidated Triaxial Compression Strength Tests

Figure B-3, Summary of Torsional Ring Shear Tests.

COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay, 1925 ECDL

Boring B-1/SI-1

Location LANDSCAPED MEDIAN BETWEEN DRIVEWAYS

Project No. G0058

Drilling Contractor/Rig Britton Exploration/ CME 550 TRACKED RIG

Date of Drilling 5/10/11

Ground Surface Elev. ~132' Logged By JD

Hole Diameter 6" AUGERS, 3.5" HQ CORE, 4 7/8" TRICONE

Surface BALE SOIL/VEGETATION, A+ DIRECTION: SIDE

Weather CLEAR, BREEZY, COOL

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
2		CL	0.0'-5.5': SILTY CLAY w/ SAND; DAMP TO MOIST, FEW WHITE DENDRITIC MINERALIZATIONS, FIRM TO STIFF, MODERATE TO HIGHLY PLASTIC, ABUNDANT ROOTS.					HA		DRIER: PAUL HELPER: SERGIO START DRILLING @ 9:30AM
			0.0'-5.5': <u>ARTIFICIAL FILL</u>				3		15"	2" w/ HOLLOW STEM AUGERS.
			<u>TERRACE DEPOSITS?</u>	2			9	MC	15"	
4				1			13		18"	
								HA		4
			<u>5.5'-7.0': TERRACE DEPOSITS</u>				9			
			5.5'-7.0': FINE TO MEDIUM SAND w/ CLAY, MOSTLY MEDIUM RED BROWN, FEW 1/2" PEBBLES (ROUND), FRIABLE, WEAK.	4			13	MC	15"	6
6		SC		3			10		18"	
			<u>7.0'-9.8.0': MONTEREY FORMATION.</u>					HA		
			7.0'-9.8.0': WEATHERED MONTEREY FORMATION; FINE LAMINATED SHALE, DAMP TO MOIST, VARI-GATED BUFF TAN TO BLACK, BRITTLE, HARD SHALE LAMINATIONS (PORCELAIN LIKE) ALTERNATING w/ BROWN TO BLACK WEAKER SHALE LAMINATIONS, MODERATE TO DEEPLY WEATHERED, WEAK TO FRIABLE, LOW TO MODERATE HARDNESS, INHOMOGENEOUS.	6			3	MC	15"	8
8				5			9		15"	
							50/4"			
10							6	mc	14"	10
				8			14		14"	
12			10.0'-11.5': FEW OFFSET LAMINATIONS, DEEPLY WEATHERED TO CLAY, VERY PLASTIC.	7			13			12
								HA		
14		SHALE								14
			15.0'-16.5': HARDER SHALE, WEAK, BRITTLE, DAMP, FINELY LAMINATED	10			13		13"	
16				9			23	MC	13"	16
							50/5"		16"	
18										
								HA		18
20			20.0'-21.5': FINELY LAMINATED, HIGHLY PLASTIC, VERY CLAYEY VARYING TO BRITTLE, DAMP.	12			24			20
				11			14	MC	13"	20
22							17		18"	22
								HA		-CFT 4.5" & CASTING TO 26'
24										24
			25.0'-26.5': DEEPLY WEATHERED SILTY CLAYSTONE, HIGHLY OXIDIZED, HIGHLY PLASTIC, SOIL-LIKE, MOIST, VERY STIFF, VARI-GATED LIGHT GRAY AND REDDISH ORANGE.	14			7		17"	10:15AM SWITCHING TO
26				13			12	MC	17"	26
			26.5'-28.0': DARK GRAY BROWN w/ YELLOW ORANGE OXIDIZED STAINING, SILTY CLAYSTONE, LAMINATED, MOIST, HIGHLY PLASTIC.	1			29		18"	26
28								HA	0.5'	11:30AM-11:45PM DRILLING
									1.5'	SHOT DOWN; NEEDS A NEW PRESSURE GAUGE.
				2				HA	3.5'	-28
									5.0'	2:00PM: START CURING

TERRACE DEPOSITS?
ARTIFICIAL FILL
WEATHERED MONTEREY FORMATION

WEATHERED MONTEREY FORMATION

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
32			28.0'-33.0': HARD, BRITTLE, LAMINATED SHALE, DOLOMITIZED, VERY FRACTURED	2				HQ	5.5' 5.0'	32 2:32 PM @ 33'
34			33.0'-38.0': HARD, STRONG SHALE, BUFF TO TAN w/ GRAY TO BLACK LAMINATIONS, CLOSELY FRACTURED. POOR RECOVERY. VERY HARD CORING RUN w/ A FEW FASTER SPOTS. FINELY LAMINATED, FEW OXIDIZED STREAKS.	3				HQ	1.5' 5.0'	34
36										36
38			38.0'-43.0': BOTTOM 3.5' OF CORE INTACT. DARK BROWN, CLAYSTONE w/ ABUNDANT PETROLEUM/TAR SEAMS IN FRACTURES, HARD, MODERATELY STRONG, LAMINATED, LITTLE WEATHERING, CLOSELY FRACTURED.	4				HQ	4.0' 5.0'	38 3:15 PM @ 38' 3:46 PM
40										40
42										@ 41: VIBRATING WIRE PIEZOMETER SENSOR S/N 1107485
44			43.0'-48.0': CORE IS COMPLETELY INTACT, A FEW MECHANICAL BREAK AT THE TOP. DARK BROWN CLAYSTONE, HARD, MODERATELY STRONG, LAMINATED, FRESH, CLOSE TO MODERATELY FRACTURED, NUMEROUS TAR SEAMS ALONG FRACTURES, SOME OFFSET LAMINATIONS AT BOTTOM OF RUN.	5				HQ	5.0' 5.0'	44 3:44 PM 4:10 PM
46										46
48			48.0'-53.0': CORE IS NEAR INTACT w/ 4 MECHANICAL BREAKS. SIMILAR TO ABOVE IN ROCK PROPERTIES, HARD, STRONG, TAN TO WHITE, LAMINATED DOLOMITIZED ZONE NEAR BOTTOM OF RUN.	6				HQ	5.0' 5.0'	48 4:16 PM @ 48' 4:50 PM
50										50
52										52
54			53.0'-58.0': CORE HAS NUMEROUS MECHANICAL BREAKS. DARK BROWN CLAYSTONE w/ BLACK DISSEMINATIONS OF HYDROCARBONS (TAR SEAMS), MODERATELY HARD, MODERATELY STRONG, CLOSELY TO INTENSELY FRACTURED, LITTLE TO NO WEATHERING. TAR SEAMS FILL IN FRACTURES.	7				HQ	5.0' 5.0'	54 5:08 PM @ 53' END OF DAY 7:30 AM 5/11/11
56										56
58			58.0'-63.0': CORE IS VERY BROKEN UP. DARK BROWN CLAYSTONE, MODERATELY HARD, WEAK TO MODERATE STRENGTH, CRUSHED TO INTENSELY FRACTURED.	8				HQ	4.0' 5.0'	58 8:16 AM 8:39 AM
60										60
62										62
				9				HQ	8:50 AM 9:28 AM	



Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Design.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
66			63.0'-68.0': CORE IS BROKEN UP, TWO PIECES ARE 8" TO 10" LONG. SILTY CLAYSTONE TO FINE SANDY CLAYSTONE W/ FEW 1/8"-1/4" PEBBLES OR CLAST, MEDIUM TO DARK BROWN, MORE VARIABLE IN ROCK PROPERTIES. SANDY SECTIONS ARE HARD, STRONG, MODERATELY FRACTURED, LAMINATED, CLAYEY SECTIONS ARE MODERATELY HARD, NEAR TO MODERATE STRENGTH, INTENSELY FRACTURED TO CRUSHED.	9 Box 4				HQ	4.5' 5.0'	- VARIABLE RUN; SLOW AT THE START, SPEEDS UP IN THE MIDDLE, SLOW AT THE END OF RUN
68									9:20AM 9:57AM	68
70	CLAY SEAM		68.0'-70.0': FINE SANDY SILTY CLAYSTONE, MEDIUM BROWN, HARD, STRONG.	10 Box 4				HQ	5.0' 5.0'	70
72			@ 70.0': 0.5" THICK VERY PLASTIC, RUBBERY CLAY SEAM, YELLOW GREEN TO GREEN BROWN, HORIZONTALLY ORIENTED, MOIST, STRONG H ₂ S ODOE.						11mins	72
74	CLAY SEAM		BELOW: BEDDING IS DISRUPTED @ 71.5' W/ SOME PLASTIC CLAY SEAMS						10:06AM 10:30AM	74
76			@ 75.0' CLAY SEAM, MUSTARD YELLOW, VERY PLASTIC, MOIST	11 Box 5				HQ	3.5' 5.0'	76
78			BELOW: MODERATELY HARD, MODERATELY STRONG, FEW FRACTURES OFFSET BEDDING LAMINATIONS, MEDIUM TO DARK BROWN.						10:45AM	78
80			78.0'-81.0': FRACTURED CLAYSTONE; DARK BROWN, MODERATELY HARD, WEAK TO MODERATELY STRONG, CRUSHED TO INTENSELY FRACTURED.	12 Box 5				HQ	3.0' 3.0'	HARD CORING RUN; BIT NO LONGER ADVANCING @ 80'
82	HARD		81.0'-83.0': SILTY CLAYSTONE; DARK BROWN, WELL CEMENTED, MODERATELY HARD, MODERATELY STRONG, BRITTLE, FINELY LAMINATED, UNIFORM BEDDING	13 Box 5				HQ	2.0' 2.0'	80 SWITCHING FROM A CARBIDE BIT TO A DIAMOND BIT
84			83.0'-88.0': SILTY CLAYSTONE; DARK BROWN, WELL CEMENTED, MODERATE TO HARD, MODERATE TO STRONG, CLOSELY FRACTURED, FINELY LAMINATED,	14 Box 6				HQ	2.5' 5.0'	82
86	25° DIP								12:43PM 1:00PM	84
88			88-91.0': DARK BROWN SILTY CLAYSTONE WITH BASAL GRAVEL LAG, MODERATELY HARD, HIGH STRENGTH, BRITTLE, INTENSELY FRACTURED.	15 Box 6					1:30PM 1:40PM	86
90	GRAVEL LAG								2mins	88
92	40° DIP		91.0'-93.0': TAN TO BUFF WHITE SILTY CLAYSTONE, HARD, STRONG, WELL CEMENTED, PORCELAIN-LIKE, CLOSELY FRACTURED.	16 Box 7				HQ	4.5' 5.0'	90
94	TAR SEAMS		93.0'-98.0': MEDIUM BROWN SILTY CLAYSTONE, MODERATE HARDNESS, MODERATE STRENGTH, CLOSELY FRACTURED, FEW TAR SEAMS INFILLING FRACTURES.						2:19PM 2:48PM	@ 91' VIBRATING WIRE PIEZOMETER SENSOR
96									2.5' 5.0'	92 S/N 1107564
									2:50PM	94
									2:50PM	96

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
			TD = 98'							4:10 PM: HQ RODS AND 4.5" Ø CASING OUT OF HOLE.
100			11:50 AM: INSTALLED 100' OF SLOPE INDICATOR 2.75" Ø QC CASING W/ 2 GEOKON VIBRATING WIRE PIEZOMETERS TAPED TO THE SIDE OF THE CASING @ DEPTH 95' (S/N 1107564) AND 45' (S/N 1107485). 4' OF STICK UP.							100
102										4:20 PM: START REAMING OUT HOLE W/ 4 1/8" Ø 102 TRS CONE BIT.
104										104
106			1:00 PM: PUMPED ~150 GALS OF BENTONITE/ CEMENT GROUT MIX PER: 30 GALS H ₂ O / 94 1/8 CEMENT / 25 1/8 BENTONITE.							4:57 PM: REAMED TO 50' 104 7:30 AM 5/12/11 START REAMING AGAIN
108										106
110										108
112										110
114										112
116										114
118										116
120										118
122										120
124										122
126										124
128										126
130										128
										130



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay

Boring B-2/SI-2

Location 1925 ECDLL HEADSCARP AREA

Project No. G0058

Drilling Contractor/Rig Britton Exploration/CME 550 TRACKER EIG

Date of Drilling 5/12/11

Ground Surface Elev. ~119' Logged By JD

Hole Diameter 6" HOLLOW STEM AUGER, 4 7/8" TRI CONE

Surface BARE SOIL

Weather CLEAR, WARM, BREEZY

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
0.0 - 5.0'			ARTIFICIAL FILL; DESCRIBED BELOW.					HA		2:55PM: START DRILLING DRILLER: PAUL HELPER: SERGIO
2.0 - 3.5'		AF	ARTIFICIAL FILL COMPOSED OF MONTEREY SILTY CLAYSTONE CLASTS IN SILTY CLAY MATRIX, DAMP, OXIDIZED, DEEPLY WEATHERED MEDIUM BROWN AND YELLOW ORANGE, WEAK.				3 3 4	MC	12 1/8"	-2- DRILLING w/ HOLLOW STEM AUGER
5.0 - 100.0'			MONTEREY FORMATION; AS DESCRIBED BELOW.				6 6 10	MC	16 1/8"	SAMPLE #1 EXTRUDED
5.0 - 6.5'			COLLUVIUM/DEEPLY WEATHERED CLAYSTONE, VERY PLASTIC, NOT SHEARED	X				HA		-3:15PM: GRINDING AND WASH ROCK
8.0'			CHERTY/DOLOMITIZED SHALE, HARD, STRONG, BUFF TO TAN.				50/3"			-8 @ 8'
10.0 - 11.5'		COL/ WTHRD CLYST	DEEPLY WEATHERED CLAYSTONE, MEDIUM BROWN TO YELLOW ORANGE, SOIL-LIKE, VERY PLASTIC, MOIST, SOFT TO FIRM, BRITTLE, FRAGILE, SOME CLAYEY ZONES, SOME GYPSUM CRYSTALS	X			7 14 9	MC	12 1/8"	SAMPLE #2 EXTRUDED
15.0 - 16.5'			DEEPLY WEATHERED CLAYSTONE, W/ A FEW HARDER, BRITTLE SHALE FRAGMENTS, MOIST, HIGHLY PLASTIC, SOFT TO FIRM, MVS. SOFT, WET, NOT SHEARED BUT DEFORMED, SOME BRITTLE HARD PIECES, BUFF TO TAN, SOIL-LIKE	X			14 25 50/5"	MC	12 1/8"	4:20PM -16 SAMPLE #3 EXTRUDED
20.0 - 21.5'			HARDER CLAYSTONE FRAGMENTS IN A CLAY MATRIX MOIST TO WET, SOFT TO FIRM, HIGHLY PLASTIC				2 13 7	MC	12 1/8"	SAMPLE #4 EXTRUDED
25.0 - 26.5'			DEEPLY WEATHERED CLAYSTONE, VERY CLAYEY, NOT SHEARED, WEAK, SILTY, LAMINATED	X				HA		
28.0'			FREE WATER ON SAMPLER, WEATHERED CLAYSTONE, TAN TO BUFF AND REDDISH DARY BROWN, WET, HARDER BRITTLE FRAGMENTS AND SOFTER CLAYEY MATRIX.	6 5			17 13 23	MC	12 1/8"	4:57 PM -26
								HA		-28

ARTIFICIAL FILL

WEATHERED MONTEREY FORMATION

WEATHERED
MONTEREY
FORMATION


UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Design.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
32	CLAY SEAM 25" DP TAR SEAMS		30.0'-31.5': WEATHERED CLAYSTONE, DARK BROWN, MOIST TO WET ON FRACTURES, WEAK TO MODERATELY STRONG, LOW HARDNESS, INTENSELY FRACTURED, * 6" CORING RUN FROM 29.5'-30.0': SILTY CLAYSTONE; MEDIUM BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, LITTLE WEATHERING, INTENSELY TO CLOSELY FRACTURED, FINELY LAMINATED, HYDROCARBON FILLED FRACTURES (TAR SEAMS)	RUN 2 5' BOX 1			50/5" —	MC —	6:30AM: SWITCH TO HQ CORING SET 4.5" CASING TO 30' END OF DAY 9:20AM 32 7:30AM 5/13/11 8:00AM: FIRST CORING RUN TO 30' TO FINISH OUT MC RUN. CORE GOT STUCK IN 34 THE DRILL TUBE.	
34								HQ	3.0' 5.0' 10mins	
36			35.0'-40.0': SILTY CLAYSTONE, DARK BROWN, LOW TO MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, DAMP TO MOIST, CRUSHED TO INTENSELY FRACTURED (FEW INTACT PIECES OF CORE), FEW 1/2"-1/4" PEBBLES AND/OR CLASTS, FINELY LAMINATED, SOME HYDROCARBON SEAMS.	RUN 3 BOX 1				HQ	5.0' 5.0'	9:20AM 10:30AM CORING WAS SLOW @ FIRST 36 SPEED UP IN THE MIDDLE AND SLOW @ THE END
38										38 @ 36, 35': VIBRATING WIRE PIEZOMETER SENSOR S/N 1107487
40			40.0'-43.0': SILTY CLAYSTONE, DARK BROWN, MODERATE TO HARD, MODERATE TO STRONG, MODERATE FRACTURING, CONTORTED BEDDING TRANSITIONING @ 41' TO WHITE TO TAN SILTIFIED SHALE, HARD TO VERY HARD, STRONG TO VERY STRONG, LITTLE FRACTURING, TAR FILLED FRACTURES.	RUN 4 BOX 2				HQ	10:36AM 10:54AM 2.25' 3.0'	40 17mins SLOW, HARD CORING RUN 11:11AM @ 42' SETTING UP
42	BUFF TO TAN									42 RECTIFICATION TUB. 11:21AM: CORED A FEW INCHES 11:51AM SWITCHING TO DIAMOND BIT
44			43.0'-45.0': SIMILAR TO ABOVE, MEDIUM BROWN LAMINATED W/ BUFF TO TAN SILTSTONE.	RUN 5 BOX 2				HQ	11:24PM 2 1/2'	44
46	TAR SEAMS		45.0'-50.0': SILTY CLAYSTONE, MEDIUM TO DARK BROWN, MODERATELY HARD, MODERATELY STRONG, CLOSELY FRACTURE, UNIFORMLY LAMINATED, NUMEROUS TAR SEAMS ALONG FRACTURES.	RUN 6 BOX 2				HQ	12:37PM 12:59PM	46
48										48
50	20" DP		50.0'-55.0': SILTY CLAYSTONE, DARK BROWN, MODERATELY HARD, MODERATELY STRONG, INTENSELY TO CLOSELY FRACTURED, CONSISTENT AND UNIFORM LAMINATIONS, NUMEROUS TAR SEAMS ALONG FRACTURES	RUN 7 BOX 3				HQ	1:26PM 1:42PM	50
52										52
54										54
56	FISSILE WEAK SOFT ZONE		55.0'-57.0': WEAK, FISSILE SHALE/CLAYSTONE, DARK BROWN, CRUSHED TO INTENSELY FRACTURED,	RUN 8 BOX 3				HQ	2:06PM 2:23PM	56 -SOFT ZONE @ 1' INTO RUN
58	TAR SEAMS		57.0'-60.0': STRONGER, MORE WELL CEMENTED, SILTY CLAYSTONE, DARK BROWN, MODERATELY HARD, MODERATELY STRONG, CLOSELY TO INTENSELY FRACTURED, ABUNDANT TAR SEAMS ALONG FRACTURES.	RUN 9 BOX 3				HQ	4.5' 5.0' 20mins	58
60			60.0'-65.0': SIMILAR TO ABOVE.							60
62	WEAK		62.5'-63.0': WEAK, CRUSHED, FISSILE SHALE, DARK BROWN, LOW HARDNESS	RUN 9 BOX 4				HQ	2:52PM 3:14PM 3.0' 5.0' 29mins	62



Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Design.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
			64.5'-65.0': WEAK, CRUSHED SHALE, DARK BROWN, LOW HARDNESS	RUN 9 BOX 4				HQ	3:43PM	END OF DAY
66			65.0'-70.0': CLAYSTONE, DARK BROWN, LOW HARDNESS, WEAK STRENGTH, CRUSHED. LAST 6" ARE HARDER AND STRONGER, FINELY LAMINATED w/ A SEMI VERTICAL TAR SEAM.	RUN 10 BOX 4				HQ	4.0'/5.0'	7:30AM 5/16/11
68									24mins	
70			70.0'-75.0': SILTY CLAYSTONE w/ FINE SANDY LAMINATION, ALTERNATING TAN TO BUFF AND DARKER BROWN LAMINATIONS, MODERATELY HARD, MODERATELY STRONG, CLOSELY FRACTURED, TAR FILLED FRACTURES (FEW), EVENLY AND UNIFORMLY LAMINATED, FEW 1/4" PEBBLES OR CLASTS.	RUN 11 BOX 4				HQ	8:21AM 8:40AM	
72									3.0'/5.0'	
74									25mins	
76			75.0'-77.0': SIMILAR TO ABOVE.						9:05AM 9:22AM	
78			77.0'-80.0': CLAYSTONE, DARK BROWN, CRUSHED TO INTENSELY FRACTURED, WEAK, LOW HARDNESS, LAMINATED, STRONG H ₂ S ODOR.	RUN 12 BOX 5				HQ	3.5'/5.0'	
80									25mins	
82			80.0'-85.0': CLAYSTONE, DARK BROWN w/ WHITE TO TAN 1/4" LAMINATIONS, INTENSELY FRACTURED, LOW HARDNESS, WEAK STRENGTH, STRONG H ₂ S ODOR, LOCALLY MODERATE HARDNESS/STRENGTH.	RUN 13 BOX 5				HQ	9:46AM 10:08AM	
84									4.0'/5.0'	
86			85.0'-90.0': FAULTED/BRECCIATED CLAYSTONE, DARK BROWN, INTENSELY FRACTURED, MODERATELY HARD, MODERATELY STRONG, ABUNDANT TAR SEAMS ALONG FRACTURES AND FAULTS. BEDDING LAMINATIONS ARE VERY DISRUPTED BY NUMEROUS, NEAR VERTICAL, ANASTOMOSING FAULTS, VERY BRECCIATED.	RUN 14 BOX 5/6				HQ	10:44AM 10:58AM	
88			@ 89': MUSTARD YELLOW TO GREEN, THEN CLAY FILM ON BEDDING PLANE, POOR RECOVERY, VERY PLASTIC.						4.5'/5.0'	
90									29mins	@ 88.35': VIBRATING WIRE PIEZOMETER SENSOR S/N 1107563
92			90.0'-95.0': SILTY CLAYSTONE w/ FEW ELONGATE CLASTS, MEDIUM TO DARK BROWN, MODERATELY HARD, MODERATELY STRONG, CLOSELY TO MODERATE FRACTURING, FEW OFFSET LAMINATIONS (FAULTS), FEW TAR SEAMS ALONG FRACTURES/FAULTS.	RUN 15 BOX 6				HQ	11:27AM 11:42AM	
94			@ 94.75': MUSTARD YELLOW/GREEN CLAY FILM ALONG BEDDING PLANE, VERY PLASTIC, POOR RECOVERY						27mins	
96			95.0'-100.0': TRANSITION FROM SILTY CLAYSTONE, MEDIUM TO DARK BROWN, MODERATELY HARD/STRONG, MODERATELY FRACTURED, FINELY LAMINATED TO RIP UP CLASTS/GRAVEL LAG @ 96.25' TO CLAYEY SILTY SAND, SLIGHTLY FRITABLE, LOW TO MOD. HARDNESS, WEAK TO MOD. STRENGTH, POORLY BEDDED.	RUN 16 BOX 6/7				HQ	12:09PM 12:29PM	
									5.0'/5.0'	
									15mins	

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
100		25 MP	@ 97.75' AND BELOW: FINELY LAMINATED SELTY CLAYSTONE, BUFF TO TAN, WEAK ALONG LAMINATIONS, MODERATE TO HARD, MODERATE TO STRONG, CLOSE TO MODERATE FRACTURE. TD = 100'	RUN 16 Box 6/7				HQ	50% 15 min 12:44 PM	100 1:00 PM: START PULLING SAMPLING RODS AND 4 1/2" CASING @ 30'
102			5/17/11, 9:05 AM: INSTALLED 100' OF 2.75" Ø SLOPE INDICATOR SLOPE INCLINOMETER & CASING WITH TWO GEPKON VIBRATING WIRE PIEZOMETERS TAPED TO THE SIDE OF THE CASING AT 45' (S/N 1107437) AND 95' (S/N 1107563), 6.65' OF STICKUP.							102 H4 II 2:37 PM: START REAMING HOLE w/ 4 1/2" Ø TRE CONE BIT 5:50 PM: REAMED TO 100'
104										
106			10:30 AM: PUMPED ~130 GALS OF BENTONITE/ GROUT PER MIX: 30 GALS H ₂ O / 94 lb CEMENT / 25 lb BENTONITE							106
108										108
110										110
112										112
114										114
116										116
118										118
120										120
122										122
124										124
126										126
128										128
130										130



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay

Boring B-3/SI-3

Location 1925 ECDL; DOWNSLOPE OF B-2

Project No. G0058

Drilling Contractor/Rig Britton Exploration/CME 550 TRACKED RIG

Date of Drilling 5/17/11

Ground Surface Elev. ~87' Logged By JD

Hole Diameter 6" HOLLOW STEM AUGER

Surface BARE SOIL

Weather CLOUDY, COOL, BREEZY

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
0.0' - 3.0'	ARTIFICIAL FILL		ARTIFICIAL FILL; SILTY CLAY W/ ROCK FRAGMENTS, MEDIUM TO DARK BROWN, MOIST, PLASTIC, SILTY CLAY FILLS THE INTERSTICES BETWEEN ROCK FRAGMENTS OF MONTEREY SHALE. PIECES THAT ARE WHITE TO BUFF, WELL CEMENTED, SILICEOUS SHALE, HARD, STRONG. ONE PIECE OF CONCRETE IN DRIVE SAMPLE. FILL IS LOOSE, WEAK, AND FRIABLE.					HA		11:25AM: START DRILLING W/ HOLLOW STEM AUGERS
2		CONC.					5			
3							3	MC	8"	11:35AM
4							4			
								HA		
3.0' - 14.0'	LANDSLIDE DEBRIS		LANDSLIDE DEBRIS; INTENSELY FRACTURED FRAGMENTS OF MONTEREY SILTSTONE AND SHALE, DEEPLY WEATHERED, HIGHLY OXIDIZED, TANTO BUFF AND IRON STAINED.				1			
6							1	MC	10"	
							2		12"	
								HA		
8										
14.0' - 99.0'	MONTEREY FORMATION		MONTEREY FORMATION; AS DESCRIBED BELOW.				6		12"	
							5	MC	18"	11:50AM
							8			12:30PM: SWITCHING TO
14.0' - 15.0'	LIGHTLY WEATHERED CLAYSTONE		LIGHTLY WEATHERED CLAYSTONE; MOTTLED LIGHT GREY, YELLOW ORANGE AND DARK BROWN, MOIST, HIGHLY PLASTIC, LOW HARDNESS, WEAK, INTENSELY FRACTURED, TAR SEAMS NEAR BOTTOM OF SAMPLE ALONG FRACTURES, SOIL-LIKE, STIFF.	RUN 1					2:08PM	10-HQ CORING SYSTEM. 8.58' LONG CORE PARCEL LOSING FLUID CIRCULATION IN THE LOOSE FILL.
12				Box 1				HQ	1.0' / 5.0'	12
14		CONTACT ZONE							15 mins	14
15.0' - 15.5'	SHALE		SHALE; BUFF TO TAN, HARD TO VERY HARD, STRONG, WELL CEMENTED, SILICA CEMENTED, FINELY LAMINATED.	RUN 2				HQ	2:23PM	16
16		VY. HARD		RUN 3				HQ	2:40PM	STOPPED RUN SHORT, LOSING CIRCULATION.
18				RUN 4				HQ	3:40PM	INSTALLED CASING TO 13' - CIRCULATION RETURNS - LOST CIRCULATION AGAIN
20								HQ	4:05PM	18-PUSHED CASING DOWN 13' - ROTIL RATE INCREASED RAPIDLY IN MIDDLE OF RUN THEN SLOWED AGAIN
22				RUN 5				HQ	4:49PM	20- END OF DAY
24								HQ	7:52AM	21-30AM, 5/18/11
25.0' - 30.0'	CLAYSTONE		CLAYSTONE; DARK BROWN, MODERATE HARDNESS, MODERATE STRENGTH, FINELY LAMINATED, WELL CEMENTED.	RUN 6				HQ	7:28AM	A PIECE OF CORE IS STUCK IN THE END OF THE SAMPLER SUEWAYS - BLOCKING THE SAMPLER AND PREVENTING ANY SAMPLING.
26								HQ	0.25' / 5.0'	28
28								HQ	12 mins	
								HQ	9:40AM	



Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
32			30.0'-35.0': SAMPLES FROM THE CORE BARREL; CLAYSTONE, DARK BROWN, MODERATE TO HARD, MODERATE TO STRONG, FINELY LAMINATED, WELL CEMENTED.	RUN 7				HA	10:31AM	- NO CIRCULATION, NO RECOVERY?!
34									10:31AM	PULLED THE CORE BARREL
36									10:31AM	- 32 OUT OF THE HOLE AND THE END WAS PLUGGED W/ HARD PIECES OF CLAYSTONE
38			35.0'-38.0': CLAYSTONE, DARK BROWN, MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, INTENSELY FRACTURED, FINELY LAMINATED.	RUN 8				HA	10:58AM	- 34 - PUSHED CASING TO 20' PUT ON CARBIDE BIT
40			38.5' ± 1.5" THICK, DARK GREYISH TO BLACK AND WHITE LAMINATED CLAY ZONE DIPPING ~ °; AT THE BASE OF IT, THE LAMINATIONS TRUNCATE ALONG A PAPER THIN SEAM AGAINST HARDER CLAYSTONE BELOW.	BOX 1					11:16AM	- 36 - STILL LOSING RETURN FLOW
42			40.0'-45.0': GOOD RECOVERY. SILTY CLAYSTONE, DARK BROWN TO LAMINATED LIGHT AND MEDIUM BROWN, LOW TO MODERATE (LOCALLY) HARDNESS, WEAK TO MODERATE STRENGTH, INTENSELY FRACTURED. FEW TAR SEAMS	RUN 9				HA	11:29PM	- 38
44			40'-41' LESS LAMINATED, MORE MASSIVE. FEW 1/4" CLASTS.	BOX 2					11:47PM	- 40 - LOSING FLUID RETURN.
46			45.0'-50.0': SILTY TO FINE SANDY CLAYSTONE; MEDIUM BROWN, FINELY LAMINATED, MODERATE TO HARD, MODERATE STRENGTH, CLOSELY FRACTURED, TAR SEAMS ALONG FRACTURES. MODERATELY CEMENTED.	RUN 11				HA	11:56PM	- 42
48				BOX 2					12:15PM	- 44 - VIBRATING WIRE PIEZOMETER SENSOR SN 1107480
50									12:29PM	- 46 - NO FLUID RETURN
52									12:48PM	- 48 - DRILL RATE INCREASED A COUPLE TIMES AT THE START OF THE RUN THEN FLOWED.
54									12:59PM	- 50
56			50.0'-55.0': WELL CEMENTED SHALE, BUFF TO TAN CHANGING TO MEDIUM BROWN @ 53.25, HARD TO VERY HARD, STRONG TO VERY STRONG, INTENSELY FRACTURED W/ TAR SEAMS RUNNING ALONG FRACTURES, SOME QUARTZ FISSURES, FINELY LAMINATED, CONTORTED BEDS @ 53 (SOFT SEDIMENT DEFORMATION), SILICA CEMENTED.	RUN 12				HA	1:19PM	- 52 - SWITCHED TO DIAMOND BIT
58				BOX 3					1:48PM	- 54
60									2:19PM	- 56 - LITTLE TO NO FLUID RETURN DURING CORING RUN.
62			55.0'-60.0': CEMENTED SHALE, MEDIUM TO DARK BROWN, MODERATE TO HARD, MODERATE TO STRONG, CLOSELY FRACTURED, LOCALLY SILICA CEMENTED, FINELY LAMINATED, NUMEROUS FRACTURES FILLED W/ TAR SEAMS	RUN 13				HA	2:45PM	- 58
				BOX 5					3:04PM	- 60 - PUSHED CASING DOWN TO 25'
			60.0'-65.0': SILTY CLAYSTONE; MEDIUM TO DARK BROWN LAMINATIONS, MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, NOT AS WELL CEMENTED AS ABOVE, CLOSELY FRACTURED, FEW TAR SEAMS ALONG FRACTURES, FEW 1/4" - 1/2" CLASTS/PEBBLES ALONG LAMINATIONS.	RUN 14				HA	4:24PM	- 62 - GOOD RETURN FLOW, NO FLUID LOSS
									4:56PM	
									5:21PM	
									6:13PM	
									6:50PM	
									7:30PM	


UNOXIDIZED MONTEREY FORMATION



Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recon. (%)	Remarks
				RUN 15 BOX 4				HQ	5/5'	END OF DAY
66			65.0'-70.0': SILTY CLAYSTONE, WELL CEMENTED W/ SILICA, LAMINATED DARK BROWN W/ LOCALLY WHITE TO TAN CHERTY LAYERS (66'), MODERATE TO HARD, MODERATE TO STRONG, INTENSELY TO CLOSELY FRACTURED,	RUN 16 BOX 4				HQ	5.0/5.0	7:30 AM 5/19/11 - GOOD CIRCULATION - NO FLUID LOSS
68			CONTORTED BEDS FROM 65.5'-67.0' (SOFT SETTING DEFORMATION), FEW 1/4" CLASTS AND TAR SEAMS ALONG FRACTURES.						21 mins	68
70			70.0'-71.0': SILTY CLAYSTONE, WELL CEMENTED, SIMILAR TO ABOVE, ABUNDANT TAR SEAMS AND FRACTURES, FEW OFFSET LAMINATIONS.						8:33 AM 8:50 AM	70 - GOOD CIRCULATION - NO FLUID LOSS
72			71.0'-74.0': CLAYSTONE, DARK BROWN, LOW HARDNESS, WEAK, MASSIVE, H ₂ S ODOR, UNIFORM COLOR AND COMPOSITION, LITTLE FRACTURING	RUN 17 BOX 4/5				HQ	5.0/5.0	72
74			74.0'-75.0': SILTY CLAYSTONE, FINELY LAMINATED MEDIUM TO DARK BROWN, MODERATE HARDNESS AND STRENGTH, MODERATELY CEMENTED.						23 mins	74
76			75.0'-76.0': SIMILAR TO ABOVE, MEDIUM BROWN TO BUFF						9:13 AM 9:37 AM	76
78			76.0'-77.0': CLAYSTONE, LAMINATED DARK BROWN W/ WHITE STRIPES, WEAK, LOW HARDNESS, CRUSHED, FRIABLE.	RUN 18 BOX 5				HQ	4.4/5.0	- GOOD CIRCULATION
80			77.0'-80.0': TRANSITION BACK TO SILTY CLAYSTONE, LAMINATED BUFF TO TAN AND MEDIUM BROWN, MODERATE HARDNESS/STRENGTH, INTENSELY FRACTURED, SOME SILICA CEMENT.						23 mins	78
82			80.0'-85.0': CORE IS VERY BROKEN UP. CLAYSTONE, MEDIUM TO DARK BROWN LAMINATED, FRIABLE TO LOW HARDNESS, WEAK, CRUSHED, STRONG H ₂ S ODOR.	RUN 19 BOX 5/6				HQ	3.0/5.0	80 - GOOD CIRCULATION
84									24 mins	84
86			85.0'-90.0': CLAYSTONE, DARK BROWN W/ NUMEROUS WHITE TO TAN ELONGATE CLASTS ALIGNED W/ THE LAMINATIONS, LOW TO MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, CRUSHED TO INTENSELY FRACTURED, STRONG H ₂ S ODOR.	RUN 20 BOX 6				HQ	5.0/5.0	86 GOOD CIRCULATION
88									26 mins	88
90			90.0'-92.0': CLAYSTONE, SIMILAR TO ABOVE, CRUSHED TO INTENSELY FRACTURED.						11:27 AM 11:49 AM	90 GOOD CIRCULATION
92			92.0'-95.0': SILTY CLAYSTONE W/ FINE SAND, MEDIUM TO DARK BROWN, FINELY LAMINATED, MODERATELY HARD/STRONG, CLOSELY FRACTURED, FEW TAR SEAMS ALONG FRACTURES, WELL CEMENTED.	RUN 21 BOX 6/7				HQ	4.0/5.0	92
94									16 mins	94 @93: VIBRATING WIRE PIEZOMETER SENSOR S/N 1107565
96			95.0'-99.0': SILTY CLAYSTONE W/ FINE SAND, DARK BROWN, MODERATELY HARD/STRONG, LOCALLY WEAK, FINELY LAMINATED, WELL CEMENTED.	RUN 22 BOX 7				HQ	2.0/4.0	96

UNOXIDIZED MONTEREY FORMATION

Project Felkay/G0058Date 5/19/11Boring B-3/SI-3

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
		SANDY								
100			TD = 99'							1:30 PM: PULLING OUT HQ
102			7:30 PM: INSTALLED 100' OF 2.75" Ø SLOPE INDICATOR SLOPE INCLINOMETER QC CASING WITH TWO GEOKON VIBRATING WIRE PIEZOMETERS TAPED TO THE SIDE OF THE CASING AT 45' AND 95' BGS, 2' OF STICK UP.							100 CORE DRILL RODS
104			5/20/11, 8:00 AM: GROUTED THE BORING WITH BENTONITE/CEMENT PER MIX: 30 GALS H ₂ O / 94 LB CEMENT / 25 LB BENTONITE.							
106										
108										
110										
112										
114										
116										
118										
120										
122										
124										
126										
128										
130										

COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay Boring B-4/SI-4
 Location 1921 ECDLL; ABOVE HEADSCARP Project No. G0058
 Drilling Contractor/Rig Britton Exploration/ Date of Drilling 5/20/11
 Ground Surface Elev. ~124' Logged By JD Hole Diameter 6" HOLLOW STEM AUGERS
 Surface BARE SOIL Weather FOGGY, COOL, BREEZY


Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
0.0'-2.75'		AF	0.0'-2.75': ARTIFICIAL FILL; SILTY CLAY w/ SAND, DAMP, FIRM TO STIFF, MODERATE PLASTICITY.					HA		10:35AM: START DRILLING w/ HOLLOW STEM AUGERS, DRILLER: PAUL
2.75'-100.00'			2.75'-100.00': MONTEREY FORMATION; AS DESCRIBED BELOW				6	MC	12 1/8"	2 HELPER: SERGIO
2.75'-3.5'			2.75'-3.5': DEEPLY WEATHERED CLAYSTONE; WHITE TO TAN w/ YELLOW ORANGE STAINING, SOFT, MOIST, PLASTIC, FIRM	1			11			
3.5'-6.5'			3.5'-6.5': DEEPLY WEATHERED CLAYSTONE; WHITE TO TAN WITH YELLOW ORANGE STAINING, MOIST, VERY PLASTIC, SOIL-LIKE, FIRM TO STIFF, SOFT, FRIABLE,	2			15	HA		4
6.5'-8.0'			6.5'-8.0': SIMILAR TO ABOVE WITH HARDER FRAGMENTS OF CLAYSTONE, LITTLE MOISTURE ON SAMPLER AND THE SAMPLE TUBES, BUT THE CLAYSTONE IS JUST MOIST.	3			22	MC	14 1/8"	10:50AM
8.0'-9.5'							14			6
9.5'-10.0'							17	HA		
10.0'-12.0'							14	MC	14 1/8"	11:05AM
12.0'-14.0'							26			
14.0'-15.0'								HA		
15.0'-16.0'			15.0'-16.0': DEEPLY WEATHERED CLAYSTONE; WHITE TO TAN w/ EXTENSIVE YELLOW ORANGE IRON OXIDE STAINING, MOIST, VERY PLASTIC, SOIL-LIKE, STIFF, SOFT TO LOCALLY HARD, FRIABLE AND WEAK, FINELY LAMINATED, BLACK TAR SEAMS, SOME SILICA CEMENTED CLAYSTONE PIECES	5			13			11:20AM
16.0'-18.0'				4			33	MC	14 1/8"	16
18.0'-20.0'							27			
20.0'-21.5'			20.0'-21.5': SIMILAR TO ABOVE. LAST 4" OF SAMPLE (IN SHOP) IS VERY PLASTIC, STIFF CLAYSTONE, MOIST, SOIL-LIKE, DEEPLY WEATHERED, SOFT.	6			15	MC	14 1/8"	11:34AM
21.5'-23.4'			21.5'-23.4': SILICEOUS SHALE; WHITE TO TAN FINELY LAMINATED, HARD, STRONG.	RUN 1			5			SWITCHING TO HQ CORING
23.4'-25.0'			23.4'-25.0': CLAYSTONE; GREYISH BROWN MOTTLED w/ YELLOW ORANGE, SOIL-LIKE, VERY STIFF, VERY PLASTIC, SOFT TO LOW HARDNESS, PLASTIC STRENGTH, MOIST, VERY CLAYEY, LAMINATIONS NOT APPARENT, DEEPLY WEATHERED.	BOX 1			7	HQ	2.2	22 SYSTEM
25.0'-27.5'			25.0'-27.5': SILICEOUS SHALE; TAN TO BUFF, HARD, STRONG, LAMINATED.	RUN 2						- SPORADIC RETURN FLOW
27.5'-30.0'			27.5'-30.0': CLAYSTONE; DARK BROWN.	BOX 1						24

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
32	BRECCIA 43' DEP TAN/BUFF TAR SEAMS CHERTY		30.0'-35.0': SILICEOUS SHALE; MEDIUM TO DARK BROWN TRANSITIONING TO BUFF TO TAN @ 32'; DAMP, HARD TO VERY HARD, STRONG TO VERY STRONG, CRUSHED TO INTENSELY FRACTURED, NUMEROUS BRECCIA ZONE W/ SILICA CEMENTING THE BRECCIATED PIECES TOGETHER, FINELY LAMINATED, ABUNDANT TAR SEAMS ALONG FRACTURES.	RUN 3 BOX 1				HQ	2:47 PM 5.0'/5.0'	GOOD RETURN FLOW AND CIRCULATION
34									28 mins	
36	CHERTY BROWN		35.0'-40.0': SILICEOUS SHALE; BUFF TO TAN TRANSITIONING TO DARK BROWN @ 36'; DAMP, HARD TO VERY HARD, STRONG, INTENSELY FRACTURED, BRECCIA ZONE FROM 35'-36', FINELY LAMINATED, FEW TAR SEAMS, FEW ELONGATE CLASTS ALONG BEDDING	RUN 4				HQ	3:18 PM 3:34 PM 5.0'/5.0'	
38				BOX 1/2					30 mins	
40									4:04 PM 7:43 AM	END OF DAY 5/23/11, 7:30 AM
42	33' DEP 35' DEP TAR SEAMS		40.0'-45.0': CLAYSTONE; DARK BROWN, MODERATE TO HARD, MODERATELY STRONG, CLOSELY FRACTURED, FINELY LAMINATED, TAR SEAMS ALONG FRACTURES, DISRUPTED/FOLDED BEDDING @ 44'; MODERATELY WELL CEMENTED, SILTY TO SLIGHTLY FINE SANDY, FEW CLASTS ALONG BEDDING	RUN 5 BOX 2				HQ	5.0'/5.0' 19 mins	GOOD CIRCULATION AND RETURN FLOW
44									8:02 AM 8:16 AM	
46	40' DEP 25' DEP 20' DEP TAR SEAMS		45.0'-50.0': CLAYSTONE; DARK BROWN, MODERATE TO HARD (LOCALLY LOW), MODERATELY STRONG (LOCALLY WEAK), CLOSELY FRACTURED (LOCALLY CRUSHED), FINELY LAMINATED W/ DISRUPTED/FOLDED BEDDING @ 46'; MODERATELY WELL CEMENTED, TAR FILLED FRACTURES, FEW CLASTS	RUN 6 BOX 3				HQ	5.0'/5.0'	
48	WEAK CLAY FILM		48.25'-49.25': WEAKER, CRUSHED, CLAYSTONE.						29 mins	
50			49.75': PAPER THIN CLAY FILM, MUSTARD YELLOW GREEN, BRITTLE, PLASTIC, NOT SHEARED.						8:45 AM 9:00 AM	
52	CHERTY 30' DEP		50.0'-55.0': CLAYSTONE; DARK BROWN, MODERATE TO HARD, MODERATELY STRONG, CLOSELY FRACTURED W/ TAR SEAMS ALONG FRACTURES, SILICA CEMENTED W/ CHERTY ZONES AT 51 AND 52', FINELY LAMINATED W/ DISRUPTED/FOLDED BEDDING @ 50.5', FEW CLASTS ALONG BEDDING NEAR END OF RUN.	RUN 7 BOX 3/4				HQ	5.0'/5.0'	
54	28' DEP								20 mins	
56			55.0'-57.5': CLAYSTONE; DARK BROWN, MODERATE TO HARD, MODERATELY STRONG, CLOSELY FRACTURED, SILICA CEMENTED, FINELY LAMINATED, FAULTED/FOLDED BEDS AT 56', FEW TAR FILLED FRACTURES.						9:20 AM 9:38 AM	
58	CRUSHED CLAY FILM MASSIVE LOW HARD		57.5'-58.25': CRUSHED CLAYSTONE, DARK BROWN, WEAK, LOW HARDNESS. CLAYEY FILM ALONG UNEVEN SURFACE @ 58.25', PAPER THIN, MUSTARD YELLOW GREEN.	RUN 8 BOX 4				HQ	5.0'/5.0'	
60	MASSIVE LOW HARD HARDER		58.25'-60.0': MASSIVE CLAYSTONE; DARK BROWN, LOW HARDNESS, WEAK TO MODERATE STRENGTH, LAMINATIONS FAINT TO NONEXISTENT, H ₂ S ODOR.						27 mins	
62			60.0'-60.9': MASSIVE CLAYSTONE; SAME AS ABOVE.						10:05 AM 10:28 AM	
			60.9'-65.0': SILTY CLAYSTONE; TAN TO MEDIUM BROWN, LOW TO MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, FINELY LAMINATED, SLIGHTLY FINE SANDY, INTENSELY TO CLOSELY FRACTURED, ABUNDANT AND LOCALLY THICK TAR SEAMS ALONG FRACTURES.	RUN 9 BOX 4/5				HQ	4.8'/5.0' 18 mins	

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
				RUN 9 BOX 5					10:46AM 11:05AM	GOOD RETURN FLOW/ CIRCULATION
66	CLAY FILM		65.0'-70.0': SILTY CLAYSTONE; ALTERNATING LAMINATIONS OF BUFF/TAN AND MEDIUM AND DARK BROWN, LOW TO MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, CLOSELY FRACTURED. H ₂ S odor.						4.5' 5.0'	66
68	CLASTS 25" DEP		@ 67: 1/8" THICK CLAY FILM, MUSTARD YELLOW GREEN, SOFT, WET, PLASTIC, NO APPARENT SHEARING.	RUN 10 BOX 5				HA		68
70	CLAY FILM		70.0'-75.0': CLAYSTONE w/ BEDDING PARALLEL CLASTS, DARK BROWN w/ TAN/BUFF LAMINATIONS AND/OR CLASTS, LOW TO MODERATE HARD, WEAK TO MODERATE STRENGTH, CLOSELY TO MODERATELY FRACTURED, STRONG H ₂ S odor. @ 74: BEDDING PARALLEL PAPER TO 1/8" THICK CLAY SEAMS, NOT SHEARED BUT VERY PLASTIC AND SLICK, MUSTARD YELLOW GREEN.	RUN 11 BOX 5/6				HA	5.0' 5.0'	70 72
72	GRAY CLAY FILM 25" DEP								17 mins	74
74	CLASTS 20" DEP		75.0'-77.0': SIMILAR TO ABOVE.						11:54AM 12:14PM	76
76			77.0'-80.0': WELL CEMENTED CLAYSTONE; DARK BROWN, LAMINATED, MODERATELY HARD, MODERATELY STRONG, INTENSELY FRACTURED w/ TAR SEAMS, SILICA CEMENTED, FEW 1/2" TO 1/4" CLASTS, SILTY TO FINE SANDY.	RUN 12 BOX 6				HA	5.0' 5.0'	78
78	HARD 25" DEP CRUSHED HARD		@ 77: CRUSHED LIME, LESS CEMENTED CLAYSTONE						17 mins	80
80			80.0'-85.0': SILTY CLAYSTONE; DARK BROWN, LAMINATED, MODERATELY HARD/STRONG, INTENSELY TO CLOSELY FRACTURED, SILICA CEMENTED, FEW CLASTS, SOME FINE SAND.						12:31PM 12:46PM	82
82			@ 81.5': 84': WEAKER CLAYSTONE, CRUSHED.	RUN 13 BOX 6/7				HA	4.4' 5.0'	84
84	WEAK		@ 87.0'-83.5': TECTONICALLY FILLED/FAULTED. SLICKENED SURFACE, SUB HORIZONTAL, WAVY, SHINY, NO CLAY.						19 mins	86
86			85.0'-87.0': CLAYSTONE; DARK BROWN, LOW HARDNESS, WEAK STRENGTH, INTENSELY FRACTURED, FISSILE, BRITTLE.	RUN 14					11:28AM	88
88			87.0'-90.0': TRANSITION TO SANDY SILTY CLAYSTONE, MEDIUM YELLOW BROWN, LOW HARDNESS, WEAK STRENGTH, DAMP, FRIABLE, CRUMBLY, FINE SAND, STRONG H ₂ S odor. BEDDING NOT VERY APPARENT.	BOX 7				HA	4.4' 5.0'	90
90	MED YEL BAN		90.0'-92.5': SIMILAR TO ABOVE. TRANSITIONS FROM MEDIUM YELLOW BROWN TO THINER BROWN, AND LAMINATED.						11:37AM 11:57AM	92
92	MED YEL BAN		92.5'-93.5': WELL CEMENTED CLAYSTONE, MEDIUM BROWN, MODERATELY HARD/STRONG, INTENSELY FRACTURED w/ NUMEROUS TAR SEAMS.	RUN 15 BOX 7				HA	4.0' 5.0'	94
94	CRUSHED HARD HARD		93.5'-95.0': CRUSHED CLAYSTONE TRANSITIONS TO STRIPED BUFF/TAN AND MEDIUM BROWN CLAYSTONE, LOW HARD, MODERATE STRENGTH.						13 mins	96
96	CRUSHED		95.0'-96.0': SAME AS ABOVE.						2:11PM 2:30PM	
			96.0'-96.7': CRUSHED CLAYSTONE, WEAK.							
			96.7'-100.0': SILTY CLAYSTONE, DARK BROWN w/ TAN LAMINATIONS, MODERATE HARD/STRONG, CLOSELY FRACTURED w/ SOME OFFSETS AND	RUN 16 BOX 8				HA	4.7' 5.0'	

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Design.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
100			TAR SEAMS, SILICA CEMENTED	RUN 16 Box 8				HQ	4 1/2 / 50 15 mins 2145 f/m	
102			TD = 100'							
104			3:30 PM: PUMPED BENTONITE/CEMENT GROUT THROUGH THE HQ CORING RODS UP TO THE GROUND SURFACE PER MIX: 30 GALS H ₂ O / 141b BAG CEMENT / 251b BENTONITE.							
106			4:30 PM: PULLED THE DRILL RODS AND CASTING SET 100' OF 2.75" Ø SLOPE INDICATOR INCLINOMETER ON CASTING.							
108										
110										
112										
114										
116										
118										
120										
122										
124										
126										
128										
130										



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay Boring B-5 / SI-5
 Location 1921 ECDLL; DOWNSLOPE OF HEADSCARP Project No. G0058
 Drilling Contractor/Rig Britton Exploration/ CME 550 TRACKED RIG Date of Drilling 5/24/11
 Ground Surface Elev. ~91' Logged By JD Hole Diameter 6" HOLLOW STEM AUGER
 Surface BARE SOIL Weather CLEAR, COOL, BREEZY


Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
0.0 - 4.0			0.0'-4.0': ARTIFICIAL FILL; SILTY CLAY w/ ROCK FRAGMENTS, VERY PLASTIC, DARK BROWN, MOIST, FIRM, FRAGMENTS OF MONTEREY SHALE w/ TAR SEAMS.					HA		DRILLER: PAUL HELPER: SERGIO 8:00AM
4.0 - 100.0			4.0'-100.0': MONTEREY FORMATION				3	MC	12"/18"	2
4.0 - 15.0			4.0'-15.0': SOIL MANTLE/DEEPLY WEATHERED BEDROCK; AS DESCRIBED BELOW.				4			4 HARD GRINDING.
5.0 - 6.5			5.0'-6.5': SANDY SILT w/ CLAY; MEDIUM YELLOW BROWN, DAMP, LOOSE FRIABLE, MORE LIKE SOIL THAN FILL, UNIFORM CONSISTENCY.	1			4	MC	12"/18"	6
10.0 - 11.5			10.0'-11.5': SIMILAR TO ABOVE. MEDIUM DENSE, FINE SANDY SILT, SOIL OR DEEPLY WEATHERED BEDROCK, VERY FAINT BEDROCK TEXTURE, UNIFORM COLOR & COMPOSITION, DAMP.	3			12	MC	16"/18"	10
15.0 - 100.0			15.0'-100.0': MONTEREY FORMATION; AS DESCRIBED BELOW.	2			21			8:35AM
15.0 - 16.5			15.0'-16.5': SILTY CLAYSTONE; BUFF TO TAN w/ YELLOW ORANGE IRON STAINS, DAMP, WELL CEMENTED CLAYSTONE PIECES, THIN LAMINATIONS, HARD, MOD STRONG, DEEPLY WEATHERED.				32	MC	16"/18"	12
20.0 - 21.5			20.0'-21.5': DEEPLY WEATHERED CLAYSTONE; DARK REDDISH BROWN, DAMP, FRIABLE, WEAK, VERY DENSE, WHITE MINERALIZATIONS ALONG LAMINATIONS, THIN TAR SEAMS.				4	MC	12"/18"	14
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				4	MC	12"/18"	16
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			28	MC	10"/18"	18
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	20
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	22
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	24
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	26
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	28
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	30
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	32
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	34
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	36
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	38
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	40
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	42
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	44
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	46
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	48
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	50
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	52
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	54
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	56
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	58
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	60
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	62
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	64
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	66
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	68
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	70
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	72
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	74
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	76
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	78
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	80
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	82
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	84
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	86
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	88
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	90
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	92
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	94
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	96
25.0 - 30.0			25.0'-30.0': SILTY CLAYSTONE; DARK BROWN, DAMP, MODERATE TO HARD, MODERATE STRENGTH, INTENSELY FRACTURED (LOCALLY CRUSHED), NUMEROUS OFFSETS ALONG TAR FILLED FRACTURES, BOX 1, NUMEROUS BEDDING ALIGNED CLASTS, LITTLE TO NO WEATHERING.	4			50/2"	MC	10"/18"	98
25.0 - 26.5			25.0'-26.5': WEATHERED CLAYSTONE; DARK BROWN, DAMP, LOW HARDNESS, WEAK, LAMINATED, FEW CLASTS ALONG BEDDING.				50/5.5'	MC	10"/18"	100

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
			30.0'-35.0': SILTY CLAYSTONE w/ SOME FINE SAND, LAMINATED MEDIUM GREY BROWN AND DARK BROWN w/ 1/2" TO 1" ELONGATE CLASTS ALONG BEDDING, MODERATE TO HARD, MODERATE TO STRONG, INTENSELY TO CLOSELY FRACTURED w/ TAR SEAMS ALONG FRACTURES, SILICA CEMENTED.	RUN 2 BOX 1/2				HA	12:47pm 5.0'/5.0'	GOOD FLUID CIRCULATION
32	25'DEP CLAY FILM									
34	25'DEP		35.0'-36.5': 1/2" THICK MUSTARD YELLOW GREEN PLASTIC CLAY FILM, NO SHEARS APPARENT, BUT SLICK.						20mins	
36	HARD		35.0'-36.5': SIMILAR TO ABOVE, HARD, STRONG, SILICA CEMENTED						1:07pm 1:21pm	
38	DRK BRN		36.5'-39.0': CLAYSTONE, LOW HARDNESS, WEAK STRENGTH, MEDIUM TO DARK BROWN w/ WHITE TO TAN LAMINATIONS/STRINGERS, CLOSELY FRACTURED, BREAKS ALONG BEDDING.	RUN 3 BOX 2				HA	5.0'/5.0'	
40	CRUSHED HARD HARD		39.0'-39.5': CRUSHED CLAYSTONE, MEDIUM GREY BROWN.						15mins	
42	DRK BRN MASSIVE		39.5'-40.0': WELL CEMENTED CLAYSTONE, HARD, STRONG, LAMINATED, TAR SEAMS						1:36pm 1:52pm	
44	CRUSHED HARD OIL HARD		40.0'-41.0': SAME AS ABOVE.							
46	20'DEP		41.0'-43.0': MASSIVE CLAYSTONE; DARK BROWN, LOW HARDNESS, WEAK TO MODERATE STRENGTH, LITTLE FRACTURING, LAMINATIONS NOT APPARENT, STRONG H ₂ S ODOR.	RUN 4 BOX 2/3				HQ	4.9'/5.0'	
48	20'DEP		43.5'-45.0': SILTY CLAYSTONE w/ FINE SAND, MEDIUM BROWN w/ GRAY BROWN INTERBEDS, MODERATE HARDNESS/STRENGTH, INTENSELY FRACTURED w/ TAR SEAMS ALONG FRACTURES.						27mins 2:19pm	
50	20'DEP		45.0'-46.0': SAME AS ABOVE, OIL SHOWN ON SAMPLE						2:34pm	
52	DRK BRN HARD		46.0'-49.0': SILTY CLAYSTONE; MEDIUM BROWN, FINELY LAMINATED, WELL CEMENTED w/ SILICA, MODERATE TO HARD, MODERATE TO STRONG, TRANSITIONS TO BUFF TO TAN, LAMINATED SHALE, HARD, STRONG, CLOSELY FRACTURED, TAR FILLED FRACTURES.	RUN 5 BOX 3				HA	5.0'/5.0'	
54	20'DEP		50.0'-50.8': BUFF/TAN SILICEOUS SHALE AS ABOVE.						2:54pm 3:18pm	
56	30'DEP		50.8'-55.0': SILTY CLAYSTONE; MEDIUM BROWN TO GREY BROWN LAMINATIONS, MODERATE TO HARD, MODERATE TO STRONG, MODERATELY SILICA CEMENTED, NUMEROUS TAR FILLED FRACTURES, INTENSELY FRACTURES.	RUN 6 BOX 3/4				HQ	5.0'/5.0'	
58	20'DEP		55.0'-60.0': THE ENTIRE CORE IS INTACT.						29mins	
60	20'DEP		55.0'-56.0': INTENSELY FRACTURED.						3:47pm 4:02pm	
62	WEAK CRUSHED		56.0'-58.0': SILTY CLAYSTONE; MEDIUM BROWN AND GREY BROWN LAMINATIONS, MODERATE TO STRONG, MODERATE TO HARD, CLOSELY FRACTURED w/ FEW TAR SEAMS. FEW CLASTS ALONG BEDDING MODERATELY SILICA CEMENTED.	RUN 7 BOX 4				HQ	5.0'/5.0'	
			60.0'-65.0': SILTY CLAYSTONE; LAMINATED MEDIUM BROWN AND GREY BROWN, MODERATELY HARD, MODERATELY STRONG, CLOSELY FRACTURED w/ FEW TAR SEAMS, FEW BEDDING ALIGNED CLASTS, MODERATELY SILICA CEMENTED.	RUN 8 BOX 4/5				HQ	5.0'/5.0'	
			61.5'-63.0': CLAYSTONE; DARK BROWN, LOW HARDNESS, WEAK STRENGTH.						38mins	

UNOXIDIZED MONTEREY FORMATION

UNOXIDIZED MONTEREY FORMATION

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recon. (%)	Remarks
66	25' DIP HARD BUFF TAN		65.0'-66.0': SILTCEOUS SHALE; BUFF TO TAN, HARD TO VERY HARD, STRONG, FINELY LAMINATED, INTENSELY FRACTURED.	RUN 8 BOX 5				HQ	58 mins 5:13 PM 5:18 PM	GOOD FLUID CIRCULATION
68			66.0'-70.0': TRANSITIONS TO DARK BROWN, SILTCEOUS SHALE, HARD, STRONG, LOCALLY CONTORTED LAMINATIONS @ 66', INTENSELY FRACTURED.	RUN 9 BOX 5				HQ	4.8' / 5.0'	
70	MED BRN HARD DK BRN HARD		70.0'-71.4': SIMILAR TO ABOVE, CLOSELY FRACTURED.						26 mins 5:54 PM 7:51 AM	END OF DAY 5/25/11, 7:30 AM
72	20' DIP DK BRN MASSIVE		71.4'-74.6': CLAYSTONE; DARK BROWN, MORE MASSIVE, LAMINATIONS ARE NOT APPARENT, LOW HARDNESS, WEAK STRENGTH, CLOSELY TO MODERATELY FRACTURED, UNIFORM COLOR AND COMPOSITION. H ₂ S ODOR.	RUN 10 BOX 5/6				HQ	5.0' / 5.0'	GOOD FLUID CIRCULATION
74			74.6'-76.0': SILTY CLAYSTONE; BUFF TO TAN AND MEDIUM BROWN LAMINATIONS, MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, CLOSELY FRACTURED.						40 mins 8:31 AM 8:49 AM	
76	DE BRN		76.0'-77.0': CLAYSTONE; DARK BROWN W/ TAN CLASTS/STRINGERS ALONG LAMINATIONS, LOW HARDNESS, WEAK STRENGTH.	RUN 11				HQ	5.0' / 5.0'	
78	HARDER		77.0'-80.0': SILTY CLAYSTONE; BUFF TO TAN AND MEDIUM BROWN LAMINATIONS, MODERATE HARDNESS/STRENGTH, LOCALLY WEAK, CLOSELY FRACTURED, FEW TAR FILLED FRACTURES.	BOX 6					20 mins 9:09 AM 9:25 AM	
80	22' DIP		80.0'-85.0': SILTY CLAYSTONE; MEDIUM BROWN AND DARK BROWN LAMINATIONS W/ TAN CLASTS AND STRINGERS ALIGNED W/ BEDDING, LOW TO MODERATE HARDNESS, WEAK TO MODERATE STRENGTH, DAMP, CLOSELY FRACTURED, FEW TAR FILLED FRACTURES.	RUN 12 BOX 7				HQ	4.2' / 5.0'	
82	CLAY FILM		85.0'-90.0': CLAYSTONE; MEDIUM BROWN TRANSITIONING TO DARK BROWN W/ TAN CLASTS AND STRINGERS ALIGNED W/ BEDDING, LOW HARDNESS, WEAK, INTENSELY FRACTURE, STRONG H ₂ S ODOR.	RUN 13				HQ	5.0' / 5.0'	
84	CLAY FILM		90.0'-90.8': SIMILAR TO ABOVE; LOW HARDNESS, WEAK.	BOX 7					17 mins 9:47 AM 9:59 AM	
86			90.8'-93.5': SILTY CLAYSTONE; MEDIUM TO DARK BROWN, FINELY LAMINATED, WELL CEMENTED, MODERATELY HARD/STRONG, TAR FILLED FRACTURES, INTENSELY TO CLOSELY FRACTURED.	RUN 14				HQ	5.0' / 5.0'	
88	20' DIP HARD		93.5'-95.0': 1/8" THICK MUSTARD YELLOW GREEN CLAY SEAM, INCLINED ALONG BEDDING, STIFF, PLASTIC, NOT SHEARED, VERY SLICK. * GOOD SAMPLE	BOX 8					24 mins 10:25 AM 10:41 AM	
90	CLAY FILM		95.0'-98.5': SILTY CLAYSTONE; DARK BROWN, VARIABLY CEMENTED, MODERATE TO HARD, MODERATE TO STRONG, CLOSELY FRACTURED, FEW TAR FILLED FRACTURES, NUMEROUS TAN CLASTS/STRINGERS @ 97.1/8" THICK CLAY SEAM, MUSTARD YELLOW GREEN, STIFF, UNSHEARED.	RUN 15 BOX 6				HQ	5.0' / 5.0'	
92	CLAY FILM								24 mins 11:20 AM	
94	20' DIP HARD								5.0' / 5.0'	
96	CLAY FILM								24 mins	

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Design.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
98.5		210BSP SANDY	98.5'-100.0': FINE SANDY SILT w/ CLAY, MEDIUM YELLOW BROWN, MODERATE HARD/STRONG, MODERATELY WELL CEMENTED, STEEPLY DIPS LAMINATIONS, TECTONICALLY STRATED SHEARS @ 98.8' & 99.1'	RJN15 BOX 6				HQ	5.0% 1.50 Remains 11:40 AM	
100			TD = 100'							100
102			1:05 PM: PUMPED ~ 100 GALS OF BENTONITE/ CEMENT GROUT THROUGH THE DRILL RODS PER MIX: 30 GALS H ₂ O / 94 1/2 BAG CEMENT / 2516 BENTONITE							102
104			2:15 PM: PULLED ALL THE DRILL RODS AND CASING OUT OF THE HOLE AND WET SET 100' OF 2.75" Ø SLOPE INDICATOR QC INCLINOMETER CASING w/ ~ 0.5' STICKUP							104
106										106
108										108
110										110
112										112
114										114
116										116
118										118
120										120
122										122
124										124
126										126
128										128
130										130



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay Boring CSA/LD-2
 Location 1925 ECDILL, 6' WEST OF CSA/B-2 Project No. G0058
 Drilling Contractor/Rig RC DRILLING/LIMITED ACCESS RIG Date of Drilling 10/11/11
 Ground Surface Elev. _____ Logged By SD Hole Diameter 24" Ø AUGER
 Surface BARE SOIL Weather CLEAR, WARM, BREEZY

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
2										12:00PM: START DRILLING W/ 24" Ø AUGER.
4										2 DRILLER: RICHARD HELPER: RICH
6			MONTEREY FORMATION; DEEPLY WEATHERED CLAYSTONE AND SHALE, MEDIUM YELLOW ORANGE, YELLOW BROWN TO DARK BROWN, DAMP TO MOIST, LOW HARDNESS, PLASTIC TO WEAK STRENGTH, HIGHLY FRACTURED, THINLY LAMINATED.							
8			10-11' DARK BROWN CLAYSTONE W/ HARDER WELL CEMENTED SHALE, MOIST TO WET, PLASTIC TO MODERATE STRENGTH.							
10										10-12' MED. YELLOW ORN CLYST, MOIST TO WET, PLASTIC TO LOW HARDNESS, WEAK
12										
14			@14.5' MED YEL BRN/YEL ORN CLYST, MOIST, SLIGHT SMELL OF H ₂ S,							12:15PM: @ 10.5'
16										12:24PM: @ 14.5'
18			@18.5' SPOILS ARE MOIST TO ALMOST WET. MEDIUM TAN TO BROWN CLAYSTONE, VERY PLASTIC, LOW HARDNESS, WEAK STRENGTH.							12:30PM: @ 16' 12:30PM-1:00PM: LUNCH 1:10PM: DRILLING AGAIN
20			@20.0' HARDER DRILLING							1:20PM: @ 18.5'
22			@22.5' DARK REDDISH BROWN CLAYSTONE W/ HARDER FRAGMENTS, WET							1:26PM: @ 20.0' HARDER - DRILLING IS SLOW
24			@23' FREE WATER ON SPOILS							1:33PM: @ 22.5'
26			@25.0' WATER STANDING ON BOTTOM OF HOLE							
28			@26.5' HARDER							1:42PM: @ 25' 1:56PM: @ 26.5' SWITCH TO 12" Ø CORE BARREL 4:05PM: BOH @ 27' WATER @ 13'



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project Felkay Boring CSA/LD-1
 Location 1921 ECDH/8' EAST OF CSA/B-4 (PADRE DR-2) Project No. G0058
 Drilling Contractor/Rig _____ Date of Drilling 10/10/11
 Ground Surface Elev. _____ Logged By SS/SD Hole Diameter ~24"
 Surface _____ Weather _____

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
0.0			0.0 ~ 2.0' LARGE DIAPHRAGM CUTTINGS COMPOSED OF MONTICULI FORMATION CLASTIC/SILTSTONE.							
2			Till From Padre Boring							2
4										4
6										6
8										8
10										10
12										12
14										14
16										16
18										18
20										20
22										22
24										24
26										26
28										28



COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

Project FELAY Boring LD-1
 Location 1921 ECDLL 8 FT EAST OF CSABH (ALLOUGH ANDRE DH-3) Project No. G0058
 Drilling Contractor/Rig PC DRILLING LAR. Date of Drilling 10/10/11
 Ground Surface Elev. _____ Logged By SS/ID Hole Diameter 24 INCHES
 Surface DIRT Weather EARLY AM FOG - CLEARING

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Recov. (%)	Remarks
			<u>FILL (DH-3 BACKFILL)</u> SANDY CLAY; YAL P.A.S, AND PLASTIC, MOIST w/ ANG. GRAVE TO FINE COBBLE CUTS UP MOUNTAIN / SAME							MOB 7:30 - 10:22 AM BEGIN DRILLING 10:27 AM THROUGH PACE DH-3 SPOILS 10:37 AM - 6 FT 10:42 AM - 11 FT 10:54 - 13 FT 11:07 - 19 FT Rock? BOUNDARY SWITCH TO 18" CORE BARREL

COTTON, SHIRES AND ASSOCIATES, INC.

LOG OF EXPLORATORY DRILLING

428,1019

Project FELKAY Boring LD-3
 Location 1921 ECDLL / UPSLOPE OF CSA / B-3 Project No. G0058
 Drilling Contractor/Rig RC DRILLING / LIMITED ACCESS RIG Date of Drilling 10/13/11
 Ground Surface Elev. 92' Logged By SS Hole Diameter 2 FT
 Surface BARE SOIL Weather CLEAR, HOT

Depth (feet)	Graphic Log	USCS Class.	Geotechnical Description	Sample Desig.	Dry Density (pcf)	Moisture Content (%)	SPT Blows/ft	Sample Type	Remarks
0 - 12.4 ft			LANDSLIDE DEPOSITS (REMNANT MONTEREY FORMATION)						BEGIN 9:12 AM WITH AUGER
0 - 0.3 ft			SOIL FORMATION SILTY CLAY, BROWN, DRY, CRUMBLY, ABUNDANT ROOTLETS & ROOTHOLDS; SUBHORIZONTAL CONTACT TO						03': BN 67W, 30SW
0.3 ft - 12.4 ft			SHALE; LT GRAY - YELLOW BROWN - BLK, THINLY BEDDED, SLICED, INTENSELY FRACTURED, WEAK TO MODERATE HARDNESS, ABUNDANT ROOTLETS	B-1				B	9:37 AM
04.5 ft			0.5 FT THICK CLAYSTONE; LT OLIVE-ORANGE BRN, STIFF, MOIST, PUNE TRACER ROOTLETS BELOW 4.5 FT						9:44 AM
05.4 ft			0.5 FT THICK CLAYSTONE; LT OLIVE-ORANGE BRN, STIFF, MOIST, PUNE						06.9': BN 59W, 30SW
06.7 - 6.9 ft			CLAYSTONE; OLIVE BRN, STIFF, MOIST, PLASTIC	BS-1					10:06 AM
07.35 - 7.5 ft			SILTSTONE; LT OLIVE, FRIABLE, MOIST	BS-2					011.3': BN 61W, 25 SW
07.8 - 7.9 ft			SILTSTONE; LT OLIVE, FRIABLE, MOIST	B-2				B	012.4': CONTACT; NG 69W, 25 SW
BELOW 8 ft			SHALE IS BRITTLE						10:23 AM
011.3 ft			0.25 INCH THICK CLAY; BRN, HIGHLY PLASTIC, STIFF, MOIST WITHIN 0.3 FT THICK SILTY CLAY; LT OLIVE, WEAK, SL. MOD. PLASTIC, MOIST TO SLICED SHALE, THINLY BEDDED, MOD. HARD, FRACTURED						013.7': BN 64W, 24 SW
012.1 - 12.4 ft			BASAL LANDSLIDE GOUGE ZONE						10:36 AM
0.3 ft THICK			SILTY CLAY, HIGHLY PLASTIC, OLIVE BRN, FRACTURED, MOIST, ABUNDANT ROOTLETS, ABUNDANT ANGULAR TO TABULAR F-C GRAVEL FRAGMENTS OR SLICED SHALE ENTRAINED IN THIS ZONE WITH MANY ORIENTATIONS						016.5 ft: BN 64W, 27 SW
12.4 ft			B.O.H. - MONTEREY FORMATION						019': BN 70W, 29 SW
SHALE			DE OLIVE BRN, MOD. HARDNESS, MOIST, THINLY BEDDED, BORING IS VERY TIGHT BELOW 12.4 FT DEPTH TO GRN. 5' PETROLEUM FLOW 0.08" BELOW 13 FT						10:49 AM, 11:06 AM SWITCH TO 12 INCH CORE
025 - SEEP ON NE QUADRANT									11:16 AM - ADD 2 GALLONS H ₂ O
026 - SEEP ON SW QUADRANT									021': BN 69W, 25 SW
TOTAL DEPTH = 30 FT; NO CAVING SEEP 2.25 FT									11:40 AM
									12:11 AM - LUNCH TO 1 PM
									2:10 PM - SWITCH TO 24 INCH AUGER
									2:44 PM
									ADD 1 GALLON H ₂ O
									024.5': BN 65W, 28 SW
									SEEP
									3:17 PM
									3:30 PM

LD-1

1"=2'

S ELEVATION 124' N

0.0'-0.2'; ARTIFICIAL FILL;

0.2'-25.4'; MONTEREY FORMATION BEDROCK;

2.0': N10W, 31SW
Bedding

3.0': N25W, 32SW
Bedding

5.0': N43W, 38SW
Bedding

8.0': N65W, 34SW
Bedding

9.5': N55W, 33SW
Bedding

13.0': N25W, 31SW
Bedding

16.0': N54W, 37SW
Bedding

19.0': N54W, 35SW
Bedding

20.0': N45W, 33SW
Bedding

Black, N45W, 33SW

Bag
sample

Weathered shale and claystone; oxidized to pale orange, tan, medium brown and white; this unit is generally weak to moderately strong with localized plastic claystone interbeds, unsheared, damp to moist, closely fractured, well bedded with localized orientation changes due to folding; abundant black tar seams along fractures, fractures are tight; locally hard cemented shale near bottom of borehole.

Average strike of bedding N60W from top of hole,
Deeply weathered, cemented shale, weak, friable, damp to dry
Hard and soft brittle intervals

Deeply weathered claystone, soil-like, moist, well bedded, Fe-stained,
orange, black and gray

Hard brittle shale, cemented, tar seams

Softer, deeply weathered silty claystone, moist, white to orange, rootlets
Hard, N40W, 34SW/ N30W, 33SW

Soft, brown, chalky

Softer, low hardness, weak to moderate strength, oxidized yellow
orange, moist to damp, silty clay, less soil-like

Brittle, hard, strong, highly fractured
Variable hardness, tan, orange to gray

White tan, chalky, softer

Well cemented, hard, brittle

Variable hardness, well cemented to clayey, hard to soft
Low to moderate hardness, tan, white, orange, moist

White, chalky, variable hardness

Harder, stronger shale, well cemented, gray/white

Brown claystone, deeply weathered, medium brown to white-tan/orange,
low hardness, weak, plastic, moist, damp

White, chalky, soft to hard (sample), moist, N50W, 33SW

Hard, black tar seams, brittle

Claystone, thin bedded, orange gray, white, moist, plastic, low hardness,
weak

Gray claystone, plastic, weak, moist
gray/orange/white claystone, silty, weak
white, chalky, soft plastic

Harder, cemented, white, chalky

Silty claystone, plastic, grayish-orange, moist, unsheared

Claystone, soft, plastic, deeply weathered, highly oxidized

Hard, strong, shale, cemented, oxidized, white to orange, moist

Harder, stronger, well cemented shale

Spoils pile

TD=25.4'

No groundwater encountered

Notes:

- LD-1 drilled and logged October 10, 2011
- No groundwater encountered
- Borehole video-taped October 11, 2011
- Borehole backfilled with spoils and compacted with kelly bar.
- Drilling performed by R.C. Drilling, Thousand Oaks, CA



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

Large Diameter Boring LD-1

1921 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY
JW

SCALE
1"=2'

PROJECT NO.
G0058

APPROVED BY
JW

DATE
OCTOBER 2012

FIGURE NO.
B-1

LD-2

1"=2'

0.0'-5.0'; ARTIFICIAL FILL;

Dark brown clay, moist, plastic, firm

Clean sand, fine to medium grained
medium brown to brown, mottled, moist,
little clay binder, medium dense, to loose

Rocky fill, brown, moist, clayey

0.5'-27.6'; MONTEREY FORMATION BEDROCK;

Weathered shale and claystone; oxidized to pale orange, tan, medium brown and white; this unit is generally weak to moderately strong with localized plastic claystone interbeds, unsheared, damp to moist, closely fractured, well bedded with localized orientation changes due to folding; abundant black tar seams along fractures, fractures are tight; locally hard near bottom of borehole.

22° dip
Gray, tan, moist, plastic, claystone
Hard, brittle, fractures

Lots of roots
Raveling
22° dip
Gray/brown claystone, plastic, low hardness, moist
Brittle, hard, intensely fractured

Low hardness, plastic, weak, claystone, orange/brown/gray, moist, deeply weathered
Hard, strong, well cemented, white, fractured

Gray/orange claystone, low hardness, plastic
Hard, brittle
Fat, brown clay
N70W, 40SW on surface, N55W, 29SW average
White, brittle shale, hard, strong, intensely fractured
Gray with laminated claystone, plastic
Claystone, low hardness, weak, orange gray, plastic, moist

Hard, brittle, tan, buff, intensely fractured, N23E, 88NW fractures

Softer, low hardness, rootlets
Brittle, hard, well cemented, intensely fractured, strong

Softer claystone, orange/tan/light gray, moist, plastic, weak

Variable, low to moderate hardness, weak to moderate strength tan to brown

Harder, moderately strong, medium orange/tan/white
Black tar seam, fractures N75E, 70NW, N80E, 60NW
Soft, plastic

Harder, moderately strong shale
Bag sample, soft, plastic, gray/white/orange claystone
Hard, strong shale, laminated, brittle, white and tan/orange, laminations oxidized, closely fractured with tar seam filling, damp to moist

Bag sample, soft, plastic, deeply weathered claystone, white/tan orange/gray, moist, low hardness, gouges easily

Harder

Softer

Water at ~21.2'

Notes:
-LD-2 drilled and logged October 11, 2011
-Groundwater encountered at 21.5'
-Borehole video-taped October 12, 2011
-Borehole backfilled with spoils and compacted with kelly bar.
- Drilling performed by R.C. Drilling, Thousand Oaks, CA



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

Large Diameter Boring LD-2

1925 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY
JW

SCALE
1"=2'

PROJECT NO.
G0058


APPROVED BY
JW

DATE
OCTOBER 2012

FIGURE NO.
B-2

LD-3

S 1"=2' N
ELEVATION 94'



0.0'-12.4'; LANDSLIDE DEBRIS;

0.0'-0.3'; Silty Clay - Dark yellowish brown, dry, roots
0.3'-12.4'; DISRUPTED SHALE; Light gray to yellowish brown, thin-bedded siliceous shale, intensely to closely fractured, friable to weak strength, abundant high-angle open fractures, unstable borehole walls ravel and cave easily; shale is thinly laminated with siltstone and claystone interbeds, consistent bedding 0-12'

4.5'; 6" thick claystone, orange brown, stiff, damp, plastic, rootlets
-Near-vertical high-angle fracture zone with approximate north-south orientation along north and south walls, zone is dilated with abundant open fractures from 1/10" to 1/2", continues for most of 1-12' zone

8.0'-12.0'; Increase in brittle, siliceous shale
11.3'; 1/4" thick clay, brown, highly plastic, stiff, 1/4" thick clay is within 4" thick silty clay interbed

12.0'-12.4'; SHEAR ZONE: BASAL RUPTURE ZONE;

Pulverized shale, clay gouge, soil and roots, 3"-5" thick; shear zone is bedding plane parallel, with planar upper and lower shear boundaries with disrupted rock and soil between, 1/4" to 1/2" thick clay gouge along upper and lower shear boundaries is disrupted and discontinuous, no striae observed; loose pulverized shale between upper and lower shear boundaries, profuse root growth

12.4'-30.0'; MONTEREY FORMATION BEDROCK;

12.4'; Shale - Dark olive brown, moderately strong to strong, thin-bedded, damp, slight petroliferous odor below 13'; rock is very difficult to drill, little fracturing, unoxidized, no caving, rock is tight with consistent bedding to 24' (lower limit of logging)

- Drilling becomes very difficult at 19', using 12" core barrel to pilot drill

25.0'-26.0'; Seeps encountered during drilling

Notes:
-LD-3 drilled and logged October 13 and 14, 2011
-Groundwater first encountered at 25' on October 13 during drilling, stabilized at 26' on October 14, 2011
-Borehole video-taped October 14, 2011
-Borehole backfilled with spoils and compacted with kelly bar.
- Drilling performed by R.C. Drilling, Thousand Oaks, CA



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

Large Diameter Boring LD-3

1925 El Camino De La Luz
Santa Barbara, California

GEO/ENG BY
JW

SCALE
1"=2'

PROJECT NO.
G0058

APPROVED BY
JW

DATE
OCTOBER 2012

FIGURE NO.
B-3

APPENDIX B

LABORATORY TESTING

Table B-1, Summary of Laboratory Test Results

Figure B-1, Summary of Atterberg Limits

Figure B-2, Undrained, Consolidated Triaxial Compression Strength Tests

Figure B-3, Summary of Torsional Ring Shear Tests.

APPENDIX B


LABORATORY TESTING

The laboratory testing program performed by CSA and Cooper Testing Labs of Mountain View, California consisted of testing of the Monterey Formation claystone sampled during the field investigation to evaluate index properties and strength parameters of subsurface materials. Samples used for laboratory testing were obtained either from relatively undisturbed samples (Modified California sampling) from the upper portions of the boreholes, disturbed samples from the mud-rotary drilling (Atterberg limits testing), or bulk samples excavated from the sidewalls of the large-diameter boreholes for samples for disturbed/remolded testing. The rock descriptions and the field and laboratory test results were used to assign parameters to the various materials at the site. The results of the laboratory testing program are presented in this appendix.

The following laboratory tests were performed as part of this investigation:

1. Detailed rock description: ASTM D2487;
2. Natural moisture content of the rock: ASTM D2216;
3. In-situ unit weight of the rock (wet and dry);
4. Atterberg limits determination: ASTM D4318;
5. Unconfined compression: ASTM D2166;
6. Triaxial compression shear strength (consolidated, undrained) ASTM D4767;
and,
7. Remolded torsional ring shear: ASTM D6467.

SUMMARY OF ATTERBERG LIMITS



SAMPLE DESCRIPTION	BORING No./ SAMPLE No.	DEPTH, Ft.	LIQUID LIMIT, %	PLASTICITY INDEX, %	USCS SYMBOL
Silty Claystone; Dark Brown	B-2/Box 1	35.5'-36'	61.0	11.4	MH
Claystone; Dark Brown	B-2/Box 4	66'-67'	57.7	19.7	MH

*Reference: 1995 Annual Book of ASTM
Standards; ASTM Designation D4318:
Standard Test Method for Liquid Limit,
Plastic Limit, and Plasticity Index of Soils

COTTON, SHIRES, & ASSOCIATES, INC.

Atterberg Limits

Project Felkay Proj No. G0058 Location 1925 ECDLL; Above Headscarp


Hole B-2
Sample B-2 Box 1 (35.5'-36') Description of Sample Silty Claystone; Dark Brown

Tested by JN Date of Testing 8/22/2011

	LIQUID LIMIT			
Trial Number	1	2	3	4
Tin Number	9	1	7	16
Weight of Tin	1.61	1.61	1.55	1.64
Number of Blows	7	12	26	42
Tin + Wet Soil	23.95	22.05	19.85	19.65
Tin+ Dry Soil	15.02	14.05	12.95	12.97
Weight Water	8.93	8	6.9	6.68
Weight of Dry Soil	13.41	12.44	11.4	11.33
Moisture Content (%)	66.6	64.3	60.5	59.0

	PLASTIC LIMIT			
Trial Number	1	2	3	4
Tin Number	AA-1	C	n/a	n/a
Weight of Tin	1.59	1.55		
Tin + Wet Soil	6.89	6.87		
Tin+ Dry Soil	5.13	5.11		
Weight Water	1.76	1.76		
Weight of Dry Soil	3.54	3.56		
Moisture Content (%)	49.7	49.4		

LL 61
PL 49.6
PI 11.4



Unified Soil Classification: MH

COTTON, SHIRES, & ASSOCIATES, INC.

Atterberg Limits

Project Felkay Proj No. G0058 Location 1925 ECDLL; Above Headscarp


Hole B-2
Sample B-2 Box 4 (66'-67') Description of Sample Claystone; Dark Brown

Tested by JN Date of Testing 8/22/2011

LIQUID LIMIT				
Trial Number	1	2	3	4
Tin Number	X	17	A-2	V-5
Weight of Tin	1.7	1.58	1.59	1.51
Number of Blows	9	17	30	47
Tin + Wet Soil	21.38	18.73	17.94	13.06
Tin+ Dry Soil	13.88	12.32	11.98	9
Weight Water	7.5	6.41	5.96	4.06
Weight of Dry Soil	12.18	10.74	10.39	7.49
Moisture Content (%)	61.6	59.7	57.4	54.2

PLASTIC LIMIT				
Trial Number	1	2	3	4
Tin Number	HAA	B	n/a	n/a
Weight of Tin	1.59	1.59		
Tin + Wet Soil	5.91	7		
Tin+ Dry Soil	4.72	5.51		
Weight Water	1.19	1.49		
Weight of Dry Soil	3.13	3.92		
Moisture Content (%)	38.0	38.0		

LL 57.7
PL 38.0
PI 19.7



Unified Soil Classification: MH




COTTON, SHIRES & ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS




Drained, Residual Torsional Ring Shear Test ASTM D 6467

Job No.:	026-504	Boring:	LD-2	Date:	11/2/2011	Undisturbed:	
Client:	Cotton, Shires & Associates	Sample:	2	By:	PJ	Peak:	
Project:	Felkay - G0058	Depth:	18.0'	Checked:	DC	Residual:	
Soil Type:	Brown Elastic SILT			Clay, %:	39	Fully Softened:	X
Remarks:	A small friction correction was applied to all points.			LL:	61	Peak:	
Normal Stress, psf	2000	4000	8000	PL:	42	Residual:	X
Secant Phi, deg.	28	28	28				


Secant Residual Friction Angles




Strength Envelope



Deformation Curves



Vertical Deformation







Drained, Residual Torsional Ring Shear Test ASTM D 6467

Job No.:	026-504	Boring:	LD-2	Date:	11/7/2011	Undisturbed:	
Client:	Cotton, Shires & Associates	Sample:	1	By:	PJ	Peak:	
Project:	Felkay - G0058	Depth:	16.5'	Checked:	DC	Residual:	
Soil Type:	Brown Elastic SILT			Clay, %:	39	Fully Softened:	X
Remarks:				LL:	57	Peak:	
				PL:	39	Residual:	X
Normal Stress, psf	2000	4000	8000				
Secant Phi, deg.	25	25	25				


Secant Residual Friction Angles




Strength Envelope



Deformation Curves



Vertical Deformation







Drained, Residual Torsional Ring Shear Test ASTM D 6467

Job No.:	026-504	Boring:	LD-1	Date:	11/7/2011	Undisturbed:	
Client:	Cotton, Shires & Associates	Sample:	3a	By:	PJ	Peak:	
Project:	Felkay - G0058	Depth:	20.0-20.5'	Checked:	DC	Residual:	
Soil Type:	Brown Elastic SILT			Clay, %:	42	Fully Softened:	X
Remarks:	A small friction correction was added to each point.			LL:	68	Peak:	
Normal Stress, psf	2000	4000	8000	PL:	33	Residual:	X
Secant Phi, deg.	15	14	14				


Secant Residual Friction Angles




Strength Envelope





Deformation Curves



Vertical Deformation



LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Brown Elastic SILT	56.9	38.6	18.3	94.0	89.2	MH
■	Brown Elastic SILT	60.6	41.6	19.0	98.3	92.3	MH
▲	Brown Elastic SILT	68.3	32.9	35.4	99.7	98.3	MH

Project No. 026-504

Client: Cotton, Shires & Associates

Project: Felkay - G0058

● Source: LD-2

Sample No.: #1

Elev./Depth: 16.5'

■ Source: LD-2

Sample No.: #2

Elev./Depth: 18.0'

▲ Source: LD-1

Sample No.: #3a

Elev./Depth: 20-20.5'

Remarks:

●
■
▲

LIQUID AND PLASTIC LIMITS TEST REPORT

COOPER TESTING LABORATORY

Figure

The graph illustrates the grain size distribution of a soil sample. The y-axis represents the percentage of soil finer than a given grain size, ranging from 0 to 100. The x-axis represents the grain size in millimeters, on a logarithmic scale from 500 mm to 0.001 mm. The curve shows that the soil is 100% finer than 0.075 mm (No. 200 sieve). The distribution is well-graded, with a significant portion of the soil falling between 0.075 mm and 0.0075 mm (No. 20 and No. 200 sieves).


Grain Size (mm)	Percent Finer (%)
500	100
100	100
60	100
40	100
30	100
20	100
15	100
10	100
7.5	100
6	100
4.75	100
3.75	100
3	100
2.5	100
2	100
1.5	100
1.18	100
0.85	100
0.75	100
0.6	100
0.425	100
0.3	100
0.25	100
0.2	100
0.15	100
0.106	100
0.075	100
0.06	99
0.0475	90
0.0375	85
0.03	80
0.025	71
0.02	65
0.015	58
0.0125	52
0.0106	48
0.0085	43
0.0075	35

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#10	100.0		
#30	99.8		
#40	99.7		
#50	99.6		
#100	99.5		
#200	98.3		
0.0378 mm.	89.3		
0.0272 mm.	85.3		
0.0177 mm.	79.2		
0.0106 mm.	70.7		
0.0077 mm.	64.7		
0.0056 mm.	57.5		
0.0041 mm.	51.8		
0.0029 mm.	47.8		
0.0021 mm.	43.0		
0.0012 mm.	34.8		

<u>Atterberg Limits</u>		
PL= 32.9	LL= 68.3	PI= 35.4
<u>Coefficients</u>		
D ₈₅ = 0.0266	D ₆₀ = 0.0063	D ₅₀ = 0.0035
D ₃₀ =	D ₁₅ =	D ₁₀ =
C _u =	C _c =	
<u>Classification</u>		
USCS= MH	AASHTO=	
<u>Remarks</u>		

Figure

Particle Size Distribution Report



% COBBLES	% GRAVEL	% SAND	% SILT	% CLAY
0.0	1.5	9.3	49.9	39.3

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8 in.	100.0		
#4	98.5		
#10	97.5		
#30	94.5		
#40	94.0		
#50	93.3		
#100	91.9		
#200	89.2		
0.0382 mm.	84.7		
0.0274 mm.	81.3		
0.0179 mm.	74.4		
0.0107 mm.	67.1		
0.0077 mm.	62.8		
0.0056 mm.	56.3		
0.0041 mm.	50.3		
0.0029 mm.	45.9		
0.0021 mm.	40.2		
0.0012 mm.	31.8		

* (no specification provided)

Soil Description
 Brown Elastic SILT

Atterberg Limits
 PL= 38.6 LL= 56.9 PI= 18.3

Coefficients
 D₈₅= 0.0396 D₆₀= 0.0067 D₅₀= 0.0040
 D₃₀= D₁₅= D₁₀=
 C_u= C_c=

Classification
 USCS= MH AASHTO=

Remarks

Sample No.: #1
Location:

Source of Sample: LD-2


Date: 10/26/11
Elev./Depth: 16.5'

COOPER TESTING LABORATORY

Client: Cotton, Shires & Associates
Project: Felkay - G0058
Project No: 026-504

Figure

Particle Size Distribution Report



% COBBLES	% GRAVEL	% SAND	% SILT	% CLAY
0.0	0.0	7.7	53.6	38.7

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#10	100.0		
#30	98.8		
#40	98.3		
#50	97.5		
#100	95.8		
#200	92.3		
0.0382 mm.	86.8		
0.0275 mm.	82.8		
0.0179 mm.	76.2		
0.0107 mm.	68.8		
0.0077 mm.	62.8		
0.0056 mm.	57.2		
0.0041 mm.	51.0		
0.0029 mm.	46.0		
0.0021 mm.	39.7		
0.0012 mm.	31.1		

* (no specification provided)

Soil Description
 Brown Elastic SILT

Atterberg Limits
 PL= 41.6 LL= 60.6 PI= 19.0

Coefficients
 D₈₅= 0.0325 D₆₀= 0.0066 D₅₀= 0.0038
 D₃₀= D₁₅= D₁₀=
 C_u= C_c=

Classification
 USCS= MH AASHTO=

Remarks

Sample No.: #2
Location:

Source of Sample: LD-2



Date: 10/26/11
Elev./Depth: 18.0'

COOPER TESTING LABORATORY

Client: Cotton, Shires & Associates
Project: Felkay - G0058
Project No: 026-504

Figure

Triaxial Consolidated Undrained with Pore Pressure
ASTM D4767



Job No.: 026-498 Date: 9/20/2011

Client: Cotton, Shires & Associate: BY:DC



Project: Felkay - G0058

Sample 1)	B-4:3 @ 9-9.5'	Brown Mottled White SILT
Sample 2)	B-4:4 @ 16-16.5'	Pale Brown SILT Interming w/ Black Gravel
Sample 3)	B-4:6 @ 21-21.5'	Brown Mottled White SILT w/ Sand & Gravel

The pore pressure responded differently by going negative for sample #2. This may indicate that the sample was different from the others in possibly soil type, structure and moisture content.

Sample:	1	2	3	4
MC, %	43.8	37.4	48.4	
DD, pcf	74.3	72.2	71.4	
Sat. %	93.3	75.7	95.9	
Void Ratio	1.268	1.334	1.361	
Diameter in	2.40	2.42	2.40	
Height, in	4.99	5.10	5.02	
Final				
MC, %	43.8	40.0	45.1	
DD, pcf	77.2	81.0	76.0	
Sat. %	100.0	100.0	100.0	
Void Ratio	1.183	1.080	1.218	
Diameter, in	2.37	2.29	2.36	
Height, in	4.92	5.06	4.88	
Cell, psi	73.9	87.8	115.6	
BP, psi	60.1	61.9	59.8	
Effective Stresses At:				
Strain, %	5.0	5.0	5.0	
Deviator ksf	4.820	15.813	7.823	
Excess PP	0.839	0.646	4.721	
Sigma 1	5.974	18.904	11.137	
Sigma 3	1.155	3.090	3.315	
P, ksf	3.565	10.997	7.226	
Q, ksf	2.410	7.907	3.911	
Stress Ratio	5.173	6.117	3.360	
Rate in/min	0.0005	0.0005	0.0005	
Total C	#DIV/0!	ksf		
Total phi	#DIV/0!	degrees		
Eff. C	#DIV/0!	ksf		
Eff. Phi	#DIV/0!	degrees		

Triaxial Consolidated Undrained with Pore Pressure
ASTM D4767



Sample:	1	2	3	4
MC, %	40.2			
DD, pcf	79.5			
Sat. %	97.0			
Void Ratio	1.118			
Diameter in	2.39			
Height, in	5.07			
	Final			
MC, %	39.4			
DD, pcf	81.6			
Sat. %	100.0			
Void Ratio	1.064			
Diameter, in	2.37			
Height, in	5.01			
Cell, psi	87.8			
BP, psi	61.4			
	Effective Stresses At:			
Strain, %	5.0			
Deviator ksf	11.318			
Excess PP	1.412			
Sigma 1	13.713			
Sigma 3	2.394			
P, ksf	8.054			
Q, ksf	5.659			
Stress Ratio	5.727			
Rate in/min	0.0005			
Total C	#DIV/0!	ksf		
Total phi	#DIV/0!	degrees		
Eff. C	#DIV/0!	ksf		
Eff. Phi	#DIV/0!	degrees		

Job No.: 026-498 Date: 9/23/2011

Client: Cotton, Shires & Associate: BY:DC

Project: Felkay - G0058

Sample 1) B-2;MC-5 @ 26-26.5' Pale Brown Sandy CLAY (Silty)

Sample 2)


Sample 3)




Drained, Residual Torsional Ring Shear Test ASTM D 6467

Job No.:	026-498	Boring:	B-5	Date:	9/23/2011	Undisturbed:	
Client:	Cotton Shires & Associates	Sample:	MC-2 & MC-3	By:	PJ	Peak:	
Project:	Felkay - G0058	Depth:	10.5-11.5'	Checked:	DC	Residual:	
Soil Type:	Brown Sandy SILT			Clay, %:	14	Fully Softened:	X
Remarks:	Sample prepared over the #200 sieve. A small friction correction was applied to each point			LL:	17	Peak:	
Normal Stress, psf	2000	4000	8000	PL:	14	Residual:	X
Secant Phi, deg.	32	31	31				


Secant Residual Friction Angles




Strength Envelope




Deformation Curves



Vertical Deformation






Moisture-Density-Porosity Report

Cooper Testing Labs, Inc. (ASTM D 2937)



CTL Job No: 026-498 Project No. G0058 By: RU
Client: Cotton, Shires & Assoc. Date: 09/20/11
Project Name: Felkay Remarks:

Boring:	B-1	B-1	B-5					
Sample:	MC-7	MC-13	MC-1					
Depth, ft:	11-11.5	26-26.5	6-6.5					
Visual Description:	Very Dark Brown Clayey SAND w/ Gravel (Weathered Claystone)	Olive Brown CLAY	Dark Brown Clayey SAND (Silty)					
Actual G_s								
Assumed G_s	2.70	2.70	2.70					
Moisture, %	49.3	43.4	9.9					
Wet Unit wt, pcf	88.9	108.4	114.5					
Dry Unit wt, pcf	59.6	75.6	104.2					
Dry Bulk Dens.pb, (g/cc)	0.95	1.21	1.67					
Saturation, %	72.7	95.2	43.0					
Total Porosity, %	64.7	55.2	38.2					
Volumetric Water Cont., θ_w	47.0	52.5	16.4					
Volumetric Air Cont., θ_a	17.7	2.7	21.8					
Void Ratio	1.83	1.23	0.62					
Series	1	2	3	4	5	6	7	8

Note: All reported parameters are from the as-received sample condition unless otherwise noted. If an assumed specific gravity (G_s) was used then the saturation, porosities, and void ratio should be considered approximate.



LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	Olive Brown Sandy Elastic SILT, trace Gravel	60.2	32.2	28.0			
■	Olive Brown Fat CLAY	74.2	31.5	42.7			
▲	Brown Sandy SILT	17.2	14.1	3.1	95.5	52.6	ML

Project No. 026-498

Client: Cotton, Shires & Associates

Project: Felkay - G0058

● Source: B-1

Sample No.: MC-11

Elev./Depth: 21.0-21.5'

■ Source: B-1

Sample No.: MC-14

Elev./Depth: 25.5-26.0'

▲ Source: B-5

Sample No.: MC-2+MC-3 Elev./Depth: 10.5-11.5'

Remarks:


●
■
▲

LIQUID AND PLASTIC LIMITS TEST REPORT

COOPER TESTING LABORATORY

Figure

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.8	0.3	3.5	42.8	39.0	13.6

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/4"	100.0		
3/8"	99.7		
#4	99.2		
#10	98.9		
#30	97.7		
#40	95.4		
#50	88.1		
#100	64.3		
#200	52.6		
0.045 mm.	42.6		
0.032 mm.	37.9		
0.0212 mm.	31.6		
0.0125 mm.	26.5		
0.0089 mm.	24.2		
0.0064 mm.	20.9		
0.0045 mm.	19.4		
0.0032 mm.	17.0		
0.0023 mm.	14.4		
0.0013 mm.	11.8		

* (no specification provided)

<u>Soil Description</u>		
Brown Sandy SILT		
<u>Atterberg Limits</u>		
PL= 14	LL= 17	PI= 3
<u>Coefficients</u>		
D ₉₀ = 0.3207	D ₈₅ = 0.2717	D ₆₀ = 0.1230
D ₅₀ = 0.0656	D ₃₀ = 0.0186	D ₁₅ = 0.0025
D ₁₀ =	C _u =	C _c =
<u>Classification</u>		
USCS= ML	AASHTO=	
<u>Remarks</u>		

Source of Sample: B-5 Depth: 10.5-11.5'
Sample Number: MC-2+MC-3

Date: 9/16/11


COOPER TESTING LABORATORY

Client: Cotton, Shires & Associates
Project: Felkay - G0058

Project No: 026-498

Figure

SUMMARY OF ATTERBERG LIMITS



SAMPLE DESCRIPTION	BORING No./ SAMPLE No.	DEPTH, Ft.	LIQUID LIMIT, %	PLASTICITY INDEX, %	USCS SYMBOL
Claystone; greyish brown with orange	B-4/Box 1	24'-24.6'	71.3	37.5	CH
Sandy Silty Claystone; medium yellow brown	B-4/Box 7	89'-89.5'	47.6	8.5	ML

*Reference: 1995 Annual Book of ASTM
 Standards; ASTM Designation D4318:
 Standard Test Method for Liquid Limit,
 Plastic Limit, and Plasticity Index of Soils

COTTON, SHIRES, & ASSOCIATES, INC.

Atterberg Limits

Project Felkay Proj No. G0058 Location 1921 ECDLL; Above Headscarp


Hole B-4
Sample B-4 Box 1 (24'-24.6') Description of Sample Claystone; greyish brown with orange

Tested by JN Date of Testing 8/22/2011

LIQUID LIMIT				
Trial Number	1	2	3	4
Tin Number	42	36	L-3	15
Weight of Tin	1.6	1.63	1.68	1.57
Number of Blows	9	13	24	50
Tin + Wet Soil	21.23	20.72	26.04	22.01
Tin+ Dry Soil	12.63	12.52	15.86	13.87
Weight Water	8.6	8.2	10.18	8.14
Weight of Dry Soil	11.03	10.89	14.18	12.3
Moisture Content (%)	78.0	75.3	71.8	66.2

PLASTIC LIMIT				
Trial Number	1	2	3	4
Tin Number	58	51	8	n/a
Weight of Tin	1.61	1.65	1.62	
Tin + Wet Soil	3.6	3.8	4.94	
Tin+ Dry Soil	3.09	3.28	4.08	
Weight Water	0.51	0.52	0.86	
Weight of Dry Soil	1.48	1.63	2.46	
Moisture Content (%)	34.5	31.9	35.0	

LL 71.3
PL 33.8
PI 37.5



Unified Soil Classification: CH

COTTON, SHIRES, & ASSOCIATES, INC.

Atterberg Limits

Project Felkay Proj No. G0058 Location 1921 ECDLL; Above Headscarp


Hole B-4
Sample B-4 Box 7 (89'-89.5') Description of Sample Sandy Silty Claystone; medium yellow brown

Tested by JN Date of Testing 8/22/2011

	LIQUID LIMIT			
Trial Number	1	2	3	4
Tin Number	RA	18	12	13
Weight of Tin	1.6	1.54	1.6	1.57
Number of Blows	11	17	23	28
Tin + Wet Soil	14.96	25.61	28.53	20.3
Tin+ Dry Soil	10.23	17.74	19.69	14.32
Weight Water	4.73	7.87	8.84	5.98
Weight of Dry Soil	8.63	16.2	18.09	12.75
Moisture Content (%)	54.8	48.6	48.9	46.9

	PLASTIC LIMIT			
Trial Number	1	2	3	4
Tin Number	H-5	8	0	n/a
Weight of Tin	1.55	1.51	1.58	
Tin + Wet Soil	5.07	3.65	3.55	
Tin+ Dry Soil	4.04	3.07	3	
Weight Water	1.03	0.58	0.55	
Weight of Dry Soil	2.49	1.56	1.42	
Moisture Content (%)	41.4	37.2	38.7	

LL 47.6
PL 39.1
PI 8.5



Unified Soil Classification: ML

APPENDIX C

INSTRUMENTATION

Summary of Piezometer Data

Summary of Inclinator Data

APPENDIX C

MONITORING

Inclinometers


CSA installed three inclinometers on the parcel, identified as SI-1, SI-2, and SI-3, which have functioned throughout the measurement period and are proposed to remain in place and be periodically monitored through the project regulatory review process. Inclinometer SI-1 is located upslope of the proposed residential envelope and upslope of the 1978 landslide, east of the parcel driveway near elevation 131 feet. SI-2 is located within the proposed residential development envelope and within the headscarp of the 1978 landslide, near elevation 120 feet. SI-3 is located near the downslope edge of the proposed residential development envelope and within the upper portion of the 1978 landslide, near elevation 88 feet. The three inclinometers, with 2.75-inch casing diameter, were installed to near the full depth of small diameter boreholes B-1, B-2, and B-3, to depths of 98 feet in SI-1, 94 feet in SI-2, and 100 feet in SI-3, and were grouted in-place. The inclinometers were installed between May 11 and May 19, 2011, with initial readings taken between May 19 and June 1, 2011. The most recent reading was performed on January 5, 2012. The inclinometer data indicate that there has been no movement, within the statistical accuracy limits of the instruments, either of the hillside above the 1978 landslide or of the 1978 landslide area near SI-3.

Piezometers


CSA installed three piezometers in small-diameter borings B-1, B-2, and B-3, each consisting of 2 vibrating wire piezometer sensors that are used to record in-situ groundwater pore pressures. The piezometers have functioned throughout the measurement period and are proposed to remain in place and be periodically monitored through the project regulatory review process. Two of the piezometers (SI-1 and SI-2) are located upslope of the 1978 landslide debris, and 1 of these piezometers (SI-3) is located with the 1978 landslide debris. Two vibrating wire piezometer sensors were installed in each of the three boreholes, with one at a mid-range depth of between 38 and

45 feet, and one deep sensor between 88 and 93 feet below ground surface. Piezometers were attached to the sides of the inclinometer casing during installation and grouted in place. Water levels were recorded in these instruments (see attached piezometer graphs in this Appendix) between mid-May 2011 and early January 2012. Groundwater levels have experienced little fluctuation during the monitoring period, and generally correspond with the transition from oxidized to unoxidized bedrock between 22 and 35 feet below the ground surface. The deep and shallow sensors reveal groundwater levels nearly at the same respective elevations, indicating that neither artesian conditions nor perched water tables were present at the site during the measurement period.

SI-1, A-Axis



SI-1, B-Axis




1925 El Camino De La Luz
 A+ Direction: S10E
 Top of Casing Elevation=132'

CSA/SI-1




COTTON, SHIRES AND ASSOCIATES, INC.
 CONSULTING ENGINEERS AND GEOLOGISTS


SI-1 Vibrating Wire Piezometers



SI-2, A-Axis



SI-2, B-Axis




1925 El Camino De La Luz
 A+ Direction: S48W
 Top of Casing Elevation=119'

CSA/SI-2




COTTON, SHIRES AND ASSOCIATES, INC.
 CONSULTING ENGINEERS AND GEOLOGISTS


SI-2 Vibrating Wire Piezometers



SI-3, A-Axis



SI-3, B-Axis




1925 El Camino De La Luz
A+ Direction: S38W
Top of Casing Elevation=87'

CSA/SI-3




COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS


SI-3 Vibrating Wire Piezometers



SI-4, A-Axis



SI-4, B-Axis




1921 El Camino De La Luz
A+ Direction: S64W
Top of Casing Elevation=123'

CSA/SI-4




COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

SI-5, A-Axis



SI-5, B-Axis



1921 El Camino De La Luz
A+ Direction: S06W
Top of Casing Elevation=91'

CSA/SI-5



COTTON, SHIRES AND ASSOCIATES, INC.
CONSULTING ENGINEERS AND GEOLOGISTS

APPENDIX D


SLOPE STABILITY ANALYSIS OUTPUT FILES

APPENDIX D


SLOPE STABILITY ANALYSIS OUTPUT FILES

SSA Run #	Slope Condition Analyzed	Lower SP Wall (kips)	Upper SP Wall (kips)	TB (kips)	FS
1	Back-Calculation of existing slide debris surface	N/A	N/A	N/A	1.01
2	Slide debris In place (Critical Surface obtained from post-construction condition Run 5)	N/A	N/A	N/A	2.38
2A	Potential bedding failure with slide debris in place	N/A	N/A	N/A	2.41
3	Same as Run 2, but with slide debris removed (Critical Surface obtained from post-construction condition Run 5)	N/A	N/A	N/A	1.66
3A	Potential bedding failure with slide debris removed (same Critical Surface as Run 2A)	N/A	N/A	N/A	1.96
3B	Deep Block Search with debris removed	N/A	N/A	N/A	1.58
4	Shallow Surface from Run 7, no SP or slide debris	N/A	N/A	N/A	1.39
4A	Same as 4, but with slide debris in place	N/A	N/A	N/A	1.88
5	Critical Deep Surface, post construction of SP walls/ TBs / house loads, slide debris removed downslope of lower SP	40	50	100	1.68
6	Same Critical Surface and construction as Run 5, Seismic with k=0.15	40	50	100	1.23
7	Potential failure through upper shear pin wall (post construction, slide debris removed downslope of lower SP)	40	50	100	2.15
8	Same as Run 7, now with seismic k=0.15	40	50	100	1.24
9	Same as Run 5, with landslide debris in place downslope of lower SP	40	50	100	2.42
10	Same as Run 5, with landslide debris in place downslope of lower SP, now with seismic k=0.15	40	50	100	1.66


Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °




Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °



Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °



Name: Weathered Bedrock Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 ° Phi-Anisotropic Strength Fn.: Phi=45 (weathered)
Name: Unweathered Bedrock Unit Weight: 110 pcf Cohesion: 1 psf Phi: 32 ° C-Anisotropic Strength Fn.: X-bed Cohesion (Unweathered)=2000 Phi-Anisotropic Strength Fn.: Phi=40 (unweathered)
Name: Landslide Debris Unit Weight: 89 pcf Cohesion: 0 psf Phi: 19 °
Name: Af Unit Weight: 105 pcf Cohesion: 0 psf Phi: 25 °



EXPLANATION

Earth Materials

- Qt

Quaternary Terrace Deposits
- Tm

Monterey Formation
- Als

Active Landslide

Map Symbols

- SI-5

Small-diameter boring with inclinometer casing and piezometers installed by Cotton, Shires and Associates, Inc. in May 2011
- LD-3

Large-diameter boring drilled and logged by Cotton, Shires and Associates, Inc. in October 2011
- DH-6

Large-diameter boring drilled by Padre Associates, Inc. in September 2005 (DH-1 and DH-2) and June 2006 (DH-3 through DH-6)
- B-3

Large-diameter boring drilled by Campbell Geo, Inc. in December 2006
- Stratigraphic bedding orientations collected by Cotton, Shires and Associates, Inc.
- Average stratigraphic bedding orientations collected during the logging of large-diameter borings
- Bedding orientation on landslide basal rupture surface collected in large-diameter boring
- 70'

CSA 10' Contour
- CSA 2' Contour
- CSA 10' Contour (Approximate)
- CSA 2' Contour (Approximate)
- CSA Survey Point
- 60


City of Santa Barbara 10' Contour
- City of Santa Barbara 2' Contour
- All Lines of This Color Indicate Features From City of Santa Barbara Map, Including, but not Limited to: Houses, Fences, Roads, Vegetation and Power Poles


SURVEY LIMITATIONS NOTES


1. This is not a map of a boundary survey. No property corners have been set as part of this work.
2. Survey monuments found in the course of this mapping are set by others, and have been used only as a reference for the purpose of topographic mapping, without our verification of their agreement with applicable legal descriptions and seniority of deeds.
3. Relation of topographic features (i.e., fences, walls, trees, power poles, etc.) to property lines as shown on this map is subject to the adjustments that a boundary survey may require.
4. This survey was prepared without the benefit of a Title Report. Easements, if shown, should be considered approximate in location.
5. If this map is provided in an electronic format as a courtesy to client, delivery of the electronic CAD file does not constitute delivery of a professional work product. The signed paper print delivered with this electronic CAD file constitutes our professional work product and, in the event the electronic CAD file is altered, the print must be referred to for the original and correct survey information. We shall not be responsible for any modifications made to the electronic CAD file or for any products derived from the electronic CAD file which are not reviewed, signed and sealed by us.

General Survey Notes

- 1) All dashed lines on this map represent features (houses, walls, topography, etc.) that have not been surveyed by Cotton, Shires and Associates and are approximate only.
2. Vertical Datum for CSA topography based on NOAA published value for mean lower low water (MLLW) in Santa Barbara.
3. City of Santa Barbara topography and features taken from map dated 4/10/95 (Revised April 1997) from County of Santa Barbara website (<http://www.countyofsb.org/pwd/water/TopoFloodControl1.htm>).
4. Southern property lines are based on the MHTL elevation of 4.63 feet above MLLW (MHTL from David Skelly, GeoSoils, Inc., "Wave Runup & Coastal Hazard Analysis, 1921 El Camino de la Luz & 1925 Camino de la Luz, Santa Barbara, Santa Barbara County, California").





 COTTON, SHIRES AND ASSOCIATES, INC. CONSULTING ENGINEERS AND GEOLOGISTS		
Engineering Geologic Cross Section A-A' 1925 El Camino De La Luz APN:045-100-024 SANTA BARBARA, CALIFORNIA		
GEO/ENG BY JD	SCALE 1"= 60'	PROJECT NO. G0058
APPROVED BY JW	DATE OCTOBER 2012	PLATE NO. 2